

STACK

# THE ARCHITECTS' JOURNAL



## standard contents

every issue does not necessarily contain all these contents, but they are the regular features which continually recur.

## NEWS and COMMENT

Diary

News

Astragal's Notes and Topics

Letters

Societies and Institutions

## TECHNICAL SECTION

Information Sheets

Information Centre

Current Technique

Questions and Answers

Prices

The Industry

## PHYSICAL PLANNING

## SUPPLEMENT

## CURRENT BUILDINGS

## HOUSING STATISTICS

Architectural Appointments  
Wanted and Vacant

No. 2953]

[Vol. 114

THE ARCHITECTURAL PRESS  
9, 11 and 13, Queen Anne's Gate, Westminster,  
S.W.1. 'Phone: Whitehall 0611

Price 1s. 0d.


Registered as a Newspaper.

★ A glossary of abbreviations of Government Departments and Societies and Committees of all kinds, together with their full address and telephone numbers. The glossary is published in two parts—A to Ie one week, Ie to Z the next. In all cases where the town is not mentioned the work LONDON is implicit in the address.

AA	Architectural Association, 34/6, Bedford Square, W.C.1.	Museum 0974
AAI	Association of Art Institutions. Secy.: W. Marlborough Whitehead, "Dyneley," Castle Hill Avenue, Berkhamstead, Herts.	
ABS	Architects' Benevolent Society. 66, Portland Place, W.1.	Langham 5721
ABT	Association of Building Technicians. 5, Ashley Place, S.W.1.	Victoria 0447-8
ACGB	Arts Council of Great Britain. 4, St. James' Square, S.W.1.	Whitehall 9737
ADA	Aluminium Development Association. 33, Grosvenor Street, W.1.	Mayfair 7501/8
APRR	Association for Planning and Regional Reconstruction. 34, Gordon Square, W.C.1.	Euston 2158-9
ArchSA	Architectural Students' Association. 34/36, Bedford Square, W.C.1.	
ARCUK	Architects' Registration Council. 68, Portland Place, W.1.	Welbeck 9738
ASB	Architectural Science Board of the Royal Institute of British Architects. 66, Portland Place, W.1.	Langham 5721
AScW	Association of Scientific Workers. 15, Half Moon Street, Piccadilly, W.1.	
BAE	Board of Architectural Education. 66, Portland Place, W.1.	Grosvenor 4761
BATC	Building Apprenticeship and Training Council. Lambeth Bridge House, S.E.1.	Langham 5721
BC	Building Centre. 9, Conduit Street, W.1.	Reliance 7611, Ext. 1706
BCC	British Colour Council. 13, Portman Square, W.1.	Mayfair 8641/6
BCCF	British Cast Concrete Federation. 17, Amherst Road, Ealing, W.13.	Welbeck 4185
BCIRA	British Cast Iron Research Association. Alvechurch, Birmingham.	Perivale 6869
BDA	British Door Association. 10, The Boltons, S.W.10.	Redditch 716
BEDA	British Electrical Development Association. 2, Savoy Hill, W.C.2.	Flaxman 7766
BIA	British Ironfounders' Association. 145, Vincent Street, Glasgow, C.2.	Temple Bar 9434
BIAE	British Institute of Adult Education. 29, Tavistock Square, W.C.1.	Glasgow Central 2891
BID	Building Industries Distributors. 52, High Holborn, W.C.1.	Euston 5385
BINC	Building Industries National Council. 11, Weymouth Street, W.1.	Chancery 7772
BOT	Board of Trade. Millbank, S.W.1.	Langham 2785
BRB	Building Research Station. Bucknalls Lane, Watford.	Whitehall 5140
BSA	Building Societies Association. 14, Park Street, W.1.	Garston 2246
BSI	British Standards Institution. 28, Victoria Street, S.W.1.	Mayfair 0515
BTE	Building Trades Exhibition. 4, Vernon Place, W.C.1.	Abbey 3333
CABAS	City and Borough Architects Society. C/o Johnson Blackett, F.R.I.B.A., Borough Architect, Town Hall, Newport, Mon.	Holborn 8146/7
CAS	County Architects Society. C/o F. R. Steele, F.R.I.B.A., County Hall, Chichester.	Newport 3111
CCA	Cement and Concrete Association. 52, Grosvenor Gardens, S.W.1.	Chichester 3001
CCP	Council for Codes of Practice. Lambeth Bridge House, S.E.1.	Sloane 5255
CDA	Copper Development Association. Kendalls Hall, Radlett, Herts.	Reliance 7611
CIAM	Congrès Internationaux d'Architecture Moderne. Doldental, 7, Zurich, Switzerland.	Radlett 5616
COID	Council of Industrial Design. Tilbury House, Petty France, S.W.1.	Whitehall 6322
CPRE	Council for the Preservation of Rural England. 4, Hobart Place, S.W.	Sloane 4280
CUJC	Coal Utilization Joint Council. 3, Upper Belgrave Street, London, S.W.1.	
CVE	Council for Visual Education. 13, Suffolk Street, Haymarket, S.W.1.	Sloane 9116
DGW	Directorate General of Works, Ministry of Works, Lambeth Bridge House, S.E.1.	Reading 72255
DIA	Design and Industries Association. 13, Suffolk Street, S.W.1.	Reliance 7611
DOT	Department of Overseas Trade. 35, Old Queen Street, S.W.1.	Whitehall 0540
EJMA	English Joinery Manufacturers' Association (Incorporated). Sackville House, 40, Piccadilly, W.1.	Victoria 9040
EPNS	English Place-Name Society. 7, Selwyn Gardens, Cambridge.	Regent 4448
FAS	Faculty of Architects and Surveyors. 8, Buckingham Palace Gdns., S.W.1.	
FASSC	Federation of Association of Specialists and Sub-Contractors, 5, Arundel Street, Strand.	Sloane 2837
FBI	Federation of British Industries. 21, Tothill Street, S.W.1.	Temple Bar 6633
FC	Forestry Commission. 25, Savile Row, W.1.	Whitehall 6711
FCMI	Federation of Coated Macadam Industries. 37, Chester Square, S.W.1.	Sloane 1002
FDMA	The Flush Door Manufacturers Association Ltd. Trowell, Nottingham.	Ilkeston 623
FLD	Friends of the Lake District. Pennington House, nr. Ulverston, Lancs.	
FMB	Federation of Master Builders. 26, Great Ormond Street, Holborn, W.C.1.	Ulverston 201
FOB 1951	Festival of Britain 1951. 2, Savoy Court, Strand, W.C.2.	W.C.1.
FPC	The Federation of Painting Contractors, St. Stephen's House, S.W.1.	Chancery 7583
FRHB	Federation of Registered House Builders. 82, New Cavendish Street, W.1.	Waterloo 1951
FS (Eng.)	Faculty of Surveyors of England. Buckingham Palace Gdns., S.W.1.	Whitehall 3902
GC	Gas Council. 1, Grosvenor Place, S.W.1.	Langham 4041
GG	Georgian Group. 27, Grosvenor Place, S.W.1.	
HC	Housing Centre. 13, Suffolk Street, Pall Mall, S.W.1.	Sloane 5615
IAAS	Incorporated Association of Architects and Surveyors. 75, Eaton Place, S.W.1.	Sloane 6186
ICA	Institute of Contemporary Arts. 17-18 Dover Street, Piccadilly, W.1.	Whitehall 4577
ICE	Institution of Civil Engineers. Great George Street, S.W.1.	Temple Bar 7676
IEE	Institution of Electrical Engineers. Savoy Place, W.C.2.	Abbey 5215
IES	Illuminating Engineering Society. 32, Victoria Street, S.W.1.	



"PERMAVENT"  
LARDER LIGHT  
TYPE MBS



"PERMAVENT"  
NON-CONDENSATING  
SKYLIGHT

# GREENWOOD'S

## 'PERMAVENT' ALL-STEEL LARDER LIGHTS VENTI-LIGHTS AND SKYLIGHTS

### DAYLIGHT AND PERMANENT VENTILATION COMBINED

Greenwood's "Permavent" all-steel larder lights and venti-lights provide vision with permanent ventilation and are equipped with multi-louvred ventilating panels backed by detachable insect-proof screens. Strong and durable, they are delivered unglazed ready for building in.

"Permavent" non-condensating skylights supplied in galvanised steel or copper, unglazed and ready for fixing.

Particulars of sizes, types and prices upon application.



"PERMAVENT"  
VENTI-LIGHT  
TYPE VAS

**GREENWOOD'S AND AIRVAC**  
*Ventilating Company Limited*  
BEACON HOUSE CHANCERY BUILDING KING'S WAY AIRVAC LONDON W.C.2

## CORK, THE FLOOR THAT'S HALF AIR

is not only QUIET, WARM, LUXURIOUS  
but TOUGH, LONG-LASTING, ECONOMICAL

**C**ORK, most luxurious of floors, with the air-cellular structure that kills noise, has long been the architect's first choice where silence is essential, or comfort more important than cost.

But this resilient material, more than half air, is also exceedingly *tough*. It stands years of heavy foot traffic in busy shops, offices, hospitals, schools, restaurants, even in buses, with scarcely perceptible wear. In domestic use, it may well last a lifetime.

So cork is truly *economical*—far more so, when you count the years, than 'cheaper' floors that can never give the same satisfaction. Even first cost is competitive, normally lower than for wood blocks. And with this warm, quiet surface there is far less need for carpeting.

### PURE CORK IN TILE FORM

Armstrong's Cork Tiles, famous since 1896, are made of nothing but pure, resilient Spanish cork, bonded under heat by its own resins—no dust or gritty granules, no adulterant. A special feature of Armstrong's Cork Tiles is that they are supplied not only straight-edged but also tongued and grooved, which obviates sanding after laying and prevents lipping and curling. You are invited to write for further particulars.

### ARMSTRONG'S CORK TILE FLOORING

ARMSTRONG CORK COMPANY LTD., FLOORING DEPARTMENT,  
BUSH HOUSE, ALDWYCH, LONDON W.C.2  
Telephone: Chancery 6281

SCOTTISH BRANCH:  
5 OSWALD STREET, GLASGOW C.1  
Telephone: Central 5703





S

ITS  
ITS

ION


ights  
nent  
are  
multi-  
panels  
able  
ens.  
they  
azed

on-  
ights  
steel  
and

ypes  
tion.



# THE COBURN SYSTEM



## Sliding Door Gear

Specify the original and best  
sliding door gear for all your  
future jobs.


*Cold rolled steel tracks  
Best grey cast-iron brackets  
Maintenance-free trolleys*

Write for drawings, catalogue  
and advice.

Obtainable from all Builders' Merchants

TELEPHONE: TELEGRAMS:  
WATERLOO 4311 TROLTRACK, SEDIST,  
(3 lines) LONDON

*The* **BRITISH TROLLEY TRACK CO**  
**COBURN WORKS, COPPERFIELD STREET**  
**LONDON. S.E.1**



## HARCO RIBBON WIRE


The artistic effect of Harco Ribbon Wire renders it particularly suitable for use where care of design and appointment are of major importance. Architects will appreciate that it not only screens the unsightly, but allows free circulation of air. The patterns in which Ribbon Wire can be woven, make it the perfect selection for Lift Shaft Enclosures, Ventilating Panels, Radiator Covers, Electric Heater Covers, etc. Illustration shows Pattern No. 1376 W. Other Patterns and full particulars in Catalogue AJ 744.

**Harvey**

**G. A. Harvey & Co. (London) Ltd. Woolwich Road, London. S.E.7**



# Keep workers warm



## fit "INSULIGHT" double-glazing units

Workers can have more warmth and comfort from improved thermal insulation, when "INSULIGHT" double-glazing units are used. These units reduce heat losses, and thus cut heating costs. Used in conjunction with air-conditioning plant, the load is reduced and power saved, and the initial capital

cost is less. The hermetically sealed dry air in the space between the two glasses of the units restricts condensation and keeps the inside surfaces free from dirt. There are still only two surfaces to clean. The units can be fitted without difficulty.

*Send for the booklet about their advantages and the methods of fixing.*

Consult the Technical Sales and Service Department at St. Helens, Lancs., or Selwyn House, Cleveland Row, St. James's, S.W.1    Telephones: St. Helens 4001; Whitehall 5672-6.    *Supplies are available through the usual trade channels.*



### PILKINGTON BROTHERS LIMITED

*"INSULIGHT" is the British registered trade mark of Pilkington Brothers Limited*

s's,  
els.

**D**  
ited








AND BY APPOINTMENT  
TO HIS LATE MAJESTY  
KING GEORGE V

# MANDER'S

## DURABLE GLOSS

FOR INSIDE AND  
OUTSIDE WORK

MANDER BROTHERS LIMITED  
WOLVERHAMPTON



36—38 Berkeley Square, London, W.1.

Architects: Howard Couster & Partners

Consulting Engineers: G. A. Dodd & Partners

# DAWNAYS LIMITED


## BRIDGE AND STRUCTURAL ENGINEERS

HEAD OFFICE: STEELWORKS RD., LONDON, S.W.11: Telephone BATTERSEA 2525.

King's Dock Works SWANSEA 3185	East Moors Works CARDIFF 2557	56 Victoria St., London, S.W.1 VICTORIA 1541	Bridge Rd. Works WELWYN GDN. 242	Thorp Works NORWICH
2 Rockstone Place SOUTHAMPTON 2474	40 Park Road PETERBOROUGH 4547	155 Princes Avenue, HULL HULL, CENTRAL 8161	22 High Street ROMFORD 2106	7 The Close NORWICH 23141

Cables and Telegrams: "DAWNAYS, LONDON"—Code Bentley's 2nd.

# An important **BITUMETAL** announcement



*Come and visit our  
STAND No. 32-33  
Row B at the  
BUILDING EXHIBITION  
Olympia  
You will see the latest  
developments in roofings*

**S**INCE its inception a few years ago, 'BITUMETAL' has rapidly acquired the confidence of Architects and Engineers in many parts of the country. At no time, however, can it be said that finality has been reached in the presentation of a product or service. Our Roofing Development Department is constantly carrying out research into conditions affecting application and purpose, and recently it was observed that an aluminium sheet of 18 gauge fabricated into such a substantial unit provided in many instances a greater load-bearing capacity than was strictly necessary. We therefore introduced 20 gauge 'BITUMETAL' Roof Deck eminently suitable for many classes of

buildings, and at the same time, economical in the use of aluminium. Deck units of 18 gauge are still being produced for high load-bearing capacities, but generally it will be found that 20 gauge units will meet your requirements and at a considerably reduced price.

Full technical data of this important change is available at any of the undernoted Area Offices.

## **WILLIAM BRIGGS & SONS LTD**

DUNDEE 'Phone: 82211 (10 lines)

LONDON Vauxhall Grove, S.W.8. 'Phone: Reliance 2214/5 and 1451/2

ABERDEEN  
Bedford Road. 'Phone: 43391

EDINBURGH, 12  
Murrayfield Station  
'Phone: 61233

LEICESTER  
Belgrave Road Station  
'P. one: 60306

NORWICH Trowse Millgate. 'Phone: 26863

BRISTOL 3  
Stillhouse Lane, Bedminster  
'Phone: Bristol 64147

GLASGOW, C.3  
200 Old Dumbarton Road  
'Phone: Western 3001/2

LIVERPOOL  
Kirkby Trading Estate  
'Phone: Simonswood 3266/7



**ROOF PLUS CEILING PLUS INSULATION**






## Your timber problems solved

**S**HORTAGE of timber is a major housing problem. The answer is ready. Hills Standard "Presweld" Roof and Floor Beams for houses have become an essential part of modern building practice—specified by Architects and Builders and approved by the Ministry of Works. In addition to saving timber for other uses, these maximum-strength, minimum-weight components can be assembled and erected by semi-skilled operatives, thus saving time and labour

on site. Early delivery can be given on Beams ordered now. Full details on request.



# HILLS

(WEST BROMWICH) LIMITED

ALBION ROAD, WEST BROMWICH.  
125 HIGH HOLBORN, LONDON, W.C.1.

'Phone : WEST Bromwich 1025 (7 lines)  
Phone : HOLborn 8005-6

★ Branches at London, Birmingham, Swansea, Bristol, Manchester, Newcastle-on-Tyne, Glasgow and Belfast.

BIRMINGHAM OFFICE : 36 CANNON ST. Phone : MIDland 5175

Hilton



*The Sandstorm machine illustrated produces the pleasing sandfaced appearance which is associated with Dignus roofing tiles.*

*Rhyl U.D.C. Housing Estate roofed with Dignus Sandstorm Tiles.*



## 11×7 *plus*


The Dignus famous 11" × 7" patented Sandstorm roofing tiles are made by forcing sand at a velocity of 1,740 m.p.h. against the tile face. The sand penetrates the surface of the tile and forms the extremely tough, durable surface for which they are renowned. This process is but one of the many advantages that we offer and others are fully described in our brochure. May we send you a copy?



# DIGNUS

**SANDSTORM** *Tiles*

DIGNUS LIMITED, KEELE, NEWCASTLE, STAFFS



**I**N hotels, flats, private homes and offices; in hospitals, schools, public and factory buildings, MURAC gives a finish to walls that is quickly and economically applied, beautiful to see, easy to clean and *long lasting!*

#### MURAC SUPERSEDES DISTEMPER & WATER PAINT

Here's a matt oil paint as easy to put on as distemper, using a 6" flat wall brush. What a saving in labour costs alone! MURAC dries with a beautiful dull sheen, and its surface is so hard that not only can it be rubbed and scrubbed again and again, but it is also hygienic and impenetrable to dirt. MURAC is long-lasting, won't powder or flake, and comes in eighteen basic colours, easily blended to any shade you could want. It is made in the Brolac works by John Hall & Sons Ltd., who will gladly send you a **free colour scheme booklet** if you will write to them at the address below.

**YOU CAN  
WASH IT, RUB IT, SCRUB IT!**



# MURAC

MATT OIL FINISH FOR WALLS

JOHN HALL & SONS (BRISTOL & LONDON) LIMITED, HENGROVE, BRISTOL, 4









## The Advantages of

# "PHARAON" GYPSUM BROWNING PLASTER

Manufactured specifically to provide an economical labour-saving rendering or floating coat on high suction surfaces, such as **BRICK, STONE, CLAY TILES, PUMICE SLABS, etc.**

The modern method of plastering is to use Gypsum Plasters for undercoats rather than other materials which shrink when drying. The fact that Gypsum Plasters do not shrink is an important feature; their use eliminates the risk of shrinkage cracks in the finished work. It will be appreciated that it is an advantage that the base and finish coats should have the same chemical characteristics. By using Gypsum Plasters for both, the work is greatly speeded because succeeding coats can be applied on the same day.

**MOISTURE.** Gypsum Plaster combines chemically with a considerable proportion of the water used for gauging, so that where

Gypsum Plaster is used there is less moisture to dry out into the building.

**POROSITY.** A noticeable characteristic of Gypsum Plaster. In effect the plaster breathes so that when moisture condenses on the plastered surface it is absorbed and the damaging effects of condensation are obviated.

**COST.** Whilst initial costs may be slightly greater than where the cheapest materials are used, an increasing number of experts are, day by day, becoming convinced that the small extra cost per house

is more than offset by the increase in speed of erection and the savings in maintenance charges.



## OTHER GRADES OF "PHARAON" GYPSUM PLASTERS

**"PHARAON" Special Haired Plaster.** For rendering and floating on metal lathing, or on Gypsum plasterboards, wood lathing, concrete and other low suction surfaces.

**"PHARAON" Gypsum Wall Finish Plaster.** For high grade setting coats where a superior finish is desired. Applied neat it provides a surface to which the most delicate decorations can be safely applied.

## ALL "PHARAON" PLASTERS ARE MANUFACTURED FROM GYPSUM ROCK AND ARE THUS HIGHLY RESISTANT TO FIRE

**SERVICE.** Research and testing laboratories are maintained for the assistance of Architects, Building and Plastering Contractors, on all matters relating to the use of the Company's products. This service includes the testing of sands intended for use with Gypsum Plasters, and we recommend, whenever possible, samples of sand should be submitted. Suitable specifications for all classes of plastering will be gladly submitted on request.

We shall be pleased to see you on  
STAND 94, ROW E, BUILDING TRADES EXHIBITION, OLYMPIA.


## THE BRITISH PLASTER BOARD LIMITED

SOUTHERN SALES OFFICE  
MORRIS HOUSE,  
1-5 JERMYN STREET, LONDON, S.W.1.  
Telephone: Whitehall 9821



NORTHERN SALES OFFICE  
BIRKENHEAD ROAD,  
WALLASEY, CHESHIRE  
Telephone: Birkenhead 4411

## SPECIALITY FLOORS FOR POWER




PRODORITE TILING AT A NORTHERN POWER STATION

Head Office: Eagle Works  
WEDNESBURY STAFFS.  
Telephone: London Office: (244 13 lines)  
ARTILLERY HOUSE  
ARTILLERY ROW S.W.1  
Telegrams: ABBEY 2016 (3 lines)



PRODORITE FLOORS ARE  
STANDING THE TEST  
IN BRITAIN'S DRIVE FOR MORE POWER



9" x 9" BUFF TILES AT A SOUTHERN POWER STATION

In HOUSE...



HOTEL...



or HOSPITAL...



## Sissons Sinks are JUST what the ARCHITECT ordered!



Illustrated here—solely by way of example—is one of the many typical catering units produced by Sissons for specific purposes. Other units incorporate different features and furnish varying combinations of bowls and drainers. Alternative methods of support are also available.



Workers in Metal since 1784

WITH EVER-GROWING EMPHASIS being placed on the need for careful kitchen and washroom planning, more and more architects are specifying "stainless steel sinks by Sissons." They find that, whatever the scheme, Sissons supply *exactly* what's wanted. A wide range of standard models, covering a host of different purposes, is available; but Sissons also *specialise* in manufacturing sinks to customers' specifications. Whether you're building a house, hotel, or hospital, Sissons sinks can be made to suit your plans. Write to-day for descriptive literature.

Models may be seen at the Building Centre, Conduit St., London, W.1

**SISSENS**

STAINLESS STEEL SINKS

W. & G. SISSENS LTD., ST. MARY'S ROAD, SHEFFIELD

## Air-lift for "KISOL"

*Vermiculite*



200 bags of "KISOL" ready to leave Ringway Airport, Manchester for I.O.M.

200 bags of "KISOL" Vermiculite—a total of 700 cu. ft., weighing only 25 cwt., were recently flown from Manchester to the Isle of Man in this light freighter. This is indeed evidence of the exceptional lightness of "KISOL", and its usefulness to the architect and builder in providing a versatile insulating material of great advantage in building construction, solving many building problems such as reducing the dead-weight load on structures.

At Ronaldsway Airport I.O.M., "KISOL" Vermiculite concrete was used to insulate the whole of the roof—for one inch of "KISOL" has the equivalent insulating value of 15 inches of ordinary concrete.



Roof of Ronaldsway Airport, I.O.M. screeded with "KISOL" Vermiculite.




"KISOL" Vermiculite Concrete is esteemed by architects and builders because its absence of joints and low temperature-movement make it an ideal base for final waterproofing.

See our Display at the Building Trades Exhibition, Olympia, London.

**WILLIAM KENYON & SONS LIMITED**  
DUKINFIELD      INSULATION ENGINEERS      CHESHIRE



*Hear the Wireman*



**“You’ll  
hardly notice  
my handiwork!”**

“The wireman’s art is by no means limited to the technical aspect of the work. The final appearance of the finished job is just as much a matter of pride as its efficient operation.

SAYS JACK GRIFFIN OF BRISTOL

All wiremen receive intensive training and are taught particularly to make their handiwork as unobtrusive as possible, so that it blends with the background and passes unnoticed.”

*Sound Service by*  
**REDIFFUSION**

*Bristol is one of over 100 towns and cities in the United Kingdom where Rediffusion operates.  
May we send you full particulars of the Rediffusion Service for local communities?*

CENTRAL REDIFFUSION SERVICES LIMITED, CARLTON HOUSE, LOWER REGENT STREET  
LONDON, S.W.1

TELEPHONE: WHITEHALL 0221/30



By courtesy of Messrs. Ind Coope & Allsopp Ltd.

## **FESTIVAL INN** DORSET RD., LAMBETH.

The Saloon Bar (illustrated above) has a counter front with square reeded panels, broken by shaped pilasters. The counter top is in solid oak with a moulded front edge. The backfitting is mirrored, with eight shelf divisions above. The beer engine is a 4-pull Standard Dalex. G. & C. are also responsible for the attractive Lounge and Public Bars, all the beer-raising equipment and the fixed seating.

**BARS BY**  *of course*

**BRITAIN'S BIGGEST BAR FITTERS**

*Member of the Allied Brewery Traders' Association*

- **HEAD OFFICE :** DALEX WORKS, COLESHILL ST., BIRMINGHAM, 4. **London Office :** 109-115 Blackfriars Road, S.E.1
- **Branches :** Bristol, Cardiff, Leeds, Portsmouth, Manchester, Liverpool, Preston, Newcastle-on-Tyne, Hanley, Sheffield, Nottingham, Glasgow, Edinburgh



Architect: A. Glyn Sherwin, Esq., M.Inst. R.A., F.F.A.S., B.E. M.Inst.

The vestibule of the Longton Branch of Martin's Bank Limited executed under the direction of A. Glyn Sherwin, Esq., M.Inst. R.A., F.F.A.S., M. Inst. B.E. The Main Counter, Interior Fittings and Furniture are in Australian Walnut.

## **BATH CABINET MAKERS AND ARTCRAFT LIMITED**

### **CONTRACTORS FOR MODERN INTERIORS**

Enquiries are invited from Architects interested in the furnishing of Public Buildings, Offices, Hotels, Ships, and Private Houses.

LOWER BRISTOL RD., BATH, Tel.: Bath 7214-5      London Showrooms: 1 GRAFTON ST., W.I. Tel.: Regent 4671

*"Count them as they catch your eye"*



**3 GAS WORKS**

**SANDERS  
"SUPERIOR"**

The Gas Industry's Electrical Engineer has special problems to face, associated with corrosive atmosphere, situation of equipment, and operation for twenty four hours of the day, seven days a week.

It is significant that much of his equipment bears the encircled **S** and super-  
scription which marks the Sanders  
Superior Switch, a switch which for  
roughly thirty years has been noted  
for its complete electrical and mechan-  
ical reliability, under the worst possible  
conditions.

Count them as they catch your eye.

*Comprehensive stocks are  
carried by selected wholesalers  
in all large centres of population*



**SANDERS  
WEDNESBURY**



**WM. SANDERS & CO. (WEDNESBURY) LTD., WEDNESBURY, STAFFS.**



**IT MAY  
APPEAR  
ABSURD!!!**

**but you can  
concrete below 25° frost**

Important constructional work and housing must continue in frosty weather. Sealocrete Double Strength Premix Solution provides *the maximum safety available*. Even for cement mortar for brickwork and cement renderings, the setting time of the cement mortar or cement rendering is accelerated with the object of enabling it to be set before the frost can get it. You can continue work under any conditions—and finish it in the shortest possible time.

**DO NOT DELAY YOUR WORK, SPECIFY SEALOCRETE  
DOUBLE STRENGTH PREMIX SOLUTION TO BE  
INCORPORATED IN THE GAUGING WATER.**



**by using SEALOCRETE**  
DOUBLE STRENGTH PREMIX SOLUTION

Sole Manufacturers:

**SEALOCRETE PRODUCTS LTD., ATLANTIC WORKS, HYTHE ROAD, LONDON, N.W.10**

Telephone: LADbroke 0015 0016 0017


Telegrams: Exploiture, Wesphone, London



# the **ASCOS** nursery school *or day nursery*



**ERECTION PERIOD 4 MONTHS**



## **TIME IS MONEY!**

The ASCOS school saves money in erection time. It also effects a substantial saving by its simplified plan and construction. It reduces the cost without sacrificing essentials in conception or construction, providing 1000 sq. ft. of playroom space per unit of 40 children. The amenities are excellent for children, teaching and kitchen staff. All this it does—in an environment in which the children feel at complete ease. For these good reasons and many others, the ASCOS is deservedly popular.

An illustrated booklet on construction, features, finish and services will be sent you on request.

## **ANGLO-SCOTTISH**


CONSTRUCTION COMPANY LTD

No. 1 THE RIDGWAY, LONDON, S.W.19.

Telephone: WIMbledon 5277/8/9

T.A. 4100

*in two places at once . . .*



One of the many advantages of erecting a steel-framed building is the fact that the fabrication of the steelwork can proceed at the same time as the site is being cleared and prepared. This arrangement of "getting on with the job" in two places at once is regularly put into effect, with obvious economies, on projects where the signboard reads—BOOTH STEELWORK



## BOOTH STEELWORK

Structural Steelwork—Steel  
Rolling Shutters & Fireproof  
Doors—Welded Steel Tanks—  
Steel and Glass Partitions

JOHN BOOTH & SONS (BOLTON) LTD., HULTON STEELWORKS, BOLTON


Telephone 1195

LONDON: 26, VICTORIA ST., WESTMINSTER, S.W.1.

Telephone ABBEY 7162







**LONGEVITY.** Marley Tiles are covered by a Guarantee for fifty years against lamination and decay. The Guarantee also covers the full maintenance of the roof tiling for a period of ten years when the tiling is carried out by Marley.



*The Marley Tile Company Limited, London Road, Riverhead, Kent. Sevenoaks 2251/6*

**MARLEY**





***Building and Civil Engineering Contractors***  
FOR THE FESTIVAL OF BRITAIN 1951 EXHIBITION  
AND FOR THE

L.C.C. SOUTH BANK RECONSTRUCTION SCHEME,  
COMPLETED THREE MONTHS AHEAD OF SCHEDULE

HEAD OFFICE:

DOLPHIN SQUARE, LONDON, S.W.1      Victoria 6624


BRANCHES:

TURKEY • MIDDLE EAST • RHODESIA • UGANDA • NIGERIA

*Richard*

**COSTAIN**

*Limited*



Boiler house for New Classroom Block, Twickenham Technical College. County Architect : C. G. Stillman, F.R.I.B.A.

## GAS solved this school heating problem

Gas-fired low pressure central heating is installed in this most recent extension to Twickenham Technical College, opened in 1948.


Factors which influenced the choice of boiler plant were : the distant situation of the new buildings in relation to the main boiler house ; the difficulty of providing fuel storage and access to it ; and the difficulty of providing a suitable chimney that would be unaffected by the proximity of adjacent high buildings.

The new single-storey block contains eight classrooms with cloakroom accommodation. The total catalogue rating of the two automatically controlled boilers is 720,000 B.T.U's per hour.


*Helpful information on this and other aspects of the problem of securing efficient services for cooking, hot water, space heating and refrigeration may be obtained from the local Gas Undertaking.*

# GAS

# STRUCTURAL




# STEELWORK



BY  
**A U S T I N S**

EST. 1850



**James Austin & Sons <sup>Dewsbury</sup> Ltd., Dewsbury**

**THORNHILL IRON AND STEEL WORKS**  
**TELEPHONE: 1750 (5 LINES)      TELEGRAMS: AUSTINS DEWSBURY**

Associate Companies: ASTLEY BROOK & CO. LTD., St. George's Works, Huddersfield, Manufacturers of "A.B.C."  
GARAGES & GREENHOUSES, and A. J. RILEY & SON LTD., Victoria Works, Batley. Boiler Makers, Construction Engineers



*Living space  
wanted—  
urgently!*

There is no alternative to pressed steel door frames when building on a large scale—urgently.

The Morris Singer Company will provide full information and details by return of post.

*Standard*  
**PRESSED STEEL DOOR FRAMES**

*by*

**THE MORRIS SINGER COMPANY LTD**

FERRY LANE WORKS, FOREST ROAD, WALTHAMSTOW, LONDON E.17.  
Telephone: LARKSwood 1055



# In the PALACE, VICTORIA PALACE,



**PALACE.** Equipped with Dunlopillo throughout. Dress circle and circle recently re-equipped with Dunlopillo upholstered seats by W. W. TURNER & CO. LTD.



**VICTORIA PALACE.** Completely re-equipped with Dunlopillo upholstered seats by W. W. TURNER & CO. LTD.

## CAMBRIDGE and

## SHAKESPEARE MEMORIAL



**CAMBRIDGE.** Stalls recently re-equipped with Dunlopillo upholstered seats by W. W. TURNER & CO. LTD.



**SHAKESPEARE MEMORIAL THEATRE.** Recently completely re-equipped with Dunlopillo upholstered seats by MAPLE & CO. LTD.

**THEATRES...** *Comfort is the Keynote*

*thanks to*

# DUNLOPILLO

THE ORIGINAL LATEX FOAM CUSHIONING

DUNLOP RUBBER CO., LTD. (DUNLOPILLO DIVISION), RICE LANE, WALTON, LIVERPOOL 9.

LONDON: 19/20 NEW BOND ST., W.1  
ID/T3




# Where are the BRICKS going?

## 4: POWER STATIONS

The new generating stations are of massive proportions and necessarily conspicuous. They have received much thought from the aesthetic standpoint, and the bricks used have been carefully selected to harmonise with their surroundings.


The high-priority requirements of the British Electricity Authority, added to the urgent demands for Houses and Flats, Schools, Office Blocks, Industrial and many other types of building, have taxed the resources of the brick industry. Production is increasing in the face of many difficulties, and a steady improvement in the supply position is assured.



*Above:* Portion of Croydon Power Station, under construction.  
Architect: Robert Atkinson, F.R.I.B.A.



*Left:* Stourport 'B' Power Station.  
Architects: Farmer & Dark, F/F.R.I.B.A.




*Below:* Staythorpe Power Station.  
Architect: T. Cecil Howitt, D.S.O., O.B.E., F.R.I.B.A.

## BRICK

*The Modern Building Material*

Photographs  
by courtesy of  
British Electricity Authority

Issued by  
The National Federation of Clay  
Industries, Drayton House, W.C.1



*It pays to specify*

## McKECHNIE EXTRUSIONS

McKechnie extrusions are made in almost infinite variety. Their architectural, industrial, commercial and domestic uses range from marine pumps and ship stabilizers to electric fuses

and window frames. Because of their fine finish and minute closeness to size, their use reduces or eliminates machining, saves materials, tools and labour, and increases output.

*If you have a production or machining problem, write to 14, Berkeley Street, London, W.1.*



## McKECHNIE METAL TECHNIQUE

McKECHNIE BROTHERS LIMITED  
Metal Works: Rotton Park Street, Birmingham, 16.  
Branch Offices: London, Leeds, Manchester,  
Newcastle-on-Tyne.  
Solder Works: Stratford, London, E.15.  
Copper Sulphate and Lithopone Works: Widnes,  
Lancs.  
Enquiries for Lithopone and Solder to:  
14, Berkeley Street, London, W.1.  
South African Works: McKechnie Brothers S. A.  
(Pty) Ltd., P.O. Box No. 382, Germiston, S.A.




# GILLETT AND JOHNSTON LIMITED


The arrival of Mr. William Gillett at Croydon in 1844 was unheralded and unsung. But in that year he founded his clockmaking business... and 33 years later the bell foundry was established. Today his name, with that of his partner Johnston, is universally known.

St. James's Palace, Louvain University Library, St. Jan's Cathedral S'Hertogenbosch, Shell-Mex House, The Royal Exchange, Ottawa Parliament Buildings, the University of Chicago, and the Riverside Drive Church in New York, are but a few of the eminent buildings with which Gillett and Johnston have been associated.

BELLFOUNDERS  
AND  
CLOCKMAKERS


CROYDON





*This form of* **GYPKLITH** *construction*  
 is PARTICULARLY SUITABLE FOR FACTORY ROOFS

Registered Trade Mark



*Typical roof arrangement using inverted "T" purlins*

In the building illustrated, GYPKLITH is supported between purlins of inverted "T" section, spaced at centres equal to 2 ft. plus the web thickness and bolted direct through the flange to the trusses.

The top surface of the GYPKLITH is screeded with GYPLOC Metropolit: Stucco ready for finishing with bituminous roofing.

The underside of the GYPKLITH is left untreated in order not to impair its sound absorbent properties. A relatively smooth finish can, however, be obtained by brushing GYPKLITH Surface Filler over the underside of the slabs before fixing in place.

The thermal transmittance "U" value of this roof construction, using 3" thick GYPKLITH, is 0.15 B.Th.U's per sq. ft. per hour per 1°F difference in temperature.

Further information about this and other GYPKLITH products or systems will gladly be supplied.


Makers also of PARISTONE Browning Plaster  
 (Haird, Unhaird and Metal Lathing Quali-  
 ties) PARISTONE Wall Finishing Plaster  
 CRETESTONE Concrete Bonding Plaster  
 GYPSTONE Board Finishing Plaster

**GYPROC PRODUCTS LIMITED**


HEAD OFFICE: Westfield, Upper Singlewell Road, Gravesend, Kent. Tel: Gravesend 4251-4 Grams: Gyproc, Gravesend. GLASGOW OFFICE: Gyproc Wharf, Shieldhall, Glasgow, S.W.1. Telephone: Govan 2141-3  
 Telegrams: Gyproc, Glasgow. LONDON OFFICE: Morris House, 1-5 Jermyn Street, London, S.W.1  
 Telephone: Whitehall 8073-4 G.K.11

*Restrained*


*Elegance*



Lacrinoid door furniture is made primarily to do its job—and to continue doing it with quiet efficiency throughout its long life. At the same time, it is pleasant to both hand and eye. Shapes are simple and rely for their beauty on restrained curves which capture and enhance reflected light.



An exploded view of the model illustrated on the left. It is a lever mortice, concealed fitting and the Lacrinoid "floating spindle" principle is used, thus dispensing with grub screws. No. 280.



The back view of the finger plate illustrated on the left showing the reinforcement. Being mass produced these plates are cheap as well as sound. Supplied in two sizes. No. 1064/3.

#### COLOURS

Black Brown Ivory

**LACRINOID**

TRADE MARK

LACRINOID PRODUCTS LTD • GIDEA PARK • ESSEX  
TELEPHONE: HORNCHURCH 2981/6  
TELEGRAMS: LACRINOID, ROMFORD





BRINGING COLOUR TO LIFE



# IN THE NATION'S SCHOOLS

Colour now has other jobs to do besides hiding dirt, or lighting dark corners. It must guide and help the unsophisticated eye, comfort and cheer, stimulate the imagination and encourage a sense of pride. Chameleon-like, children take colour from their surroundings. And so it is good to see schools whose entrance and

assembly halls are bold and stimulating as well as bright, classrooms whose colour schemes are homely as well as functional, and staff rooms which are pleasantly restful.

Dockers' paint technicians never forget that paint must protect as well as please, and that children still leave fingermarks . . . .

**HERMATOR** Super Gloss Paints, for example, are full-bodied, free-flowing paints prepared from pigments of the highest purity. They are equally suitable for outdoor work and interior decoration.

## DOCKER BROTHERS

*Makers of Paints, Lacquers and Varnishes for every purpose*

LADYWOOD



BIRMINGHAM · 16





## the new lightweight **STRUCTURAL** material

### **SAVES COST**

Cavity construction with  $4\frac{1}{2}$ " facing brick externally and  $18"$  x  $9"$  x  $3"$  Thermalite building blocks as a load-bearing inner leaf is cheaper than the traditional  $11"$  cavity brick wall.

### **SAVES FUEL**

A single leaf of  $18"$  x  $9"$  x  $3"$  Thermalite building blocks is equivalent in thermal resistance to  $13\frac{1}{2}"$  of brickwork.

### **SAVES MAN HOURS**

Standard laying rates for Thermalite building blocks are as follows:  
 $18"$  x  $9"$  x  $3"$ —22 blocks per hour  
or the equivalent of  
132 brick equivalents per hour  
 $18"$  x  $9"$  x  $4"$ —20 blocks per hour  
or the equivalent of  
120 brick equivalents per hour.

### **SAVES WEIGHT**

The weights of one yard super of walling in Thermalite building blocks are as follows:  
 $18"$  x  $9"$  x  $3"$ —112 lbs.  
 $18"$  x  $9"$  x  $4"$ —150 lbs.  
These figures may be compared with a weight of 320 lbs. for one yard super of  $4\frac{1}{2}"$  brickwork.

*For full details and technical data apply to*

**THERMALITE LIMITED** Shepherds House Lane, Earley, Reading. Telephone: Reading 62650

*THERMALITE was developed in the laboratories of John Laing and Son Limited and is manufactured in Great Britain under British Patents—648280 and 648299. Thermalite is patented throughout the world.*

**NOW -**

# A Complete 'Family'

## An All-Glass 'Ventiblock' to match all 'Insulight' Hollow Glass Blocks


The 'Ventiblock' solves the problem of ventilating Glass Block installations. It is also widely used independently where permanent ventilation and light transmission are required.

### THE CLARK-EATON ALL-GLASS 'VENTIBLOCK'

incorporates two air passages; internal baffles prevent a direct draught without impeding the free flow of air, exclude driving rain, and obscure vision. The new patterns have a FLAT BASE, facilitating fixing, and are also designed to receive a detachable ANTI-FLY SCREEN, which can be supplied if required. An OPENING AND CLOSING DEVICE is in course of development.

Specify TYPE 2 to go with PB2 Hollow Glass Blocks, TYPE 3 for PB3, TYPE 32 for PB32.

The 'Ventiblock' is supplied through the usual Trade channels.



(Top) Type 3 (Fluted on one face). Size  $7\frac{1}{4}'' \times 7\frac{1}{4}'' \times 3\frac{3}{8}''$   
(Bottom, left) Type 2. Size  $5\frac{1}{4}'' \times 5\frac{1}{4}'' \times 3\frac{3}{8}''$  (Bottom, right) Type 32. Size  $7\frac{1}{4}'' \times 7\frac{1}{4}'' \times 3\frac{3}{8}''$

Patent Nos. 552195 583552. Further patents pending.  
Designed by Lethieullier Gilbert, A.I.A.A., L.R.I.B.A. and  
L. James Hobson, A.R.I.B.A.

SEE OUR EXHIBIT AT THE BUILDING CENTRE,  
9, CONDUIT STREET, W.I., OR CONSULT CLASSFILE No. 20



Stand No. 237 Row L

# JAMES CLARK & EATON LTD.

(Amalgamating James Clark & Son Ltd., and Eaton, Farr & Gibson Ltd.)


GLASS FOR ALL STRUCTURAL AND DECORATIVE PURPOSES

SCORESBY HOUSE · GLASSHILL STREET · BLACKFRIARS · LONDON S.E.1

PHONE: WATERLOO 8010 (20 lines)

BRANCHES: CANTERBURY · BOURNEMOUTH · EASTBOURNE · READING · OXFORD (H. Hunter & Co.)







## THE SADIA COAL-ELECTRIC WATER HEATER

allows great flexibility in planning

The Sadia coal-electric water heater is suitable for both houses and flats, and can be used either with a back-boiler or an independent boiler. It is a water heater planned to make the best use of available fuels. During winter, when fires are lighted, the Sadia coal-electric water heater acts as a storage tank, the back-boiler or the solid-fuel boiler heats the water, and the thermostatically controlled electric heating element in the Sadia coal-electric water heater takes over only when the fire dies down. In summer, no fires need be lighted, electricity takes over completely, and the house keeps cool.

The Sadia coal-electric water heater is the only factory-built unit of its type; made by water heating specialists it is the result of the accumulated experience of many years in this particular field. Efficiently insulated, it increases the effectiveness of the solid fuel boiler to which it is connected. When installed in blocks of flats, the patented self-venting and self-filling calorifier makes for simplified plumbing. One common down-service pipe can supply all the Sadia water heaters.

Aidas Electric Ltd., the makers of the Sadia coal-electric water heater, are always very glad to give specialist advice on all aspects of water heating to architects when they are preparing plans.





**Aidas Electric Ltd., Sadia Works,  
Rowdell Road, Northolt, Middlesex.**  
Scottish Agents: W. Brown & Co. (Engineers) Ltd.,  
89 Douglas Street, Glasgow, C.2. Manufactured in  
South Africa by Sadia Water Heaters (Pty.) Ltd.,  
3-5 Newton Street, Village Main, Johannesburg.

**SADIA**

HOT WATER BY  
ELECTRICITY

## THE WESSEX COTTAGE



### Practical, economical and good to look at

The Wessex Cottage has been developed by Orlit to meet the need for an economical and well designed dwelling which could be erected quickly and with the minimum use of skilled labour. It is particularly suitable for rural areas.

A prototype cottage (illustrated above) has been put up at the Orlit Works at Colnbrook, within 18 miles of Charing Cross. A cordial invitation is extended to architects, local authorities etc. to pay a visit of inspection.

# ORLIT CONSTRUCTION

PRE-CAST CONCRETE  
PRE-STRESSED CONCRETE



### A NATION WIDE SERVICE

ORLIT LTD. 18, Buckingham Gate,  
London, S.W.1. Tel: Victoria 6701

ORLIT (Lancashire) LTD. 3, Brown St.,  
Manchester, 2. Tel: Blackfriars 0718

TARSLAG LTD. Economac House,  
Wolverhampton. Tel: 23881

TARSLAG LTD. Tees Bridge,  
Stockton-on-Tees. Tel: 6355

BEACON PRE-CAST LTD. Marsh Green  
Road, Exeter. Tel: 4185/6

ORLIT (N. Ireland) LTD. Benson Street,  
Lisburn, Co. Antrim. Tel: 3249

THE SCOTTISH ORLIT CO. LTD. Sighthill Industrial Estate, Edinburgh 11.  
Tel: Craiglockhart 2287





HOUSING ESTATE IN  
BEAUTIFUL SOUTH  
DEVON

Many of the floors on this  
Estate were surfaced with  
Martyn Bituminous Domestic  
Flooring

## FLOORS FOR TOMORROW

*by Bruce Martyn . . .*

One of the most important features of Martyn Bituminous Flooring is its resiliency, a quality which enables it to stand up to the heaviest traffic conditions, in fact the floor actually improves with wear becoming more compact. It is damp-proof, dust-proof, ductile, warm and noiseless to the feet. It is laid cold, is resistant to fire and changes of temperature and is completely odourless at all stages. The floor can be laid directly on to a clean concrete base thus eliminating the necessity and cost of a cement and sand screed, whilst it is available in an attractive range of colours.



Martyn Bituminous Flooring is also available in Holland, Belgium, Italy, French Morocco and Tangier, and all enquiries for these territories should be made to the following licensed Contractors or to our Head Office:—

Holland and Belgium: Messrs. N. V. Vloerenbedrijf, H. de Vries & Zn. Stadhoudersweg 79, Rotterdam, Holland.

French Morocco & Tangier: Messrs. Henri Martin, 72, Rue de la Marne, Rabat, French Morocco.

Italy: Compagnia Finanziaria Industriale & Mercantile S. a R. L., 11, Corso Sempione, Milan, Italy.

*Our Technical Staff are always ready to advise on your problems*

# BRUCE MARTYN LIMITED



SPECIALISTS IN INDUSTRIAL AND DOMESTIC FLOORING

PICCADILLY HOUSE, REGENT ST., S.W.1. Phone: REGENT 6296-7

AN ILLUSTRATION OF  
A MARTYN BITUMINOUS  
INDUSTRIAL FLOOR  
LAID IN A VERY LARGE  
ENGINEERING WORKS







# Meet Daylight

the expert on  
**FACTORY LIGHTING**

Daylight can brighten your factory, increase output, make your workers happier—*all for nothing*. His services are freely available for at least five hours a day and much longer in the summer months. With rising prices, fuel shortages and power cuts, you can hardly afford to neglect Daylight.

.....


**Give Daylight a  
chance...fit  
corrugated**

**'PERSPEX'**



C.P.58A

*'Perspex' is the registered trade mark of the acrylic sheet manufactured by I.C.I.*  
**IMPERIAL CHEMICAL INDUSTRIES LIMITED, LONDON, S.W.1**




The size of the job makes no difference to Magnet. We always have large stocks for instant delivery to cope with any emergency: ample stocks of kilned and air-conditioned timber, highly skilled staffs and the most up-to-date plant at three modern factories. And, our prices are right. Complete satisfaction on EVERY job is thus assured.

For BIG jobs you must have the facilities of a BIG organisation if you are to keep to your time schedule—Magnet are always at your service.

**MAGNET**  
JOINERY LIMITED

WHITLEY STREET, BINGLEY, YORKS  
Bingley 3547 (5 lines)  
LOVE LANE, ASTON, BIRMINGHAM  
Aston Cross 1120-1  
LONDON ROAD, GRAYS, ESSEX  
Tilbury 77 (5 lines)

**first choice of all**



**EDGAR**  
*Gas Fittings & Apparatus*  
*meet the need for*  
**Secondary Lighting**

Experience has shown over a period of time that Edgar's B.W.39 wall fittings are dependable. They meet every standard required for the public's safety in case of emergency. In many public buildings . . . cinemas, theatres, restaurants . . . Edgar's lighting has given long and satisfactory service.

EXIT, WAY OUT and other signs, are also manufactured.



**WILLIAM EDGAR & SON LIMITED**

BLENHEIM WORKS · HAMMERSMITH · LONDON · W.6

Telephone: RIVerside 3486



**SOLVE** your fixing problems before construction is finished. Choose the machines and when they arrive—fix them fast, permanently and ready for instant use with Rawlbolts—no grouting-in—no cement to harden. Rawlplugs . . . speed the screw fixings with them! Switchgear, conduit, lighting, pipes and all similar fixtures—get them up quickly.

*Use Rawlplug Fixing Devices where "speed is the essence of the contract"*

**RAWLPLUG**  
FIXING DEVICES

WRITE FOR TECHNICAL LITERATURE

B398

**THE RAWLPLUG COMPANY LIMITED • CROMWELL ROAD • LONDON • S.W.7**

## Exquisite Modern and Period Lighting . . .

Chandeliers  
Wall Fixments  
Candelabras  
Table Lamps  
and Standards

Your enquiries  
are invited



421/423 FINCHLEY ROAD, HAMPSTEAD, LONDON, N.W.3. Phone: HAMpstead 7545-2948









**F**ERODO Stairtreads combine three essentials: SAFETY, smart appearance and long life.

Gleaming aluminium nosing clearly outlines each step and the inlaid Ferodo fabric affords a firm reassuring non-slip grip, even to wet leather or rubber soles—two vital factors in SAFETY. Further, Ferodo Stairtreads absorb endless wear over a period of many years without deterioration in efficiency or appearance.

They feature largely in Architects' specifications and are being installed in both new and existing public buildings, including Stores, Offices, Cinemas, Theatres, Hotels, Blocks of Flats, etc.

## A Striking Conversion... plus SAFETY



Ferodo Stairtreads are of two types—single and double channel. If preferred, in place of Ferodo fabric, the inlaid strips may be of Ferodo Composition—equally non-slip—in red, white or grey to harmonise with colour schemes. There is also a plain steel-backed Industrial type. All are described and illustrated in our Catalogue No. 732 of which a copy will gladly be sent on request.

*The illustrations are of a recent conversion at Abbey House, Victoria, London, S.W.1. Architects: Boreham Son & Wallace, London, W.C.1*

# **FERODO**

## **STAIRTREADS**

FERODO LIMITED, CHAPEL-EN-LE-FRITH

*A Member of the Turner & Newall Organisation*

## Better for every surface...



*Modern kitchen with all working surfaces and fitted cupboards surfaced with FORMICA.*



*Ladies' Powder Room at the London Palladium, panelled throughout in onyx-pattern FORMICA.*

Decorative, yet absolutely practical, FORMICA Laminated Plastic offers the architect unbounded opportunity for original ideas in surfacing. Here are a few of the advantages of this versatile material :

**HYGIENIC** — Formica has a hard, non-porous surface that cannot hold dust or germs and is easily cleaned with a damp cloth.

**HARD WEARING** — Formica withstands abrasion and heavy impact, does not crack or craze.

**NON-CORRODING** — Impervious to normal acids and alkalies, alcohol, oils and all foods.

**HEAT RESISTANT** — Unaffected by temperatures up to 120°C.

**ECONOMICAL** — Formica needs little maintenance, never needs renewal. Its first cost is the last cost.




*For further information about FORMICA please write to:*

**THOMAS DE LA RUE & CO. LTD.** (PLASTICS DIVISION), IMPERIAL HOUSE,  
84/86 REGENT STREET, LONDON, W.1

\*Formica is a registered trade mark and De La Rue the sole registered users

## AN INTERESTING NEW PRIMARY SCHOOL



**Wentworth Drive County Primary School, now completed, has some novel and interesting features :**

"A primary school to accommodate 320 pupils. A school that is practical, pleasing to see, and *one that the ratepayer can afford*. A school, above all, to be built quickly." These were the broad terms of the brief given to Mr. S. H. Loweth, F.S.A., F.R.I.B.A., M.I.Struct.E., Kent County Architect. Only 16 months later, pupils began taking their first lessons in Wentworth Drive School.

Speed of erection was a prime consideration. Wentworth Drive thus became one of the first schools in Britain to incorporate aluminium construction. Although the front of the building, as seen from the road (i.e. the Admin. Wing, Assembly Hall and School Meals Unit), is constructed of yellow stock brick in traditional style, the two long classroom-wings—which stretch out behind—were brought on site in the form of pre-fabricated aluminium units four feet wide, ready clad both outside and inside, and supplied by the Bristol Aeroplane Company. The result is a good-looking combination of old and new.

Classrooms and corridors were both con-

structed on direct-to-earth concrete, thereby saving time and expense. The flooring material used was Accotile (thermoplastic tile made by Armstrong Cork Company).

So satisfactory has the architect's design proved, that a second and adjoining school is shortly to be built next-door to the existing building, on similar lines. Wentworth Drive's heating-chamber and meals-unit are, therefore, double-sized. They will, eventually, serve both schools.

There are many modern features in the new school. It is, for instance, wired throughout for radio and gramophone reproduction. Perhaps, however, its most interesting facet is the quality of its interior decoration. A great deal of thought was devoted to this, in order to give pupils a pleasant place to work in, with no lack of variety. The colour-schemes, particularly, have been carefully devised, and have won praise from high authority.

Every classroom has a different colour-scheme—set off by the tile floors. Here, the architect was helped by the wide range of

*This new school in Dartford, Kent, was built in little over a year. The architect—Mr. S. H. Loweth, F.S.A., F.R.I.B.A., M.I.Struct.E.—went to some trouble to see that only building materials in full supply were specified. It is interesting to note that he used the same flooring material, in a variety of forms and colours, for well over half the ground-area of the building. He chose Accotile, the new asphalt-tile flooring made by the Armstrong Cork Company.*

colours in which Accotile is available.

All in all, a not-unimportant part in the project was played by Armstrong's Accotile. The decorative qualities of the tiles have given the floors an appearance of near-luxury. It is quiet to walk upon, and even in the corridors, where the hardest wear is expected, it will last well. It is very easily cleaned and—most vital—its extremely low price has helped to make Wentworth Drive School not only a first-class building but "one that the taxpayer can afford."

For full information about Armstrong's Accotile, architects and builders are invited to telephone or write to Armstrong Cork Company Limited, Flooring Department, Bush House, Aldwych, London, W.C.2. Tel: Chancery 6281. Scottish Branch: 5 Oswald Street, Glasgow, C.1. Tel: Central 5703.

*The following were responsible for Wentworth Drive County Primary School: S. H. Loweth, Esq., F.S.A., F.R.I.B.A., M.I.Struct.E., County Architect; R. T. Green, Esq., F.R.I.B.A., County Architect (in charge of Schools); R. C. Passmore, Esq., A.R.I.B.A., Principal Assistant; C. B. H. Cremer, Esq., A.R.I.B.A., Architect in Charge; Messrs. Gilbert Ash Ltd., 2 Stanhope Gate, London, W.1, General Contractors.*

**ACCOTILE\***  
"The low-cost floor with the luxury look"

★ British Registered Trade Mark 663698. Armstrong Cork Company Ltd., Registered Users.





Every foot confirms the comfort and economy of

## IOCO rubber flooring


The durability of IOCO Rubber flooring is greater than either stone or cement. In fact, it is practically indestructible in ordinary wear and is, unquestionably, the most economical floor covering you can lay. In addition it is soft and resilient to the foot, eliminates noise and is absolutely non-skid.

IOCO designers are at your service in the preparation of drawings to suit any scheme of decoration and, of course, IOCO experts carry out the laying operations anywhere in Great Britain. Write for 16-page booklet "IOCO Rubber Flooring."


- ★ Available either as flooring or inlaid tiling in a variety of plain and marbled effects.
- ★ Ideal for stairways where combined treads and nosings are recommended and with which a variety of contrasting effects can be obtained.
- ★ IOCO Rubber Flooring is manufactured entirely at the Company's Works to the standard specification of the Rubber Growers' Association, thus ensuring uniformly high quality.



For Kitchens, Bathrooms, Hallways, etc.




For Hotels, Cinemas, & Public Buildings.



For Restaurants, Cafés, Snack Bars, etc.



**IOCO LIMITED • Netherton Works • Anniesland • Glasgow • W.3**



## "BONDENN" REINFORCEMENT

Is suitable for reinforcing brick-work

It is so designed that the main members distribute the load evenly. To provide ADEQUATE PROTECTION AGAINST CORROSION it is GALVANISED AFTER MANUFACTURE. This protection is one of the main essentials for reinforcement in conjunction with GLASS BLOCK CONSTRUCTIONS.

BONDENN IS ONE OF THE REINFORCEMENTS APPROVED BY THE GLASS BLOCK MANUFACTURERS

Permanent Exhibit at



# GALVO (WIRE NETTING) LIMITED

CONEYGRE ROAD • TIPTON STAFFS • PHONE TIPTON 1191



# Originality



The safety of children in the home, has been featured by us in advertisements since first we introduced fully interlocking switchsockets some thirty years ago. This picture is reproduced from an old catalogue. Boys will always have their share of mischief and curiosity; but ingenious electrical accessories, such as those pioneered by MK, have kept each successive generation out of harm's way. In the early thirties we introduced a switchsocket to interlock with ordinary British Standard unmutated plugs. This design, substantially unaltered, is still in great demand—a sure tribute to originality and reliability.




## M.K. ELECTRIC LIMITED

WAKEFIELD STREET, EDMONTON, LONDON, N.18

Phone: Tottenham 5151

Grams: Multicon, Southtot, London

## *The finishing touch . .*



- "DON" COLOUR-FILLED STAIRTREADS provide a safe tread, giving a firm foothold under all conditions.
- Aluminium nosings, together with the attractive colour range which is available, clearly show up each step, combining artistry with safety.
- Available in the following attractive range of colours: brown, silver, green, gold, blue, maroon, black, white, pink and red.
- The more common type of fabric-filled stairtreads can be supplied as well as our well-known colour range.
- Comprehensive range of nosings available—send for brochure, and copy of Architects' Journal Information Sheet.



COLOUR-FILLED  
ALUMINIUM  
*stairtreads*

PATENT No. 645569

SMALL & PARKES LIMITED · MANCHESTER · 9  
LONDON: 18 HIGH STREET, WIMBLEDON, S.W.19

## *Windows of yesterday*

The Georgian bay window has permanent charm.

Note how this is preserved in the JONWINDOW illustrated, combining appropriate decoration and sympathetic rendering with 'down to earth' fitness to purpose.

In 1951 JONWINDOWS will be supplied to The Building Centre New Premises at 26 Store Street, London, W.1; and British European Airways Buildings, London Airport



## *Everywhere the windows of TODAY*

# JONWINDOWS


JOHN WILLIAMS & SONS (CARDIFF) LTD  
EAST MOORS RD. CARDIFF

Telephone: Cardiff 2501    Telegrams: "Metal" Cardiff

ARE GALVANIZED BY THE HOT DIP PROCESS

BANK CHAMBERS    FINSBURY PARK N.4    TEL.: ARCHWAY 2294    'GRAMS: DISSOLVING LONDON





Not only are Econa traps and fittings available in a comprehensive range of standard designs, but they are also supplied to meet those many special requirements which arise from time to time even at the drawing-board stage. Starting from straight smooth-bore copper tube we can bend it into the most unusual shapes and introduce branches at will. Econa fittings help the architect to work without allowing his drainage problems to stifle his inspirations.



*Econa traps and fittings are all made from smooth copper tubes.*

# Econa

**CAN HELP YOU....**

**ECONA MODERN  
PRODUCTS LIMITED**

**AQUA WORKS, WARWICK ROAD,  
TYSELEY, BIRMINGHAM 11.**

*'Phone ACocks Green 2211*

T & H



**Take any number...**

In mass production the batch number of a lamp is an important reference, as from every batch, during manufacture, a certain percentage of lamps is subjected to numerous tests. Statistical analysis of the results of these tests gives early warning of any tendency to drift from the desired standard in light output, mechanical strength, life etc. You can therefore, take any number of these lamps with the assurance of consistently high quality throughout.

*Checking luminous efficiency of G.L.S. lamps in an Integrating Sphere.*


## METROVICK LAMPS

*Quality controlled throughout manufacture*

**METROPOLITAN-VICKERS ELECTRICAL CO. LTD., ST. PAUL'S CORNER, 1-3 ST. PAUL'S CHURCHYARD, LONDON E.C.4**

*Member of the A.E.I. group of companies*





WATERLOO MANSIONS, DOVER  
(By courtesy of Dover Harbour Board)

*Olivette*

## HIGH GRADE ENAMEL PAINTS

These paints represent the finest quality decorative materials and have proved their outstanding resistance to the ravages of atmosphere and light in coastal districts—the most exacting test. Even pale shades, so often fugitive, possess excellent colour and gloss retention. A short range of Olivette Exterior “Superfast” Greens of proved excellence for exterior work is also available.

*Olivette High Grade Enamel Paints are available in both Exterior and Interior qualities. Each range provides the finest finish, maximum protection and greatest durability.*

**.....defiant of wind and weather**

**W. & J. LEIGH LIMITED**

**TOWER WORKS • BOLTON • LANCs**

Telephone: Bolton 4277 (3 lines)

London Office: 15 St. Helen's Place, E.C.3

Glasgow Office: 163 Gt. Vincent Street, C.2

Telegrams: “Fabrique Bolton”

Phone: London Wall 1457/9

Phone: Central 2079





## J. GERRARD & SONS LTD.

*Builders and Civil Engineers*

Contractors for the Showrooms and Offices for  
Messrs. Richard Haworth & Co. Ltd.,  
Newgate Street, London.

*Head Office and Works:*

SWINTON,  
MANCHESTER.

Tel. Swinton 2261 (8 lines)

*London Office:*

VICTORIA HOUSE,  
SOUTHAMPTON ROW,  
LONDON, W.C.1.

Tel. Holborn 8348



PREMISES FOR MESSRS. RICHARD HAWORTH & COMPANY, LTD.  
NEWGATE ST., LONDON, E.C.1 Architect: T. H. GROSS, A.R.I.B.A.

EXHIBITION DISPLAYS

### OSTERS & FLEMING

ARCHITECTURAL WOODWORK


88, 89 THE ARCHWAYS

STUDLAND ST., LONDON W.4

RIVERSIDE 1653

INTERIOR DECORATIONS

# SULZER



Factory of Messrs. Courtalds Ltd. at Carrickfergus, Northern Ireland.

26-inch Low-Pressure Steam Distribution Main with expansion bend by Sulzer Bros. (London) Ltd.

AIR CONDITIONING  
VENTILATION  
PANEL WARMING  
SPACE HEATING

ELECTRODE BOILERS  
INDUSTRIAL PIPING  
ALL-WELDED STEEL  
PIPING INSTALLATIONS

SULZER BROS. (LONDON) LTD., 31, BEDFORD SQUARE, LONDON, W.C.1

SULZER BROTHERS LIMITED HAVE OFFICES AT:— WINTERTHUR — PARIS — NEW YORK — MADRID — CAIRO — RIO DE JANEIRO — BUENOS AIRES — SHANGHAI — KOBE.  
Agencies at:— BRUSSELS — MILAN — AMSTERDAM — LISBON — COPENHAGEN — OSLO — STOCKHOLM — HELSINKI — ATHENS — ISTANBUL — ALGIERS — JOHANNESBURG — HAIFA — BOMBAY  
BARACHI — COLOMBO — SINGAPORE — BANGKOK — MANILA — MONTREAL — MEXICO CITY — BOGOTA — CARACAS — SANTIAGO (CHILE) — LIMA — LA PAZ — SYDNEY — MELBOURNE — WELLINGTON



## *Movable Walls of Impeccable Appearance*

There is nothing temporary in the appearance or performance of the Luxfer-Snead System of partitions—yet a complete suite of offices can be re-positioned in a week-end if so needed.

The 3 in. thick wall units are of double sheet steel with insulation board cemented to the inner side and  $1\frac{3}{4}$  in. dead air gap. Panel units lock together with internal concealed link plates. Single or double glazing is secured by positive 'snap on' glazing strips. Door and panel units of the same size are interchangeable.

In these Luxfer partitions the functional advantages of good sound and heat insulation and provision for enclosed electric wiring are combined with modernity and dignity of appearance. You will find them in many important buildings where their handsome highly finished plain surfaces and practical attributes make them the obvious choice.

Solid or glazed walls are available in both standard units or purpose-built. Full particulars will be sent gladly on request.



# **LUXFER LIMITED**

**WAXLOW ROAD • HARLES DEN • LONDON • N.W.10**

Telephone: ELGAR 7292-5

Telegrams: LUXFER, HARLES, LONDON.



THE ARCHITECTS' JOURNAL

No. 2953 4 OCTOBER, 1951 VOL 114

EDITORIAL BOARD: (1) *Consulting Editor*, F. R. Yerbury, Hon. A.R.I.B.A. (2) *Guest Editor*, Frank Russon, F.I.O.B. (3) *Town Planning Editor*, Dr. Thomas Sharp, L.R.I.B.A., P.P.T.P.I. (4) *House Editor*, J. M. Richards, A.R.I.B.A. (5) *Technical Editor*, R. Fitzmaurice, B.Sc., M.I.C.E., Hon. A.R.I.B.A. (6) *Editor Information Sheets*, Cotterell Butler, A.R.I.B.A. (7) *Editorial Director*, H. de C. Hastings.

SPECIALIST EDITORS\*: (8) Planning (9) Practice (10) Surveying and Specification (11) Materials (12) General Construction (13) Structural Engineering (14) Sound Insulation and Acoustics. (15) Heating and Ventilation (16) Lighting (17) Sanitation (18) Legal.

ASSISTANT EDITORS: (19) *Chief Assistant Editor*, D. A. C. A. Boyne (20) *Assistant Editor* (News), K. J. Robinson (21) *Assistant Editors* (Buildings), (21) L. F. R. Jones, (22) A. P. Lambert, (23) *Assistant Editor* (Information Sheets) E. G. Johnson (24) *Assistant Technical Editor*, M. Jay (25) *Photographic Department*, (25) E. R. H. Read, (26) H. de Burgh Galwey (27) *Editorial Secretary*, Betty E. Harris

\* To preserve freedom of criticism these editors, as leaders in their respective fields, remain anonymous

9, 11 & 13 Queen Anne's Gate, Westminster, London, S.W.1 Whitehall 0611

Subscription rates: by post in the U.K. or abroad, £2 10s. 0d. per annum. Single copies, 1s.; post free, 1s. 3d. Special numbers are included in Subscriptions; single copies, 2s.; post free, 2s. 3d. Back numbers more than 12 months old (when available), double price. Half-yearly volumes can be bound complete with index in cloth cases for 25s. 0d.; carriage, 1s. extra.



## HE QUITE FORGOT

Opening a new industrial estate, particularly a well designed one, should, I would have thought, have been a rather inspiring business. Last week's opening at Harlow was not, but it's hard to say why. Half way along a new concrete road, flanked on one side by the new buildings, complete or nearly so, standing in the tumbled muddy soil of the building site, and on the other, the brown mouldering shapes of one of Harlow's earlier industries, a farm, stood a circle of unimpressed journalists and labourers eyeing a little black box on a shabby deal table. By turning a switch on the box, Mr. Lindgren, Parliamentary Secretary to the MOLGP (who was standing in for Hugh Dalton), turned on the supply of electricity to the factories. Not a very inspiring

movement anyway, hardly as dramatic as cutting a tape, but everyone made the most of it, fussing around with cameras and adjusting the position of the table while Mr. Lindgren posed and posed.

\*

He made a speech, of course, telling us that this was the only way to settle London's congestion, a policy he had been advocating (as I am sure you all remember) for the past twenty-five years. He wished well the industrialists and workmen who were going to the estate, and he expressed appreciation of the efforts of Richard Costain, Chairman of the Development Corporation. But once again, as so often happens, no reference was made to the designers of the buildings, or the planners or the consultants (though of course he remembered the building operatives). Now I am quite sure that nobody, from the top architect to the most junior draughtsman, cares tuppence whether he remembers them or not, but the public would, I'm sure, respect more highly those public servants who can remember these details, and give credit and thanks where it is due.

\*

As I left the site, I passed a little group of men filling in the hole around the tree which Mr. Lindgren had planted to commemorate his visit. It seemed rather close to one wall of a factory, which fact no doubt prompted a journalist to call out to the gardeners: "You'll be cutting that down in a few year's time"; to which remark the gardeners, not one whit perturbed and not pausing to look up from their task, replied: "We know, we know."

## THE PREDICTABLE ENGLISH

We are a wonderful people. I have

been told a story about a meeting which recently took place in the Festival offices to decide how many extra precautions would be needed on the South Bank to prevent large-scale pilfering (more politely "souvenir-hunting") during the last days of the exhibition. It was attended of course by the South Bank security staff, and also by a hard-bitten officer from Scotland Yard with a lifetime of experience of the British public behind him.

\*

His advice was asked about the need for extra police on the last day. He thought for a moment, and then came out with this very useful generalization: "No need to worry too much," he said. "The British public doesn't pilfer on a Sunday. Wednesday or Saturday, yes. But Sunday, no."

\*

No doubt he is right, but (writing before the event) I don't suppose the Festival authorities took many chances, so I hope for your own sake that before you slipped that prize pullet under your coat or that useful-looking household gadget into your pocket, you made quite sure that the gentleman in the mackintosh who looked as though he was merely trying to get there first wasn't in fact a plain-clothes detective.

## CIVIL ART

Just before it closed, I visited an exhibition of paintings and sculpture by the Association of Civil Servants Art Group. This was held in what is called the "Pillared Hall" in the new Whitehall office buildings designed by Vincent Harris. The Hall lives up to its name, having octagonal black columns in pairs down each side of it, in a manner not unreminiscent of one of the rooms in Stockholm Town Hall. Much more





## THE MODERN WINDOW

*is fitted with friction hinges  
has no stay to clutter the cill  
never slams : will not corrode*

# HOPE'S

HENRY HOPE & SONS LTD., Smethwick, Birmingham, & 17 Berners St., London, W.1

domin  
colour  
and cr  
of the

The  
of co  
tradit  
ceivab  
conce  
fully  
land o  
benea  
were i  
with h  
ing su  
suffus  
wall,  
metic

As I  
prise  
abstra  
colour  
ing, I  
hamp  
ture  
to his

THOS  
A C  
holds  
soon  
and  
strict  
be he  
a year  
rashl

Tho  
could  
ful v  
think  
if r  
grow  
possi  
whic  
197,0  
First  
in la  
tive  
from  
paid  
main  
of te  
time  
Seco  
conc  
room  
of C  
must



dominating, though, is the strongly coloured floor of squares of maroon and cream linoleum. However, enough of the room: I went to see the paintings.


The standard is remarkably high, but, of course, as one would expect, very traditional in expression. Every conceivable technique was used, and every conceivable artistic subject was faithfully portrayed, even a view of Highland cattle (albeit very small) standing beneath large and misty hills. There were illuminated manuscripts decorated with halfpenny-sized medallions depicting sunsets, and a large, pink and yellow suffuse painting of roses on an old brick wall, every chip and crack of which was meticulously recorded.

As I left, however, I noticed to my surprise a small disruptive element. Some abstract paintings with a strength of colouring which I could not help feeling, I hope quite groundlessly, may well hamper the artist's career if his departure from convention becomes known to his superiors in The Service.


THOSE 300,000 . . .

A General Election on October 25 holds out the possibility that we may soon have a Conservative government, and in that event ASTRAGAL (though strictly non-party) thinks that we shall be hearing more of the 300,000 houses a year which a Party Conference rather rashly chose as their target figure.

Though nothing in home affairs could be more worth while, it is doubtful whether anyone in the industry thinks we can reach this output, even if re-armament and export needs grow no greater. But it is perhaps possible to agree on the methods which offer a chance of improving on 197,000; and on those which don't. Firstly, we must build new dwellings in large contracts; "large" being relative to the locality, and thus varying from 50 up to 500 and more. This puts paid straight away to daydreams (now mainly indulged in by evening papers) of tens of thousands of 3-houses-at-a-time speculations by small builders. Secondly, we could gain a good deal by concentrating for 5 years on 2-bedroom and even 1-bedroom dwellings of 600-700 feet super. Thirdly, we must admit that prefabrication of



*The Festival authorities may feel a little ashamed if they get to hear that at this year's Milan Triennale people wishing to travel to the exhibition by wire did not have to walk—as did Charles Elleano at the South Bank (see note below). Instead they travelled in this "seggiovia" from the station shown above.*




structure has little to offer us while light materials are so scarce. We must, in fact, cut on carcassing to save what we have for finishings and equipment. This seems to point to a wide use of materials such as "no fines" which does the mass of the structure with nothing but small stones and a little cement. It might also be helpful to sack the man who allows us to export complete prefabricated timber houses at a time when we are beginning to walk round the walls of new first-floor bedrooms rather than across the middle of the floors.

#### GOING BY WIRE

I don't suppose many AJ readers have any more desire than I have to emulate the feat of Charles Elleano, who re-

cently made a high wire crossing of the Thames to the South Bank with so much French grace and aplomb. Yet surely the pleasures and possibilities of the more sedentary kind of wire travel are unduly neglected in this land of ours.

I am prompted to this reflection by the photographs that I show you on this page of the "seggiovia" erected in the Parco at Milan for the Triennale. The purpose of this amiable and elegant device was to waft foot passengers across that part of the park which contained the exhibition, affording them a (let us say) woodpecker's-eye view of the pavilions on the way. How delightful to cross the Thames, or swing among the trees of Kensington Gardens or Battersea, in this manner!



## Farewell to an Exhibition : Welcome to a Regained South Bank

In this last view of the South Bank Exhibition we have numbered those buildings which could and should be retained until actual building for the permanent redevelopment starts, so as to ensure that this hard-won site maintains its role as a cultural centre and an integral part of central London. The periodic crowds drawn to the Festival Hall (1), the only permanent building would be supplemented by using the Lion and Unicorn Pavilion (2), as an art gallery, by the Telekinema (11) and by the

use of the administration block (9) as offices, and the Homes and Gardens Pavilion (10) might be used as a BEA terminal with Undergrat access at Waterloo Station Gate (3). Another attraction would be the riverside walk (5), with fountains, ponds, plants and look-out platforms retained, running from the '51 Bar (4) (with the vast building site of the cleared upstream section to be watched from its terrace) past the pier (6) and the Shot Tower (7), to the Thameside Restaurant (8).

AST  
If  
sun  
enc  
in v  
you  
to  
cer  
cro  
a m  
nin  
(sh  
stea  
or  
clin  
as  
one  
a fi  
no  
has  
To  
veil  
sev

Th  
Ma  
Fri  
cin  
stor  
ter,  
in  
Wh  
suc  
inc  
am  
to  
snu  
gap  
the  
crie  
enc

Th  
Joh  
enc  
arc  
stri  
lust  
kno

An  
cele  
filed  
the  
Ger  
of  
two  
eve  
seen

## ASTRA ET ASTRAGAL

If you have been in London this summer you may have been fortunate enough to see that pleasing French film in which one of the characters, a very young man, having waved his farewells to a departing lady, turns, disconcertingly, to the agape audience and crows delightedly: "I am the lover of a married woman!" as he takes a running leap back to his *appartement* (short lease only). Throughout life one steadily accomplishes those acts, moral or otherwise, which mark one's social climb. ASTRAGAL, almost as brashly as the young man, can now announce one such step: he has been invited to a film première. A little late in the day, no doubt, but do not scoff at one who has reached out and touched the stars. To be precise, the hem of Anne Todd's veil (was it, I wonder, her sixth or seventh?).

The occasion was the showing of *The Magic Box*, the film of the life of Friese-Green, the inventor of the cinematograph. This is a sad film, the story of a dull and unsuccessful character, despite a very good performance in the principal part by Robert Donat. Whatever chance the story had was successfully ruined by the policy of including virtually every eminent actor amongst the cast. The result was similar to a charity matinée. The audience, snug in the gilded belly of the Odeon, gaped and lunged as they strove to spot their favourites. "Why, look!" they cried: "Laurence Olivier." And, sure enough, there he was.

The sets of Edwardian interiors by John Bryan were first-class, and, oddly enough, like many a contemporary architect's sitting room. Dark green striped wallpapers, cluttered shelves of lustre china, beaded footstools—you know whom I have in mind.

Afterwards, of course, there was a celebrity inspection. Down the stairs filed the nobs, flashing smiles to greet the flash-bulbs; from film stars to Gerald Barry and even the benign face of painter Carel Weight in shaggy tweeds. Overheard in the foyer: "My evening's made for me, my dear, I've seen John Rothenstein!"

ASTRAGAL

## The Editors

## ILL-INFORMED CRITICISM

A STATEMENT by an Alderman at the annual conference of the Institute of Housing condemning "the rake-off of those professional men, the architects" did not receive much publicity in the daily Press. Nevertheless, there were newspapers which saw fit to publish it, and it is, therefore, encouraging to be able to report that the President of the RIBA has written to those newspapers to refute such criticism.

We publish this week in our correspondence columns two letters, which readers have sent to us, drawing our attention to Alderman W. E. Power's comments. In one of them is quoted in full the report of the Alderman's speech which appeared in several Liverpool newspapers.

What the Alderman says is all the more dangerous for the element of truth which it contains. It can well be argued that housing would be cheaper if architects were not employed and designs standardized. Thanks to our Victorian forefathers, many of the public and, indeed, even engineers, have not yet entirely got rid of the idea that the architect is only the man who applies the art to a building. It's an old story, but it is hard to live down. It is made even harder to live down by the fact that there are still architects practising who, by their inefficiency, or whimsicality, do unreasonably increase the cost of building.


It is obviously the task of the daily papers to publish the articles describing the architects' job and the disastrous lowering of already low standards which would come about if architects did not control the design and layout of housing. It is not for the JOURNAL to tell the architectural profession how essential they are, but rather is it the JOURNAL's task to remind the profession that criticism is most effectively answered by results. Inefficiency and slowness in the design and erection of housing *may* do calculable harm to an architect's reputation. The harm done to the citizen and his family patiently waiting to be housed is not so easily assessed. Architects, by virtue of their name, claim the chief responsibility in the building world. They must, therefore, be prepared to be the chief target for criticism.

## THE NEED FOR REPLANNING PLANNING LAWS

There is an increasingly widespread belief that amendments must be made to the present system of planning and licensing if building controls continue. On page 405 of this issue Ernest Watkins reports on some of the criticisms of the 1947 Planning Act made at the recent TCPA Summer School at Oxford. These, and other criticisms, have a much less academic sound—thanks to the political atmosphere of 1951—than comments on the Act made twelve months ago. It seems opportune to suggest that the architectural profession



(and, therefore, its professional associations?) might consider the collection of material concerning the practical working of the Act. Such material would provide valuable evidence for anyone who was made responsible for reviewing the Act. And it certainly will need reviewing if shortages of men, money and materials continue in the building industry for even another ten years, for it is no more adequate than the existing defence regulations governing building licences. The inevitability of a continuation of building controls is emphasized by the fact that the Home Secretary recently made an Order, under the Civil Defence Act, 1948, declaring that it was the duty of every local authority in England and Wales to make plans for the provision of civil defence shelters.



### "Ten Architects"

Vernon H. Lee, A.R.I.B.A.

Anthony Jackson, A.R.I.B.A.

### "Architects' Critical Partnership"

Tony Moore

T. A. Baldwin, A.R.I.B.A.

Marek Żulawski

### The Architect's Rake-Off

SIR.—The following is a copy of a paper cutting published in the *Liverpool Evening Express* on Thursday, September 20, and is forwarded to you without comment:—

"Council houses would be cheaper but for the rake-off of these professional gentlemen, the architects," Alderman W. E. Power of Birkenhead, told the Institute of Housing Conference at Scarborough today. "The necessity of employing architects to get a proper building is raising the cost of houses," he said. "Before the war the houses used to be built on plans and specification. Now there seems to be something very suspicious knocking about, and the Ministry must know about it. Isn't it

a remarkable thing that the builders will not accept a contract unless there are quantities drawn? Those quantities cost money. You have to pay a percentage to the quantity surveyor, and so add appreciably to the cost of the houses."

Sometimes plans were not ready, for the builders were afraid to say anything in case they offended the architect. Alderman Power continued: "The Ministry must tackle the people who are too big to be spoken to—these professional gentlemen who are having a rake-off from housing. They are not necessary at all, for there are standard designs of houses and there is the commonsense of the local engineer."

Alderman Power also had a word to say about "the steel racket."

"I think," he said, "the Ministry have fallen down altogether because there are many authorities—particularly one or two I know of myself, who placed their orders at the beginning of the year and have no steel at all."

"Who has got the steel? They cannot get it and consequently the houses have been held up."

"TEN ARCHITECTS"

Chester

[Alderman Power's remarks are the subject of this week's first leading article.—ED.]

SIR.—I have just read the remarks by Alderman W. E. Power which were addressed to the Institute of Housing Conference at Scarborough. Such a libellous and ill-informed statement made by an alderman should be dealt with at a high level. As editor of the leading architectural Journal, and spokesman for our profession, it would be in the interests of all architects if you were to press for an inquiry by the RIBA into this civic leader's statement.

Already it is regrettable that so many local authorities still carry out housing schemes and all their building under an engineer, without inferring that architects can be dispensed with. One has only to scan the pages of the architectural journals to see how deplorably low is the general standard of architecture in this country. Imagine what the state of affairs would be if this alderman's suggestions were adopted by any of the one hundred local authorities to whom this statement was made.

Southport

VERNON H. LEE

### The Architect's Object

SIR.—John Summerson's criticism (AJ September 13) contains much superficiality

of statement. Architecture interprets the culture in which it is built. Architects reacted to the eclectic Renaissance and in their search for a true expression explored different problems. This exploration continues. The difference between problems explored and solved gives personal style; the style of the architect. The intuition of the problems involved—the expression of man's relation to the universe—gives the style of the culture.

All art must be in the cultural style to be meaningful to those who live in the environment. Eclectic art may be superficially pleasing but is empty in content. To be eclectic, architecture need not merely revert to past cultural styles. It can arise from a personal romantic concept in which intuitive symbolism is replaced by sentimental association. The winning design for Coventry Cathedral is in this category.

To suggest that contemporary architecture merely arises from a negative analytical approach is to accept the mediocre as a basis for discussion. In architecture in all cultures, planning and construction are never initially conceived as being the ends. They are always used as a means in the expression of an intuitive concept of a building.

For there are two concepts involved in architecture—a general and a particular. Each culture develops a concept as stated before. Obviously, if a cathedral is to be meaningful to us today and we accept that the Royal Festival Hall is contemporary, then both cathedral and concert hall will be in the same cultural style.

Within this general concept each building arises from the emotional demands of the architect, his concept of the building. That is, in a creation of a building, the architect imagines himself within and outside the building and designs to satisfy his own emotional demands, both conscious and unconscious. The concept of the building will be different as the emotional demands are different. This is Le Corbusier's poetry, when building is uplifted to architecture by the emotional demands of the architect. This, we are told, has not "the slightest relevance to a place of orthodox worship."

ANTHONY JACKSON

Brixton

### Design for Juveniles

SIR.—We were interested to see the House illustrated on page 348 of the JOURNAL for September 20, and we imagine in a few years' time the following dialogue being heard in North End, Hampstead, N.W.3:—

"DAD! Where are you?"

"Building a coal store in the yard."

"Have you seen Nurse?"

"Yes, she's in the kid's bedroom" . . .

"Oh, Nurse, where's Maggie?"

"She left here about half-an-hour ago, and if she hasn't lost her way, she should have reached the bathroom by now.—Why?"

"I thought she was looking after young Albert on the balcony—he's dropped his hammer through the floor, broken the dining room window, and now he's fallen through the railing! I'd better tell Dad to stop messing about with that coal store and fix some rabbit wire to the balcony . . . DAD!!"

Is our imagination too vivid, or do the people in Hampstead Heath lead a more settled life and control their children to better advantage than do we Northerners?

"THE ARCHITECTS' CRITICAL PARTNERSHIP"

Sheffield

## Laugh with a Sob

SIR,—The Town Hill Rest Precinct well deserved ASTRAGAL'S criticism (AJ September 20): what could one do but laugh—albeit with a sob at the end—at such a prospect. It is the only shred of enjoyment it will ever give.

Other similar "gardens" come easily to mind which merit harsh words: must we for ever withhold our indignation at that which is so obviously comfortless and barren in summer and winter alike?

London

TONY MOORE

## Cafes or Craggy Cliffs?

SIR,—In the past few months pressure of public opinion has caused the Ministry of Works to reconsider at least two of its major building projects: first the new Colonial Office then the "reconstruction" of Carlton House Terrace. General dissatisfaction has also been expressed with the appearance of most of the Government office buildings erected under the Lessor Scheme.

It is alarming that a body responsible to the public for the design of such a large volume of post-war building should show such an appalling lack of imagination and architectural appreciation in fostering these schemes, which will survive as our legacy to many future generations. The fact that the Colonial Office and Carlton House Terrace projects had reached such an advanced stage before they became public is regrettable in itself. It seems that the Ministry, fearing the consequences of publicity, proceeds with its plans in secret as long as possible and then, when the facts do leak out, disarms criticism by saying that it is too late for any major alteration to be made.

This unsatisfactory process seems to be starting again in the case of a site in Horseferry Road, Westminster, where building work has already begun on what promises to be another huge scheme. Surely it would be very much in the public interest for drawings of the intended building to be made available very soon so that any justifiable criticism can be made and acted upon.

In the meantime, we hear that part of the South Bank site is earmarked for Government offices. It would be very pleasant to think that the many delightful buildings which are there at present will be replaced by something equally worthy of this fine site; but one has only to look immediately across the river at the monstrous mountain of stone which is being raised in Whitehall Gardens to see an awful warning of what Government offices can, and usually do, look like. This year's Exhibition has shown us the wonderful possibilities of South Bank, with its restaurants, bars, fountains and terraces along the river. Are these newly won amenities to be retained in a permanent form, or are they to be swept away with indecent haste and replaced by great craggy cliffs of offices as lively and inviting, especially by night, as Whitehall, County Hall or the Colorado Desert? In view of the tremendous interest which has been aroused in the South Bank site, it would seem that the Ministry of Works, and any other authorities involved, would be well advised to take the public into their confidence and to let us see what their proposals are before the excavators and pile-drivers move in.

T. A. BALDWIN

London  
[ASTRAGAL made a similar suggestion on September 6.—Ed.]

## Homes for Murals

SIR,—In your last issue ASTRAGAL threw a somewhat nostalgic light on some aspects of the liquidation of the South Bank Exhibition.



The photograph above shows the new central laboratory at Cambridge for Spillers Ltd. It was designed by Lanchester and Lodge and was recently completed.

Having painted one of the murals, I remember the birth of this great exhibition as one of the happy periods in my life, not only because I was at last doing work connected with something real and necessary in relation to architecture—which had always been my ambition—but also because of the atmosphere of expectation and optimism connected with the whole venture. It seemed to me and to many others that a new and fruitful era in mural painting was about to dawn in this country. Unfortunately our hopes have been dashed, and—perhaps prematurely—a feeling of frustration is setting in.

Not only has nothing happened so far, not only have the art critics ignored the issues involved and failed to seize this opportunity to consider what was good and what was bad from the point of view of a possible recreation of the lost tradition in the integration of painting and sculpture with architecture, but we now hear that some of the murals which "do not find homes" following the close of the Exhibition may be auctioned as so much used timber or otherwise disposed of as scrap.

This is the country where even Sir Gerald Barry, as reported in the *News Chronicle*, dare not mention the word "culture" for fear of setting "certain newspapers feeling for the safety-catches of their revolvers." But—for better or worse—these murals represent a serious effort and illustrate the state of mural painting in this country, and, by inference, of our artistic culture. They could be preserved by placing them, free of charge, in government buildings, schools, the factories of the nationalized industries, canteens, trade union conference rooms and so on.

But there comes a "Grey Eminence" whose narrow mind decides everything: The Taxpayer. It appears that the Festival authorities have now but one thought—to reduce the deficit to a minimum. Every shilling helps.

This, it seems to me, makes the whole problem interesting to architects. Almost all the murals are on wooden panels and easily transportable. Many of them could be cheaply acquired. It would be interesting to see if architects are serious when they talk about the desirability of introducing painting to architecture. Here is their chance: ready-made murals to try out.

MAREK ZULAWSKI

London

## DIARY

*Exhibition of British Popular and Traditional Art.* Sub-title: Black Eyes and Lemonade. At the Whitechapel Art Gallery. Daily except Mondays, 11 a.m. to 6 p.m. Sundays, 2 p.m. to 6 p.m.

UNTIL OCT. 6

*London: An Adventure in Town Planning.* Exhibition of work by Assist. Professor Smigielski, staff and students of the School of Architecture, Polish University College. At ICA, 17-18 Dover Street, Piccadilly, W.1. Weekdays 10 a.m. to 6 p.m.

UNTIL OCT. 6

*New Timbers and Their Uses*, by R. P. Woods, Chief Scientific Officer, TDA. At Hereford College of Further Education, Newtown Road, Hereford, at 7.15 p.m.

OCTOBER 9

*Prestressed Concrete*, by O. J. Masterman, BRS. At the Sunderland Technical College, The Green, Sunderland, at 7.0 p.m.

OCTOBER 10

*The RIBA Form of Contract*, by C. Stanbury Madeley at the Building Department, North Staffordshire Technical College, Caudon Place, Stoke-on-Trent, at 6.30 p.m.

OCTOBER 11

*Social and Economic Developments in China.* A talk by Joseph Needham. Organized by the Students' Planning Group of the TCPA. At 28, King Street, Covent Garden, W.C.2, at 6.15 p.m.

OCTOBER 11

*Scottish Housing Since the War.* A paper to be read by R. J. Gardner-Medwin, Chief Architect and Planning Officer to Department of Health for Scotland. At the Annual General Meeting of The Housing Centre Trust, 13, Suffolk Street, S.W.1, at 6 p.m.

OCTOBER 16


*The Quantity Surveyor and the Building Contract.* A lecture by Arthur J. Willis. (Sponsor, The Institute of Quantity Surveyors.) At the Institute, 98, Gloucester Place, W.1. 6.45 p.m.

OCTOBER 24

*Exhibition of Architecture.* Sponsored by the Institute of Registered Architects. The above exhibition will be on view at the following places:—East Finchley Library (until Oct. 6); Thomas Parsons Showrooms, 70, Grosvenor Street, W.1. (Oct. 8-19); Council Office, Surbiton (Oct. 22-27); Building exhibition, Olympia (Nov. 14-28).




HARLOW NEW TOWN, ESSEX : OPENING OF



*The industrial estate forming part of the new town at Harlow was opened on September 24 by G. S. Lindgren, Parliamentary Secretary to the MOLGP. The buildings have been designed in the Harlow Development Corporation's Architects' Department under Frederick Gibberd, architect-planner, and V. Ham-*


*nett, executive architect. Above, centre, are two standard factories. 8 sectional factory units are seen to the right of these. Left, a factory under construction; Centre, top, and in the photograph below, are the laboratories for the British Hydromechanics Research Association. (See JOURNAL for June 7.)*



## THE INDUSTRIAL ESTATE



Above is a view of the two standard factory units when nearing completion; below, a ground floor plan of one of them. Its production area (of 13,824 sq. ft.) has a steel frame. The walls below cill level are of cavity construction (brick outer and breeze block inner skins); above cill level, vertical patent glazing, and from eaves to top of patent glazing the walling is of asbestos sheeting, lined with insulation boarding. The roof is flat, with monitor roof lights giving 7.5 per cent. average daylight factor over the whole floor. It is covered with bituminous built-up roofing on 2-in. wood wool slabs. The two-storey office block also has a steel frame, with cavity walls (brick outer and 3-in. hollow brick inner skins). In this, and the sectional factories, are contained light engineering, medical appliance and scientific instrument works. Four standard factories and five units of sectional factories are at present under construction. A six-acre site is being levelled for a glass-bottle manufacturer who will build his own factory, and work will begin shortly on two standard factories, four units of sectional factories and two other factories to be built by their owners.



## RIBA

*President Defends Profession*

A. Graham Henderson, the RIBA President has written to *The Liverpool Echo* which printed the comments on the architectural profession made recently by Alderman W. E. Power, of Birkenhead, and discussed in our correspondence columns on the opposite page and in our first leading article:—


"My attention has been drawn to your issue of September 20 in which remarks made by Alderman W. E. Power of Birkenhead at the Annual Conference of the Institute of Housing are quoted. He is alleged to have said in effect that but for the employment of architects to design the houses and surveyors to prepare bills of quantities on which the builders base their competitive tenders for the work, Council housing would be cheaper.

"There are certain statements made at public meetings and quoted in the public press from time to time which are so manifestly absurd that it seems unnecessary to refute them, but when a subject of such vital importance as housing is referred to in an irresponsible manner I feel that the remarks made cannot be ignored.

"I am certain that a responsible body such as the Institute of Housing would realize the absurdity of attempting to carry out housing without proper professional assistance, apart from the fact that the Ministry of Health have directed the local authorities in their various housing manuals and instructions to seek the best possible professional skill, I think it is fair to state that not only those responsible for the carrying out of housing schemes but also the general public are now aware that the quality of the houses built is almost as important as the quantity if we are to avoid the creation of further slum areas, the existence of which in the past have caused, to a large extent, the problem of re-housing.

"The enormous improvement which has been effected in the standard of housing for the last few years has been due to the efforts of architects who have achieved not only improved design in houses but, by their professional skill, have effected economies in planning and convenience of arrangement. This statement is borne out by the circular sent out from the Ministry of Local Government and Planning to housing authorities in April last dealing with what steps can be taken to secure a reduction in the cost of house building without prejudice to essential standards. The Minister expresses the view that many able architects have shown that it is possible by skilled planning to maintain the existing standards within smaller

NEW LONDON SHOWROOM AND OFFICES, FOR




The London showroom and offices for Richard Haworth & Co., Ltd., illustrated here, were designed by F. M. Gross. The available space was narrow and elongated and is lighted at only three points. The entrance lobby, typing space, salesroom and showroom are combined in one room, the showroom being separated by a curtain which runs in a recessed ceiling track. A false ceiling was suspended to obtain the required depth for artificial light and the air conditioning system. All irregularities in the existing walls have been straightened out by panelling and

screen walls. The top photograph shows the four salesmen's desks, which are attached to a built-in filing cabinet with roller shutters. The heating system is behind the counter, with cold air inlet above and warm circulation grills below. When more space is needed in the room these tables can be detached. Above, left, a view down the length of the room, with the showroom at the far end. Above, right, the manager's office with a built-in fitment on the far wall in mahogany and abura. The curtains are green, the upholstery lime green, and the carpet fawn.



## MANCHESTER TEXTILE FIRM



*The street entrance is shown in the photograph on the left.*

*The facade is faced with Italian cippolino marble, the outer framing and the door are of teak and the door frame and lettering in coinage bronze.*

*Below this photo is the receptionist's desk and enquiry counter in macoree with routed lines. The top and shelf are of sycamore. A ribbed glass screen behind separates the area from a private interviewing office. Below, a corner of the showroom which is on a higher level. The light railing is of wood and brass.*

*Above the heating grills there is a small display case. The general contractors were Messrs. J. Gerrard & Sons, Ltd. For sub-contractors see page 424.*



total superficial areas than those previously prescribed. The circular goes on to state that if plans are prepared by a qualified architect, provided they comply with the conditions in the circular, they need not be submitted for approval to the Ministry.

"Regarding the necessity of employing quantity surveyors, it will be obvious to anyone who knows anything about tendering for housing that without a properly prepared bill of quantities it would be quite impossible to check tenders received and that if each builder had himself, individually, to prepare such a bill the cost of doing so would be reflected in his estimate."



*This feature covers aspects of legislation, parliamentary news or statutory rules and regulations which are of special significance to the architectural profession.*

## ERNEST WATKINS

## The Architect and Current Affairs

Among the papers read at the recent Town and Country Planning Summer School at Oxford was one by H. W. Wells entitled *A Critical Analysis of the Working of the 1947 Act*. Mr. Wells is far from being a harsh critic of the Act, or of intentions behind it. On the contrary, in some respects he appeared as an apologist, and in doing so displayed two of the common failings of apologists, their tendency to equate intention with performance and their tendency to regard planning under the 1947 Act with blinkered eyes.



In his discussion of the sections of the Act which deal with the preservation of buildings of historical or architectural interest, Mr. Wells mentioned the common complaint that it may well be idle to list a particular building for preservation if there are no funds available to preserve it. He continued: "We must not, however, under-estimate the extent to which 'listing' has created a consciousness of what is worth preserving. People are becoming increasingly proud of owning a 'listed' building. If planning consists of no more than writing the name of a building on a certain list in a public office and then hoping that someone, owner or third party, will find money to preserve it, then, to me, it is pretty well indistinguishable from plain anarchy. (Granted anarchy may preserve




## FESTIVAL INN, DORSET ROAD, LAMBETH,




Old licensed premises belonging to Ind Coope & Allsopp, Ltd., in Dorset Road were required for demolition by the LCC before the war in order to continue a housing scheme. A new site on the opposite side of the road was made available, but the war held up the work, and the new premises, designed by W. J. Witham, Regional Architect to the brewers, have only recently been completed. The restricted area of the site necessitated the planning of the public rooms on two floors, and storage of all kinds had to be at basement

Ground floor plan [Scale:  $\frac{1}{4}$ " = 1' 0"]

First floor plan



Second floor plan



level. The separate outside staircase, which provides a private entrance for the tenant's flat, also acts as an emergency fire escape for the first floor lounge, which is seen above, left. The mural is by Stanley Mills. External walls are mainly of 13½-in. brickwork and 11-in. cavity walls for parapets. The facing bricks are 2½-in. light russet brown, hand-made. The fireplace

LONDON, S.W.8.

Sections A-A and B-B (Scale:  $\frac{1}{8}'' = 1' 0''$ )

wall in the public bar, seen below, is faced with 2-in. bricks, and murals here, and in the saloon bar (right), are by William Morris. Below, on the opposite page, is a photograph from Dorset Road looking north-east and above is a view looking south-east. The general contractors were Gee, Walker & Slater, Ltd. Sub-contractors on page 424.



many buildings, but we did not need a 1947 Act for its creation."

Mr. Wells then passed to *Tree Preservation, Agriculture and Location of Industry* (the arrangement of subjects is his, not mine) and said this, and this only, about location of industry: "Industry is moving into areas of possible unemployment. There is plenty of evidence of the effectiveness of the national policy in these directions." The only comment I can find breath enough to make is that not even a parliamentary secretary to a ministry could have produced a statement more bland, or more evasive.

But Mr. Wells became more alive and thought-provoking when he passed to those parts of the Act (VI and VII) dealing with development charges. His account of the criticisms of these parts of the Act included most of those often made at present. Development charge, he said, was—in practice—a tax of development and redevelopment, and a deterrent to useful redevelopment in particular, and the problems of valuation that it raised were insoluble. (Insoluble, that is, to a surveyor attempting to use the recognized methods of his profession.) In Mr. Wells' view, the conditions under which such selections had to be made allowed only of theoretical valuations, since the valuation must be based on "market values" in circumstances which could never arise in an actual market.

The speaker went on to discuss what amendments to these parts of the Act were first, desirable, and second, possible. His first point was that the 1947 Act was framed, after the investigation made by the Uthwatt Committee, to provide a solution to the compensation-betterment problems of the thirties, but that these problems were quite different from those existing today, for these reasons: (a) The dominant factors in development today were first, shortages and, second, cost of material and labour (not cost of land). (b) Shortages, gave value to a licence to build, not to permission to develop. (c) Cost ruled out a great deal of private development of the kind that gave rise to the problems the Uthwatt Committee attempted to solve. (Will anyone ever build houses, on an extensive scale, for letting?) (d) Today the value of agricultural land had risen, and so had diminished the change in value attributable to anticipated change in use.

The conclusion Mr. Wells reached was that the policy on which the development charge is based had become increasingly divorced from reality, in that the administrative act which adds value to land is the grant of the building licence for it, yet, by definition, that licence is not a thing which should have value, since it is only granted when some need is established. In short, Mr. Wells infers, but does not say, that the government should impose a fee on the grant of a building licence (parallel, perhaps, to the sum collected by the revenue for "monopoly" value on the grant of a new wines and spirits licence?). Over the development charge he is more explicit. He suggests that the simplest solution might be to drop both the payment of compensation for restrictions imposed and the collection of betterment for freedoms granted, and he quotes a sentence from MOLGP's Survey to hint that the authorities might be glad to settle for that, too.

Has the 1947 Act been in operation long enough to have become, so to speak, a vested interest, too established to make any radical change likely? I cannot feel that is so. Reform of this Act does not lend itself to any popular slogan, so I imagine that both parties will steer clear of it in any election campaign. Nevertheless, it is impossible to escape the feeling that substantial amendments to that Act may become solid possibilities in the not too distant future, which adds considerably to the value of the kind of practical analysis of the experience gained since 1948 contributed by Mr. Wells.


## PRIMARY SCHOOLS



at LEAGRAVE, LUTON, BEDFORDSHIRE

designed by HOWARD V. LOBB and PARTNERS

The junior and infants' schools, which are situated in the valley of the River Lea between Legrave High Street and a new housing estate, were opened last week by the Chairman of the Bedfordshire County Council. The 16-acre site, on which a nursery school will be built later, has been planted in accordance with a scheme of landscaping designed by H. F. Clark and will contain a group of tall beeches along the line of the river. The site is bisected by Strangers Way, a road which has been extended to connect the High Street with the new housing estate.

*Junior assembly hall from the south-west.*





Site plan

Plan of junior school  
[Scale:  $\frac{1}{8}$ " = 1' 0"]

PLAN.—The junior school accommodates 480 boys and girls in twelve teaching rooms, which are arranged in three groups. The buildings are planned


*Above, general view of junior school, from the south-east. Right, looking through the entrance doors into the assembly hall.*





in a series of compact blocks for economy and because it is thought that very long blocks of classrooms are rather intimidating to a child. Each classroom has a French window leading to a paved outside teaching space. The assembly hall, which opens off the main entrance hall, is intended for use by the local community out of school hours. There is a film projection room, but the MOE would not

#### KEY

1. Classrooms.
2. General purposes rooms.
3. Girls' lavatories
4. Boys' lavatories
5. Upper part of boiler room.
6. Drying room.
7. Staff room.
8. Staff cloakrooms and lavatories.
9. Head teacher.
10. Dining hall.
11. Kitchen.
12. Medical inspection room.
13. Waiting room.
14. Assembly hall.
15. Play shed.
16. Motor room and garden store.







## INFANTS' SCHOOL

at LEAGRAVE, LUTON, BEDFORDSHIRE  
designed by HOWARD V. LOBB AND PARTNERS


sanction a stage for amateur theatricals and at present there is only a small platform. The infants' school, which accommodates 360 children in nine teaching rooms, was the second to be built and was partly affected by recent cost restrictions.

**FINISHES.**—The greater part of the building has pitched roofs and brick walls of a variegated plum-red colour to be in harmony with the nearby houses and the general character of the countryside. The sloping roofs are covered with cedar shingles. The interiors mostly have walls of plain brickwork, the dadoes, above which the brickwork is painted, being the same as the outside facing bricks. The floors of the classrooms and dining hall are of beech blocks and in the assembly hall beech boards. The ceilings are of insulating board sprayed with a mix containing vermiculite, which has good insulating properties.

The general contractors were T. & E. Neville, Ltd.  
For sub-contractors, see next week's issue.

*Top, assembly hall and main entrance looking north-east. Above left, the staff room. Above right, typical infants' classroom.*

Plan of Infants' School (Scale:  $\frac{1}{8}$ " = 1' 0")  
For key to figures see previous page




## FLATS

in HAMPTON ROAD, TWICKENHAM, MIDDLESEX  
designed by ERIC LYONS and G. PAULSON TOWNSEND

Owing to a future road widening scheme, this block of six flats, known as Box Corner, is set well back from the Hampton Road. Access was restricted to Third Cross Road and so the main entrance to all except the two flats at the north end of the building is by a paved terrace leading to the glazed screen in the stair hall, which faces south. All the flats have living rooms with a south or west aspect. Box Corner has been built for a private client, but the tenants are from the Borough housing list.

*View looking north with the main entrance on the left.*





Ground and part first floor plans [Scale:  $\frac{1}{4}$ " = 1'0"]



Section B-B



Section A-A


## FLATS

in HAMPTON ROAD, TWICKENHAM, MIDDLESEX  
designed by ERIC LYONS and G. PAULSON TOWNSEND

**SITE.**—At the rear of the building are placed garages, a cycle store and drying yard, with access in the north-west corner of the site. The terrace on the south is separated from the main garden by a low brick wall of dark red facing bricks. On the west side of Third Cross Road a further site is to be similarly developed, but with flats 3 storeys high.



The south-west facade facing Third Cross Road. The drive on the left leads to lock-up garages.



*Looking west at the main entrance and stair hall.*

**PLAN.**—Each flat has a total floor area of 730 sq. ft. including the balcony or garden room, which is the minimum area for which a licence can be obtained. It is considered that this large recessed balcony amply compensates for the slight reduction in room sizes. The kitchen, which is entered from the

living room, is planned with room for a breakfast table.

**CONSTRUCTION.**—There are weight-bearing walls throughout, supporting the reinforced-concrete hollow-tile floor and roof. The external cavity






Main hall and first floor landing.




The main staircase from the entrance hall.

## FLATS

in HAMPTON ROAD, TWICKENHAM, MIDDLESEX  
designed by ERIC LYONS and G. PAULSON TOWNSEND




Section through landing [Scale:  $\frac{1}{4}'' = 1'0''$ ]



Section A-A

Section B-B

Section C-C




Main staircase, ground and first floor plans [Scale:  $\frac{1}{16}'' = 1'0''$ ]





walls are 10½ in., comprising 4½-in. external brickwork and 4-in. internal hollow-clay blocks. The main staircase is formed of precast concrete units cantilevered from the back wall of the hall.

**FINISHES.**—The ground floor slab is waterproofed with bitumen membrane and finished with linoleum. The first floor slab is finished with ¾-in. boarding on 2-in. battens, laid on a glass-wool blanket. Treads and risers of the main staircase and the floor of the hall are covered with compressed rubber tiles. The roof is insulated with a foamed-slag screed and finished with asphalt. Windows are painted white and cills dark blue. The boarding to the stair hall screen and the balcony balustrades are of red cedar, oiled to retain the colour. Internally, all flats are distempered or painted white except for a wallpaper panel on the fireplace wall of the living room.



*Above left, typical first floor living room with open fireplace. Below, the glazed screen dividing the living room and garden room in a first floor flat.*






The main entrance door has a wide projecting frame and is set in a glazed screen with panels of vertical boarding.

## FLATS

in HAMPTON ROAD, TWICKENHAM, MIDDLESEX


designed by ERIC LYONS and G. PAULSON TOWNSEND




Section B-B and detail of jamb [Scale: 1 1/2" = 1' 0"]

**SERVICES.**—Hot water is provided by the back boiler in the living room fireplace, supplying the cylinder which has an immersion heater for summer use in the adjacent cupboard.

The general contractors were the Eden Residential Construction Co., Ltd. For sub-contractors, see page 424.



Elevation, plan and sections A-A and C-C of main entrance door [Scale: 1/2" = 1' 0"]



back  
the  
mer

ntial  
see



nce









# SPECIALISED FITTINGS | LAVATORY CUBICLES

43.Z3


The Architects' Journal Library of Information Sheets 331. Editor: Cotterell Butler, A.R.I.B.A.




● TILE PARTITIONS WITH TERRAZZO POSTS.




TERRAZZO SLAB PARTITIONS WITH TERRAZZO POSTS.




UNIT FOR TILE PARTITIONS.




CENTRE POST FOR TILE OR TERRAZZO SLAB PARTITIONS.




ALTERNATIVE LINTELS.




WALL POST. TILE CUBICLES.



CORNER POST.



WALL POST. TERRAZZO SLAB CUBICLES.



CORNER POST.

note: cross-sectional sizes of posts and lintels may be varied to suit requirements

## TILE OR TERRAZZO SLAB LAVATORY CUBICLES.

Manufacturers: Carter and Co. London Ltd. and Art Pavements and Decorations Ltd.

### 43.Z3 TILE OR TERRAZZO SLAB LAVATORY CUBICLES

**This Sheet** describes two types of lavatory cubicle : one composed of double-sided glazed tile partitions and precast terrazzo posts and lintels, and the other of precast terrazzo slab partitions, posts and lintels.

#### Tile Cubicles

**Partitions :** These are prefabricated from specially keyed 6 in. by 6 in. tiles and galvanized iron connecting lugs.

The introduction of tiles other than 6 in. by 6 in. for decorative purposes is likely to weaken the construction and is not recommended. An overall size of 6 ft. by 5 ft. should be regarded as the maximum. A semi-recessed paper holder may be incorporated in the partition if required.

**Posts :** These are of reinforced terrazzo and are grooved to take the partitions. When the partition is to be supported clear of the floor, the stopping of the groove at the required height from the floor level forms a bearing surface for it. At the top a cramp is fixed from the top edge of the partition to the top of the post. The reinforcing rods project above the post to engage in holes left in the underside of the lintel.

**Lintels :** These are of reinforced terrazzo and are connected to the posts as described above. The lintel returns are grooved on the underside to accommodate the tops of the partitions.

**Fixing at wall :** The tile connecting lugs at the edge of the partition are grouted into the brickwork.

#### Terrazzo Slab Cubicles

**Partitions :** The terrazzo slab partitions are 1½ in. thick and are reinforced with ½ in. diameter rods at 9 in. centres vertically and horizontally. An overall size of 7 ft. by 6 ft. 6 in. should be regarded as the maximum.

**Posts :** These are as described above for tile cubicles. Corner posts are cast in one piece with the end partitions.

**Lintels :** These are of reinforced terrazzo and, with the exception of the returns, are holed to receive the projecting rods of the posts. The returns are cast in one piece with the end posts and partitions.

**Fixing at wall :** Where the wall linings are of terrazzo or tiles the partitions are tightly butted to the brickwork. Where the wall is fairfaced brickwork or plaster finished the partitions are housed in a groove cut into the brickwork. Alternatively, lugs may be cast in the edge of the partitions for grouting into the wall face.

#### Fittings

Threaded brass sleeves are cast in the posts to take the hinge screws and are tapered to prevent their being dislodged.

#### Finish

Both types of cubicle are available in a wide range of colours. A combination of colours may be used, e.g. one colour for partitions and another for posts and lintels.

#### Compiled from information supplied by :

**Carter & Co., London, Ltd.**

Head Office : 29, Albert Embankment, London, S.E.11.

Telephone : Reliance 1471.

Works : Poole, Dorset.

Telephone : Poole 125.

**Art Pavements & Decorations Ltd.**

Address : St. Paul's Crescent, Camden Town, London, N.W.1.

Telephone : Gulliver 2226.

Telegrams : Granulemos, Norwest, London.

(Both companies are members of The Carter Group.)

Copyright Reserved.

The Architects' Journal Library of Information Sheets.

Editor : Cotterell Butler, A.R.I.B.A.









## SPACE HEATING | UNITS | GAS

29.C3


The Architects' Journal Library of Information Sheets 332. Editor: Cotterell Butler, A.R.I.B.A.



PRINCIPAL HEATING APPLIANCES.



SUPPLEMENTARY HEATING APPLIANCES: FIXED TYPES.



SUPPLEMENTARY HEATING APPLIANCES: PORTABLE TYPES.

FIXED TOWEL RAIL.

## 29.C3 DOMESTIC GAS SPACE HEATING BY INDEPENDENT APPLIANCES

This Sheet summarises the common types of domestic gas space heating appliance.

## General

Comfortable warmth can be achieved by a judicious combination of radiant and convected heat and air movement. A gas fire fitted to a flue provides a high temperature source of radiant heat and sufficient air movement for comfort and a gas convector heater has the function of an air warmer. The sizes of these heaters to perform a particular task will depend largely on the size and construction of the room to be heated and the use to which it is put. The gas undertaking will give advice on the sizes and types of heater required.

## Principal Heating Appliances

These are all radiant heaters and some are provided with a convection component.

**Hearth types:** These are designed for fixing in front of a fireplace with a flue. Input ratings range from 10,000 to 20,000 B.Th.U./hr.

**Inset types:** These are for fitting into a fireplace in the same position as a solid fuel grate with an air space above opening directly to the flue. Input ratings range from 10,000 to 24,000 B.Th.U./hr.

**Panel types:** These are designed for fitting into a prepared wall recess connected to a flue and arranged so that the burner level of the fire is at least 9 in. above the floor. Input ratings range from 10,000 to 20,000 B.Th.U./hr.

## Supplementary Heating Appliances: Fixed Types

These are all convector heaters, although some are designed to provide additional radiant heat.

**Flueless floor types:** These are for permanent installation without connection to a flue. Input ratings range from 2,000 to 12,000 B.Th.U./hr.

**Flueless wall types:** As above, but wall mounted. Input ratings range from 2,000 to 4,000 B.Th.U./hr.

**Balanced flue convection types:** These are designed to fit on an outside wall. The flue is carried through the wall and air for combustion is drawn from the same position as the flue terminal. The burner chamber is therefore sealed from the room. Input ratings range from 5,000 to 10,000 B.Th.U./hr.

**Towel rails:** These are generally water or oil filled rails heated by a small gas burner. Input ratings range from 500 to 1,000 B.Th.U./hr.

## Supplementary Heating Appliances: Portable Types

**Types for use with flue:** These are designed for temporary connection (by flexible tube) to any gas point which conveniently enables the fire to stand in a fireplace and utilize the flue. Input ratings range from 5,000 to 12,000 B.Th.U./hr.

**Flueless types:** These may be connected to any convenient gas point by flexible tube. Input ratings range from 2,000 to 5,000 B.Th.U./hr.

## Installation

For details of laying and fixing of installation pipes, see Sheet 37.D2. Control cocks may be concealed under floor boards, in the skirting or behind the appliance, but should be readily accessible. Cocks with removable keys are available for nurseries, etc. Where a fire is to be fitted on a floor made of com-

bustible material, it should be supplied with an incombustible hearth extending at least 12 in. in front and 6 in. on both sides.

**Hearth types:** The jambs and lintel of the fire opening should be in one plane and the fire should entirely cover the fire opening. The lower part of the fire forming the rear wall of the burner housing should form an effective seal on the hearth to prevent chimney draught from interfering with the proper operation of the burner.

**Inset types:** It is desirable that a baffle be inserted in the chimney above the fire to collect falling material and to prevent an excessive ventilation rate. When dog or basket grates are fitted in a recess, the height of which is more than 3 ft., a screen of non-combustible material, e.g., glass, metal, etc., should be fitted across the front at the top of the recess.

**Panel types:** These should be fitted in accordance with the manufacturer's instructions. Metal fixing bolts of approved design, and not wood or fibre plugs, should be used. Provided that the fire is fitted so that the burner is 9 in. minimum above the floor level, a hearth is not required. Fires of input rating higher than 15,000 B.Th.U./hr. should not be fitted to precast concrete flues having internal dimensions of 12 in. by 2½ in. or less.

**Supplementary heating appliances:** Appliances of the fixed type should be rigidly secured to the floor or wall. Portable heaters should have a gas control cock on the inlet end of the tube. The cock and tube should be of a pattern approved by the gas undertaking.

## Ventilation

**Heaters fitted to flues:** See Sheets 30.B1 and 2.

**Flueless heaters:** The gas consumed should never exceed 500 B.Th.U. per 100 cu. ft. of room space, and heaters should not be fitted in rooms which have neither air brick nor flue. Air bricks should ventilate directly to the open air or to a lobby or corridor ventilated directly to the open air. The total minimum unobstructed cross-sectional area of air bricks should be as follows:—

Cubic capacity of room	Unobstructed area of air bricks	
	Directly communicating to open air	Communicating to lobby or corridor
Up to 2,000 cu. ft. . .	20 sq. in.	40 sq. in.
2,001 to 3,000 cu. ft. . .	30 sq. in.	60 sq. in.
3,001 to 4,000 cu. ft. . .	40 sq. in.	80 sq. in.
For each additional 1,000 cu. ft. or part thereof . . .	10 sq. in.	20 sq. in.

Compiled from information supplied by:

## The Gas Council

Address: Gas Industry House, 1, Grosvenor Place, London, S.W.1.

Telephone: Sloane 4554.

Telegrams: Gascil, Knights, London.





IN  
QU  
TH

The  
rece  
the  
gre  
isst  
we  
stre  
tern  
the  
Do  
wit  
giv  
sys  
com  
art  
we  
to

Br  
whi  
load  
to  
use  
is a  
up  
are  
abl  
and  
la)  
of  
equ  
stre  
on  
row  
a n  
bod  
of f  
ten  
app  
the  
ben

the  
mo  
rec  
to  
of  
con  
equ  
at  
stra  
hei  
a r  
(Fi  
If  
to

INFORMATION CENTRE · INFORMATION SHEETS  
 QUESTIONS AND ANSWERS · CURRENT TECHNIQUE  
 THE INDUSTRY · PRICES · TECHNICAL ARTICLES

## TECHNICAL SECTION

*The subject of prestressed concrete received considerable attention at the recent Building Research Congress (reported in the last three issues of the JOURNAL), and last week a symposium, entitled "Prestressed Concrete Statically Indeterminate Structures," was held at the Institution of Civil Engineers. Donovan Lee, whose name, coupled with that of McCall, has been given to one of the most successful systems of applying prestress to concrete, wrote us the following article. Part II will appear next week, and the week after we hope to report on the symposium.*

### PRESTRESSED CONCRETE

By Donovan H. Lee  
 (Part I)

Briefly, prestressed concrete is concrete in which the bending tension induced by the load is eliminated by applying a compression to it prior to loading. The usual example used to explain the principle of prestressing is a row of books, which cannot be lifted up from the ends in one piece unless they are pressed together. As the books are unable to resist tension between one and another, the compressive prestress (see Fig. 1a) which is applied right through the row of books from end to end must at least be equal to the intensity of the tensile bending stress which would be created by the length of the row. It is well known that in any length of a member spanning in the same way as these books, compression is caused at the middle of the span at the top and equal and opposite tensile stress on the underside. The previous application of the prestress then neutralizes the tension that would normally occur. The bending tension caused by the weight  $W$  on

the span 1 is  $f_t = \frac{Wl}{8Z}$  where  $Z$  is the

modulus of the cross-section ( $bd^2/6$  for a rectangular section). If the prestress force is to be the minimum necessary, the best level of application is that which will cause a compressive stress at the bottom surface equal to the bending tension and no stress at the top surface. To achieve this the prestress needs to be applied at one-third of the height up from the underside in the case of a member with a rectangular cross-section (Fig. 1b).

If the prestress is increased it is possible to support other weights (see Fig. 1c) on the

row of books without a collapse occurring. There is a limit however to the load that can be supported because the stress at any point must not exceed the safe compressive stress at any stage of loading. The main points of the design will be shown to be readily covered by simple expressions but the application of them involves practical considerations which cannot be briefly dealt with here.

It is first desirable, however, to make clear why concrete is a material which is particularly suited to prestressing, and what are the advantages obtained by this as compared with normal concrete with mild steel reinforcement. Any material which is considerably weaker in tension than in compression, such as concrete or cast iron, can benefit by prestressing as this provides a means of controlling the stresses to suit the natural properties of the material. Thus, with prestressed concrete the whole of the section can be utilized, unlike normal reinforced concrete where that part of the concrete section which is subject to tension does not contribute directly to the bending strength. Also, the maximum steel stresses that can be permitted in reinforced concrete are controlled principally by the size of the hair cracks, which prevents the use of high grade steels. This is a distinct disadvantage as the ratio of cost to useful steel stress decreases with increase of the steel stress. Thus, for instance, if the strength of high tensile alloy bars with an ultimate strength of 70 tons per sq. in. as used in prestressed concrete could be utilized fully in reinforced concrete, the cost of steel as compared with ordinary mild steel reinforcement would be halved. With prestressed concrete this limitation of steel stress does not exist as the steel is tensioned whilst it is still unbonded to the concrete and thus does not transmit its strain to the adjacent concrete. In fact, in view of certain losses in prestress due to volumetric changes in the concrete (such as shrinkage), a high initial prestress in the steel is most desirable as this reduces the percentage losses. Prestressing also permits the use of high grade concrete which also has a more favourable cost-stress ratio than normal reinforced concrete. By applying a compressive stress to the concrete the resistance to shear is very greatly increased. This generally makes mild steel shear reinforcement unnecessary and allows the use of relatively narrow sections.

A unique property of prestressed concrete beams which is often taken advantage of is the tendency to camber upwards on prestressing, thus bringing the dead-load forces (such as the weight of the beam) into operation simultaneously with the prestressing forces. By increasing the eccentricity of the prestress above that required to give the triangular stress distribution ( $h/6$  in Fig. 1b) these dead load moments can be counteracted so that the resultant stress due to prestress and dead-load is still triangular (diagram 1 plus diagram 2 = diagram 3, Fig. 1c). This means that practically all the dead-load can be "absorbed" without increase of section or prestress merely by lowering the prestressed bar or cable at the centre but not at the ends.

In view of these factors the use of prestressed concrete usually leads to much smaller sections than reinforced concrete and in building construction it frequently rivals cased steel joists for shallowness. In addition, the "crackless" concrete is not only

itself more resistant to the weather, particularly to the effects of polluted atmospheres and sea-water, but the access of moisture and industrial fumes to the prestressing steel is prevented. The general absence of shear reinforcement also means there is usually no steel near to the concrete surface and liable to exposure by surface damage to the concrete.

#### METHODS OF PRESTRESSING

Basically there are two main methods of prestressing:

1. *Pre-stressing*, where wires of  $\frac{1}{2}$  in. dia. and up to about 0.2 in. dia. are stretched between abutments and held under high tensile stress whilst the concrete is placed in moulds around them. After the concrete has hardened sufficiently the wires are released and cut, and in trying to regain their original length they impart a compression to the concrete by virtue of the bond between it and the wires. As the stress transfer between the concrete and the steel is caused by mutual surface action (i.e. bond) there is an upper limiting value for the ratio of area and circumference for a given steel stress, which for a steel with an original prestress of about 70 tons per sq. in. restricts the maximum wire size to about 0.2 in.

2. *Post-tensioning*, where the concrete is cast first with longitudinal ducts for high tensile bars or cables composed of a number of parallel wires. After the concrete has hardened the bars or cables are threaded through the ducts, tensioned by a hydraulic jack and then anchored at their ends against the concrete. Alternatively the cables or bars may be in sheaths which are placed before casting of the concrete, the sheaths preventing the concrete from reaching cables or bars and allowing free movement. The reaction of the anchor plates against the concrete imparts a prestress to the concrete which is prevented from buckling by the bars or cables being in contact with it and which resist any lateral displacement.

There are two important pre-tensioning methods in general use. However, lack of space only allows mention of the two principal ones. One of these, generally known as the "long line" method and sometimes as the Hoyer method, utilizes casting beds of great length, the wires being stretched from end to end and the members cast with small gaps between them to allow the wires to be cut after the concrete has hardened, so that a dozen or more members may be cast in each line. (Fig. 2a.) This system is largely used for making prestressed railway sleepers (Fig. 2b) and also for floor joists, piles and beams. In the other method individual moulds are used and these moulds are made strong enough to hold the wires in their stretched condition until the concrete is set and sufficiently hardened. (Fig. 3.) With this latter method curing is normally accelerated by steam or immersion in hot water so that the moulds are brought back into use again in 5 hours, or overnight. With the long line method steam curing is also sometimes used, either by using jacketed moulds connected to steam mains or by hoods applied over the moulds after concreting. The outlay on plant and equipment is considerably greater for the long-line than the individual mould method but the latter uses more expensive moulds which also necessitate a fairly large capital expenditure. For small productions, particularly where space is limited the individual mould method is normally the more economical. However, it suffers from certain technical difficulties connected with the temporary wire anchorages which make it less popular than the long line process.

For use where numbers of members of small or medium length are required of the same or similar section. As bond is depended upon to transfer the tension in the wires to create the compressive prestress in the concrete, there is no cost incurred in end anchorages. Because of this both pre-tensioned systems have a cost advantage

where the length of the members is short, in spite of the heavy capital costs which have to be written off. As the length of a member increases the relative cost of the anchorages decreases and a point is reached where post-tensioning becomes cheaper. The exact length at which this occurs depends on various factors.

Generally speaking pre-tensioning is usually cheaper up to 20 ft. and post-tensioning above 25 ft., but these figures can only be a rough guide as each case differs. Thus pre-tensioned piles up to 60-ft. long and post-tensioned railway bridge slabs of only 12-ft. span have been made apparently economically.

Apart from the reduced capital costs there are some other advantages when using post-tensioning. Whereas pre-tensioning is only really suitable for precast work, post-tensioning can and is also used for *in situ* construction. This extends its scope to the largest engineering works and in fact there appears to be no upper limit of size beyond

which post-tensioning cannot be used. Another technical advantage arises from the ability to curve the bars or cables thus changing the distribution of prestress along a member to correspond with the varying moments. With pre-tensioning, as the wires are straight, this can only be achieved by varying the section, and this may clash with aesthetic or functional considerations. A third advantage is the reduced loss of prestress caused by shrinkage and creep of the concrete, which will be discussed later.

On the whole, post-tensioning is considerably more flexible than pre-tensioning which really can only be used for the simple type of structural elements such as simply-supported beams and not for continuous beams, portal frames and other constructions in which several members are formed into one assembly by stressing.

Typical of post-tensioning systems are, in chronological order, the Freyssinet, Magnel and Lee-McCall systems. The first two use cables of high tensile wires 0.2 in. dia. with

an ultimate strength of 100-110 tons per sq. in. and an initial prestress of approximately 60 tons per sq. in.; lately, however, 0.27 in. dia. wires with an ultimate strength of 90-95 tons per sq. in. have also been introduced. The Lee-McCall system employs alloy steel bars up to 1½-in. dia. with an ultimate strength of 66-72 tons per sq. in. and an initial prestress of 42 tons per sq. in.

The Freyssinet cable may contain from 12 to 20 wires arranged concentrically about a central spiral. The wires are held pressed to the spiral at intervals by adhesive tape and may be surrounded by a 30g black iron sheath if required to be cast in the concrete instead of threading through pre-formed ducts. The cable is stressed by fixing the ends of the wires in pairs in a special jack, stressing and anchoring in a conical concrete wedge as shown in Fig. 4b. This wedge consists of two parts (Fig. 4a); the female section is usually cast into the concrete and the plug driven home by an auxiliary ram incorporated in the stressing jack after the




Fig. 1a.





Fig. 1b.

Fig. 1c.  
Principles of prestressed concrete.

# Big Three — leaders in the world of paint



*Duresco the King of Water Paints—the famous oil-bound, washable distemper, first of its kind invented and still the best*

*Silcolac Hard Gloss Paint, without equal in its class for durability and working qualities. Hygienic, anti-corrosive, damp-resisting*



*D.E.C. Duresco Emulsion Coating—An entirely new, entirely different type of wall paint. Easy to apply, gives a superb finish and possesses outstanding durability, inside and out*

Send for the  
Duresco File of Information Sheets and Tint Cards

## Duresco Products

See us  
on Stand Nos. 174  
Row H, 209 Row J  
at the  
**BUILDING  
EXHIBITION  
OLYMPIA**  
Nov 14 - 28

DURESCO PRODUCTS LIMITED, CHARLTON, LONDON, S.E.7






*"I cannot...make shoes  
like a shoemaker..."*

Wellington's reply to the praises of  
a flattering admirer claiming that  
he was superior only in his own field.

**WELLINGTON**  
TUBE WORKS LTD

FOR STEEL TUBES AND  
STEEL TUBE FABRICATION

HEAD OFFICE & WORKS • GREAT BRIDGE • TIPTON • STAFFS




## Puzzled?

If ever you find yourself in difficulties  
when working with laminated plastics,  
this may interest you. We are continually  
developing better ways of fixing WARERITE  
Materials, and when it comes to solving problems,  
we haven't been beaten yet! So when you  
strike any tricky snags put our technical staff on their  
mettle—they're only too glad to help. Many  
useful hints are given in recent Warerite booklets—  
if you would like copies of them or advice  
don't hesitate to write or 'phone—


**WARERITE**

REGD. TRADE MARK

LAMINATED PLASTICS



MADE BY WARERITE LIMITED (UNIT OF BAKELITE LTD) • WARE • HERTS • TELEPHONE WARE 503  
Manufacturers of Decorative Laminates for over 20 years



- KEY  
 A Stretching bed.  
 B Multi-hole crosshead.  
 C Anchor blocks.  
 D Stretched wires.  
 E Hydraulic jack.  
 F Extension gauge.

*Pre-tensioned concrete. Above, Fig. 2a, the "Long Line" method. Below, Fig. 2b, pre-tensioned concrete sleeper factory—view of fixed end abutments.*



required force and elongation has been reached. If the jack is only used at one end the plug at the other is driven home manually just before stressing.

#### THE MAGNEL SYSTEM


The Magnel system differs from the Freyssinet in the arrangement of the wires, the stressing and anchoring. The wires are in horizontal groups of four; thus each cable comprises a multiple of four wires which are arranged in a rectangular grid with vertical and horizontal spacers to keep the wires in their proper positions. The wires are stressed two at a time (Fig. 5b) and are anchored in sandwich plates by steel wedges which are driven home by a hammer (Fig. 5a). The sandwich plates bear against a distribution plate which transmits the pre-stressing force to the concrete. The advantage of this system is that it allows cables of up to 64 wires to be used. Also there is more certainty of equal stress in the individual wires as only two are stressed at a time. Disadvantages are the relatively high cost of the anchoring and the size of duct required to accommodate the rather bulky cables.

#### THE LEE-McCALL SYSTEM

In the Lee-McCall system, which uses high tensile bars, the anchorages consist of nuts screwed on to the bar at each end (Fig. 6a).

The nut bears against a mild steel end plate which is usually cast into the concrete. Stressing is carried out by screwing an adapter on to the extended thread beyond the nut, sliding the jack over it and securing by means of a cotter (Fig. 6b). After the required force and extension has been reached the nut is screwed home to bear against the end plate. The jack is removed by simply withdrawing the cotter after which

the adapter can be screwed off. The threading on the bar and nut is of a special type with tapering threads so that with the nut in the proper position the anchorage is as strong as the unthreaded part of the bar. The advantages of this system are the relatively low cost of the end anchorages and no risk of slipping (as with wedge fixings) due to the positive end anchorage. The stressing is simple and rapid as each bar is



- KEY  
 A Stress carrying steel mould.  
 B Vibrating table.  
 C Anchor plate.  
 D Anchor blocks.  
 E H.T. steel wire.

*Fig. 3. Pre-tensioned concrete, "Individual Moulds" method.*



*a Flat Roof  
is as watertight  
as its joints*

A flat roof is as watertight as its joints.

The problem of making watertight expansion joints in flat concrete roofs can be solved by the use of Expandite rubber waterstops.

These waterstops were developed in the first place for sealing joints in hydraulic structures and are widely used by hydraulic engineers.


Three different sections are available, and, as shown in the illustrations below, the complete joint consists of the

waterstop, Flexcell cane fibre joint filler, and a surface seal of one of the Expandite rubber-bitumen sealing compounds.


This is but one example of the general problem of sealing joints where there is movement. Government, Consulting and Municipal Engineers are constantly sending us drawings and asking for our suggestions on the treatment of joints in all types of structures. Can our Technical Department be of assistance to you?

Sealing 'joints which move' is our speciality.


**TYPE A** TO ACCOMMODATE EXTREME MOVEMENT IN TENSION OR SHEAR



**TYPE B** FOR JOINTS WHERE RELATIVELY LESS MOVEMENT IS ANTICIPATED



**TYPE C** A MORE ROBUST SECTION FOR JOINTS WITH COMPARATIVELY SMALL MOVEMENT



**EXPANDITE LIMITED**

**CUNARD ROAD,  
LONDON, N.W.10  
ELGAR 5151**

equiva  
in. dia  
wires.  
special  
which  
It is  
the ca  
not es  
vide a  
and to  
ture  
With  
jected  
the L  
short  
nectin  
With  
it is  
conve  
line a  
the se  
is als  
units  
them  
of inc  
As  
such  
post-  
Their  
origin  
sive  
to of  
system

#### LOSS

Con  
chan  
to sh  
proc  
stres  
chan  
thes  
steel  
conc  
rein  
for.  
stres  
limi  
the  
shri  
a re  
avai  
ing  
for  
fully  
The  
qua  
conc  
unit  
With  
afte  
to r  
Thu  
equi  
of  
tens  
pos  
to c  
uni  
a s  
wor

equivalent to a number of wires; thus a  $1\frac{1}{8}$ -in. dia. bar is equivalent to  $18 \times 0.2$  in. dia. wires. However, with lengths beyond 60-ft., special high efficiency couplers are required which are not necessary with wire cables.

It is usual with all three systems to grout the cables or bars after stressing. Although not essential this is done in order to provide additional protection against corrosion and to improve the performance of a structure when subjected to excessive overloads. With the Freyssinet system the grout is injected through a hole in the male cone; both the Lee-McCall and Magnel systems require short ducts behind the anchorages connecting with the bar or cable ducts.

With any of these post-tensioned systems it is feasible to cast a beam in sections of convenient lengths. After placing them in line and jointing, the stressing will convert the sections into a homogeneous beam. It is also possible to tie a number of pre-cast units together transversely, thus making them act together rather than as a number of independent beams.



As is usual with a new building technique, such as prestressed concrete, many other post-tensioned systems are in use at present. Their development in their countries of origin can probably be attributed to excessive individualism since they do not appear to offer any particular advantages over the systems just described.

#### LOSS OF PRESTRESS




Concrete is subject to volumetric and linear changes throughout its life. These are due to shrinkage, which is part of the hardening process, creep, which is a function of the stress on the concrete, seasonal temperature changes and humidity variations. All of these cause a variation of prestress as the steel participates in the movement of the concrete. They also occur in ordinary reinforced concrete but are rarely allowed for. However, in prestressed concrete the stresses can be predicted within close limits and it is, therefore, usual to allow for the major of the secondary stresses, i.e., shrinkage and creep. Both of these lead to a reduction of prestress, thus decreasing the available prestress and therefore the carrying capacity; hence the critical conditions for design usually exist when they are both fully realised.

The total shrinkage of concrete of the quality usually employed in prestressed concrete is about  $350 \times 10^{-6}$  per unit length, i.e., 0.42 in. in 100 ft. With post-tensioning, as only the shrinkage after stressing is of consequence, it is usual to reduce the previous figure to  $200 \times 10^{-6}$ . Thus the loss of stress in the steel (which is equal to [strain]  $\times$  [modulus of elasticity] of the steel) is 4.5 tons per sq. in. for pre-tensioned concrete and 2.5 tons per sq. in. for post-tensioned concrete. The shortening due to creep amounts to about  $0.3 \times 10^{-6}$  per unit length per lb./sq. in. average stress, with a slightly higher figure for pre-tensioned work since the concrete is usually less mature


The Freyssinet system. Below, Fig. 4a, anchorage; right, Fig. 4b, jack.



The Magnel system. Below, Fig. 5a, anchorage; right, Fig. 5b, jack.







## health through GLASS

Will the hospital of the future be built entirely of glass, like some gigantic green-house? . . . More and more glass is being used in hospital construction inside and out. Much of it is coming from Chance Brothers. The classically simple lines of Chance Reeded and Reedlyte Glasses offer opportunities for large-scale partitioning and interior design in almost every kind of modern building. From the practical point of view, they are exceptionally white and allow the maximum passage of light while ensuring a high degree of privacy. Both surfaces are smooth and free from crevices, easy to keep clean.



### CHANCE REEDED

- Narrow Reeded ( $\frac{1}{8}$  in. ribs)
- Broad Reeded ( $\frac{3}{8}$  in. ribs)
- Major Reeded ( $1\frac{1}{8}$  in. ribs)
- Cross Reeded ( $\frac{1}{2}$  in. ribs)

### CHANCE REEDLYTE

- A stippled-finish version of Reeded to give increased obscuring power.
- Narrow Reedlyte ( $\frac{1}{8}$  in. ribs)
- Broad Reedlyte ( $\frac{3}{8}$  in. ribs)

The maximum size of the above glasses is 100 in. x 42 in.

Free samples of glass and detailed literature will be forwarded on request

FOR SCIENCE, INDUSTRY AND THE HOME

CHANCE BROTHERS LIMITED, Glass Works, Smethwick 40, Birmingham. Telephone: West Bromwich 1824.  
LONDON OFFICE: 28 St. James's Square, London, S.W.1. Telephone: Whitehall 6002. Branch Works at Glasgow, St. Helens and Malvern.


when the prestress is applied. This leads to a loss of 5 tons per sq. in. in the steel. In addition, with pre-tensioned work there is another loss due to compression of the concrete which causes a loss of approximately another 5 tons per sq. in. Due to the high stress used in wires some creep normally occurs in these as well, which is equivalent to a loss of prestress of 2 to 4 tons per sq. in.; there is no creep, however, of the Lee-McCall high tensile alloy steel bars. With these bars there is a slight overall reduction of losses due to their lower modulus of elasticity. On the average the loss of prestress or pre-tensioned concrete is 18 to 20 tons per sq. in. and 10 tons per sq. in. and 7.0 tons per sq. in. for wire and bar post-tensioned systems respectively. For design purposes it is convenient to express this loss as a percentage of the original prestress. The appropriate figures are:—

—	Ultimate Strength.	Initial Prestress.	Per cent. Loss.
	(Tons per sq. in.)		
<i>Pre-tensioned systems</i>			
0.08 in. dia. wires ..	140/150	100	20
0.20 in. " " " " ..	100/110	70	25
<i>Post-tensioned systems</i>			
0.20 in. dia. wire cables ..	100/110	65	15
High tensile bars ..	66/72	42	16

The author would like to express his thanks to the following firms for the loan of photographs:

Dow-Mac (Products), Ltd. (Fig. 2b).  
 McCall's Macalloy, Ltd. (Fig. 6b).  
 Prestressed Concrete Co., Ltd. (Fig. 4b).  
 Stressed Concrete Design Ltd. (Fig. 5b).

*The Lee-McCall system. Below, Fig. 6a, anchorage; right, Fig. 6b, prestressing jack and pump.*



*A digest of current information prepared by independent specialists; printed so that readers may cut out items for filing and paste them up in classified order.*

## INFORMATION CENTRE

### 13.73 materials: timber GLUE JOINTING

*The Structural Application of Glue in Framing Farm Buildings.* Bulletin No. 102. Aero Research Technical Notes. (Aero Research Ltd. June, 1951.)

Reprint of American paper first published in *Agricultural Engineering*. Specialized interest but useful for study of possible value of glue joints in structural timber where work is done by unskilled men, as is often the case when farm buildings are erected.

### 13.74 materials: timber TIMBER PRESERVATIVES

*Preservative Treatments for Timber in Buildings.* Draft BS C of P. Sub-Code 112.100 (British Standards Institution. 1951. 2s.)

Wood preservatives for use against fungal and insect attack. Does not deal with fire-proofing.

Now that there is a tendency to use small, highly-stressed structural timber members,

the use of timber preservatives has become of great importance. This draft Code contains a useful survey of the problem, including descriptions of types of fungal attack, types of beetle, different classes of preservatives and their limitations, and notes on methods of applying preservatives. What one wants to know most is: which of the proprietary preservatives are best? But, unfortunately, information of this type cannot be given in a Code. However, from this Code one can learn general principles, which are useful, and careful reading may enable one to question the purveyor of cures in an intelligent manner.

### 17.78 construction: general BUILDING IN COLD WEATHER

*How one builder beat winter weather.* (Engineering News-Record [USA]. July 19, 1951. pp. 33-34.)

Faster work schedule easily offset extra cost of all-weather protection in construction of two-storey school building.

It is interesting to note the manner in which American builders approach the problem of winter construction. The treatment described is particularly suitable for one- or two-storey buildings with frames of welded steel or precast concrete and roofs of precast units.

The Clifton Fine School has one wing 246 ft. by 56 ft. and another 403 ft. by 82 ft. Foundations were started in September, 1950, but by the time the steel frame was erected winter had begun. The roof, of lightweight insulating tiles, was placed on the rafters, joints grouted and the whole covered by tar paper nailed to the tiles. 80-ft. run of light scaffolding was erected to roof level on each side of the frame and plywood panels on simple wood frames provided cladding. Windows were plastic-covered

wire mesh on rough sash. Tarpaulins were used to seal up the end openings. Work continued on brick and concrete block exterior and glass-brick fenestration unhampered by rain or frost; fuel-oil stoves supplying the necessary heating. When a section of building was completed, the wind-break was hastily rebuilt in the next 80-ft. section. Having kept to schedule through the winter months, it is expected that the building will be completed by the original completion date—September, 1951.

The scaffolding and windbreak are fully recoverable and can be retained and re-used for the next job.

### 19.128 construction: details STEEL CANTILEVERS


*Long Cantilevers.* (Engineering News-Record [USA]. March 22, 1951. p. 44.)

Structural steel frame supporting glass roof over swimming pool for Bogota Country Club, Bogota. Span, 76 ft. Anchor cantilever, 38 ft. long, carries 4-in. concrete roof slab. Whole beam supported on single column, approximately 20 ft. high. The frames, of built-up plate sections, are at 20-ft. centres.

### 21.38 construction: miscellaneous HAND TOOLS

*Powered Hand Tools, Nos. 1, 2 and 3.* MOW Advisory Leaflets Nos. 18, 19 and 20. (HMSO. 1951 2d. each.)

Useful notes on powered tools for builders and craftsmen. First leaflet deals with electric tools for woodworking; second with powered tools for all trades; third with maintenance, and safety precautions.



**ADVANCE CONTROL  
OF TEMPERATURE  
ON H.W.  
HEATING SYSTEMS**

The Sarco E.T.O. Controller anticipates the effect indoors of any external temperature change.

*It is a self-contained fully-automatic control for accelerated hot-water heating systems, providing equable indoor temperatures under conditions of changing outdoor temperatures.*

*It controls heat supply at the minimum required to balance heat losses whatever the outside temperature conditions, giving maximum fuel economy.*

*It can be designed to suit heat emission curves appropriate to the type of heating surface installed.*

*It can, after installation, be corrected to allow for any variation between design and site conditions.*

*A boiler is subjected to less strain, and corrosion troubles avoided, because the boiler can be operated at a constant water temperature.*

*The E.T.O. is non-electric, entirely self-operating and direct-acting. It has packless glands which eliminate the trouble so commonly experienced with ordinary glands.*

*It is reasonable in cost; easy to install; easy on maintenance.*

For more information, please send the request slip to  
SARCO THERMOSTATS LTD., CHELTENHAM, GLOS.

**SARCO E.T.O. CONTROLLER**

REQUEST SLIP FOR ADDITIONAL INFORMATION

NAME:

ADDRESS:



AR 1051

# TWO NEW Eggshell Finish Paints

**Neophane**  
*for wall exteriors*

**Emulsyn**  
*for interior decorating*

Two new paints which claim your attention. The eggshell finish paints which have the qualities of a durable oil paint yet are applied with the ease of a distemper

For exterior walls, Stucco Cement, Plaster etc.—NEOPHANE  
For interior decoration—can be wet scrubbed—EMULSYN

Write for full particulars to the sole manufacturers:—  
**NORTH BRITISH CHEMICAL CO. LTD.**  
(PAINTS DIVISION) DROYLSDEN - MANCHESTER



*This feature covers both the production and marketing of new materials and designs of equipment as well as the general trend of developments within the Building Industry.*

## THE INDUSTRY

By Brian Grant

### DUCTS FOR ELECTRIC WIRING

Readers will probably remember the description in the JOURNAL some months ago of a special type of inflatable rubber tube which was then put forward mainly as a method for casting in concrete the long ducts necessary for post-tensioning wires. These tubes, known as Ductubes, have the advantage that they decrease in length on inflation and that, when the concrete is cured, the tubes, on deflation, not only increase in length again but at the same time twist longitudinally; the combined movements freeing the tubes from the concrete.

During the last few months, several further developments have taken place, and these tubes are now being used by the Post Office for the casting of telephone cable ducts direct in concrete, a method which should be considerably cheaper than the usual glazed stoneware pipe. The same method is also being adopted for drainage work on airfields. Both these methods involve comparatively large diameter tubes, up to about 3 in., and it is interesting to note that the smaller types are now being used for forming runs for electric wiring in concrete floors. This saves the cost of the conduit, and on the site it is quite easy to arrange the tubes so that they are clear of reinforcement bars or any other obstacles. At each ceiling point the tubes are fed through a wooden fixing block which is also cast in the floor, so that the final installation is simple and rapid.

The tubes are made in lengths of 60 ft., but, if necessary, two lengths can be joined together easily, to form longer runs. Diameters available are:  $\frac{3}{4}$  in., 1 in.,  $1\frac{1}{2}$  in., 2 in., 3 in.,  $3\frac{1}{2}$  in., and 4 in. It is claimed that the tubes can be used at least a hundred times, though many have already survived three times as many occasions as that. (The Ductube Co. Ltd., Regent House, 235-241, Regent Street, London, W.1.)

### INTELLIGENCE IN LIFTS

Those of you who have been irritated by lifts which rush past the floor on which you are waiting should go to the new Government offices in Whitehall Place and see what can be done. The installation in this building consists of a bank of four, interconnected, passenger-operated lifts at each of the two main entrances. Each lift in the bank is operated in combination with the other three. The essential points of the installation are:—(i) calls are answered in rotation for the direction of travel, irrespective of the sequence in which they have been registered, (ii) the first car in the bank of lifts (travelling in the direction required) to reach the floor will answer the call, which cannot be cancelled until answered, (iii) an automatic weighing device enables the car, when full,


to by-pass any landing calls, (iv) the departure of lift cars can be speeded up to suit the flow of passenger traffic, (v) car doors are each fitted with a safety edge, so that, when closing, the slightest pressure on either of these edges reverses the doors' direction of travel and causes them to open; after a short delay, the doors close again.

A visual indicator is fitted over each lift entrance in the lower terminal hall, showing the next lift to leave the floor for an up journey. Passengers entering the car press the appropriate button and the car and landing doors automatically close, completing the electrical interlocks. The car then starts its journey, automatically stopping at the floors, in rotation for the direction of travel, for which a call has been inserted. For example, if "up" calls have been made for, say, the 7th, 4th, 6th and 2nd floors in that sequence, for a lift travelling in the up direction, the car will first stop at the 2nd floor and, after discharging passengers, will proceed to the 4th floor and so on, ignoring any down calls until its return journey.

At landings there is only one button for "up" and one for "down." An intending passenger pushes the appropriate button and this registers the call in the control system; the first car in the bank of lifts (travelling in the required direction) to reach the floor will then answer the call. When the car approaches the floor, a gong rings and a light over the lift entrance goes on to tell the passenger which of the four lifts is stopping, giving him ample time to move to the lift.



*The use of "Ductube" to form  $\frac{3}{4}$ -in. ducts in floor slabs, to obviate use of metal conduit. Above, method of looping "Ductube" through fixing block and passing through steel shuttering. Right, complete lighting and power layout.*



The lifts can be attendant-operated if desired and a change-over switch is provided for this purpose. At the bottom terminal floor level there is a supervisor's panel for each bank of lifts. This contains a position indicator for each lift in the bank, together with the necessary operating switches, and gives the lift supervisor a visual indication of the position and direction of travel of each lift, together with the number of calls in the system for each lift. The lifts are despatched from the terminal floors automatically; the interval between lift departures being determined by the lift supervisor to suit the flow of passenger traffic.

In effect the whole system seems to behave much as lifts should, but too often don't. One push at each floor will produce one lift, instead of four pushes producing no lifts at all for different directions—enough to make one try for the Civil Service oneself. (The Express Lift Co. Ltd., subsidiary of the G.E.C., Magnet House, Kingsway, London, W.C.2.)

### CUPBOARD LATCHES

I have just come across a cupboard latch which completely does away with any handle or knob on the outside of the door. Operation could not be simpler: to close the door—push until the catch clicks; to open—push the door again for  $\frac{1}{2}$  in. or so. This push releases a catch and a spring pushes the door ajar. This new Tutch latch, which is now being made in this country, is made up of two units: the latch, and the strike hook, mounted on the door. The latch consists of a catch and a pusher, spring-loaded with a common spring and secured within a housing by two rivets. The basic operating principle centres on the pivoting action of the catch and pusher on the two rivets, assisted by the action of the spring, which operates for part of its length in tension and part in compression. When the strike hook enters the latch it compresses the pusher, causing the catch to fall and hold in the notch provided in the strike hook. The latch is now in the locked position. Immediately the catch holds, the pusher, released from compression, moves forward to its original position and pre-sets the catch for releasing the strike hook. Release is achieved upon the next compression of the pusher, which causes the catch to move upwards, freeing the strike hook. The description may sound a little complicated, but there are comparatively few parts, and as they are all made from precision pressings, in large quantities it is possible to sell the catch at the low price of 3s. 9d. retail.

This is a useful device, which should help people who haven't enough hands to carry a tray and open a door at the same time. (Linread, Ltd., Sterling Works, Cox Street, Birmingham, 3.)



## ENQUIRY FORM

I am interested in the following advertisements appearing in this issue of "The Architects' Journal." (BLOCK LETTERS, and list in alphabetical order of manufacturers names—

.....  
 .....

Please ask manufacturers to send further particulars to:—

NAME .....

PROFESSION or TRADE .....

ADDRESS .....

A.J. 4.10.51

## Buildings Illustrated

New London showroom and offices for Messrs. Richard Haworth & Co. Ltd. (Pages 404-405.) Architect: F. M. Gross, M.S.I.A., F.R.S.A. General Contractor: J. Gerrard & Sons Ltd. Sub-contractors: Shop front, interior fittings, panelling and furniture, Osters & Fleming; chairs, Ernest Race & Co. Ltd.; ventilation system, Ventaxia Ltd., and Supervent Ltd.; central heating, Rosser & Russell Ltd.; collapsible window guards, Acme Metal Works Ltd.; lettering, The Lettering Centre; electrical works, Courtney Pope (Electrical) Ltd.; light fittings,

Troughton & Young Ltd.; façade marble, Fenning & Co. Ltd.; sanitary equipment, Froy & Sons Ltd.; glass, Clark & Eaton; carpets, Perez; flowers and plants, Belsize Nurseries.

"The Festival Inn," 47, Dorset Road, Lambeth, S.W.8. (Pages 406-407.) Architect: W. J. Witham, A.R.I.B.A., Regional Architect, S.E. Region, (Messrs. Ind Coope & Allsopp, Ltd.). Assistant Architect: E. V. Leece, A.R.I.B.A. Consulting Engineer: (Structural Steelwork) J. C. Brownlie, Interior Decoration and furnishing: M. Grischotti. General Contractor: Gee, Walker & Slater, Ltd. Sub-Contractors: asphalt, Durable Asphalt Co. Ltd.; bricks, (exterior facings), Proctor & Lavender Ltd., (interior linings), Henry J. Greenham, Ltd.; structural steel, The Somerville Barnard Construction Co. Ltd.; fireproof construction (floors and roofs), The Kleine Co. Ltd.; glass, W. H. Underhill & Son, Ltd.; roof lights and cellar flaps, Haywards Ltd.; linoleum flooring and stairtread, Korkoid Decorative Floors; cork tiling floors, Cork Insulation & Asbestos Co. Ltd.; central heating, ventilation, G. N. Haden & Sons, Ltd.; grates, Bratt Colbran Ltd.; electric wiring, British Electric Co.; electric light fixtures, Troughton & Young (Lighting) Ltd.; sanitary fittings, B. Finch & Co. Ltd.; door & window furniture, Yannedis & Co. Ltd.; casements, Aygee Ltd.; screens and gate, F. W. Potter & Soar Ltd.; plaster, Suspended ceiling by Bracketing, Centreing & Lathing Ltd.; decorative plaster, Fibrous Plaster, H. E. Gaze, Ltd.; balustrade to stairs, Yannedis Ltd.; bar counters, joinery, Gaskell & Chambers Ltd.; tiling, wall & floor, B. Finch & Co. Ltd.; carpets & curtains, Peter Jones, Ltd.; paints, Hadfields (Merton) Ltd.; fixed seating, Gaskell & Chambers; easy chairs, David Joel Ltd.; other seating, Storey & Co. Ltd., Russell Furnishings Ltd.; tables and stools, C. & R. Wall Ltd.; cellar hoists, Aldous & Campbell Ltd.; clocks, Smiths, English Clocks Ltd.; signs, Buckleys (London) Ltd.

"Box Corner," 68, Hampton Road, Twickenham, Middx. (Pages 411-416.) Architects: Eric Lyons, F.R.I.B.A., A.S.I.A., and G. Paulson Townsend, L.R.I.B.A.. General Contractors: Eden Residential Construction Co. Ltd. Sub-contractors: Wall dampcourse, D. Anderson & Sons Ltd.; slab dampcourse, Field & Palmer Limited; reinforced concrete, Smiths Fireproof Floors Ltd.; facing bricks, Marston Valley Brick Co. Ltd.; common bricks, clay blocks, London Brick Co. Ltd., Flettons; concrete coping, Girlings Ferro Concrete Co. Ltd.; glass, Frank Mayle & Son Ltd.; rubber flooring, G. C. Constructional Flooring Co.; linoleum, Catesby's Limited; back boilers, Newton Chambers & Co. Ltd.; electric wiring, F. C. Clover; plumbing Faithful Bros.; electric light fitting, Hume Atkins & Co. Ltd.; sanitary fittings, J. W. Sergeant Ltd.; door furniture, Stedall & Co. Ltd., Comyn Ching Limited; wood windows, J. Alsford Limited; plasterer, Newman Bros.; stair balustrade, Light Steelwork Limited; metal glazed screen, J. Gardiner Sons & Co. Ltd.; joinery (general), West London Timber & Moulding Co. Ltd.; (kitchen fittings), Built-in Fixtures Ltd.; (mantel fittings), Joinery & Builders Supplies Ltd.; (doors), W. Hazelby Ltd.; (hand-rails), F. J. Lewis Limited; wallpaper, John Line & Son Ltd.; paint and distemper, Imperial Chemical Industries Ltd.; asphalt, Field & Palmer Ltd.; fireplace tiled surrounds, Broad & Co. Ltd.; signs, The Lettering Centre; furniture, Dunns of Bromley.

We regret that in our last issue we described Mr. S. A. W. Johnson-Marshall, the chief architect to the MOE, as assistant senior planning officer, reconstruction areas group, architects' department, LCC. We also regret that Mr. Anthony Cox was described as Andrew Cox and that Mrs. Patricia Goddard was described as H. G. Goddard.

In our issue of Sept. 20, 1951, we inadvertently referred to the "Creda Unit Type Ranges" as "Unity Ranges."

## Heat, Light—and Time

The water and gas supplies, the electricity and telephone wiring in modern buildings are, as a matter of course, planned on the drawing board, but the clocks are too often forgotten. Yet in all large buildings accurate and consistent time-indication is important and it pays to plan it with the other services. The time-indication for the South Bank exhibition was planned in this way using Gibson Master-and-Slave clocks. There are 133 Slave clocks and Time Recorders (some of them specially designed for the buildings in which they are used), driven by electrical impulses from a single Master clock. Batteries charged from the mains maintain the system during power-cuts.

Baume and Company are specialists in electrical time-indication and are always prepared to design special clocks.

**Baume & Co. Ltd.**  
 LONDON and LA CHAUX-DE-FONDS


CLOCK AND WATCH MAKERS FOR MORE THAN A CENTURY

BAUME  
 WATCHES

Longines  
 WATCHES

HEUER  
 TIMERS

Gibson  
 CLOCKS



# TUCKER'S 'Armourply'

**DOORS • COUNTERS  
AND TABLE TOPS  
CUBICLE UNITS  
REFRIGERATORS**

*Metal  
Faced  
Plywood*

**INSULATING PANELS  
ESCALATOR PANELS  
ROOF PANELS  
VEHICLE BODIES**

*Combines light weight with strength in a wide range of decorative and utility surfaces.*


Manufactured by

**WILLIAM MALLINSON & SONS LTD**

130-150 HACKNEY ROAD, LONDON, E.2.

Telephone: SHOREDITCH 8888-8811 Telegrams: ALMONER, LONDON

We are  
exhibiting  
at the  
**BUILDING  
EXHIBITION**  
OLYMPIA, Nov. 14-28  
STAND No. 100  
Row F



Borough of Camberwell Housing.

Architects: Messrs. John Grey & Partners, F.R.I.B.A., A.A.Dip.

Finlock Gutters eliminate painting and maintenance to the eaves.

**FINLOCK GUTTERS LTD., 20, ST. JOHN'S ROAD, TUNBRIDGE WELLS, KENT**

WORKS AT: LEEDS, YORKSHIRE.  
EDINBURGH, SCOTLAND.  
CWMBRAN, SOUTH WALES.

BARNSTAPLE, DEVONSHIRE.  
SOUTHAM, WARWICKSHIRE.  
TUNBRIDGE WELLS, KENT.

Telephone: Tunbridge Wells 20396/7/8

## FINLOCK

Regd. Trade Mark

**SAVE £30 PER PAIR OF HOUSES**

### Omissions


9 yds. 11 in. Brickwork	160 ft. super of Roofing
160 ft. of 2 in. by 3 in.	80 ft. of Tilt-Fillet
80 ft. of Fascia	80 ft. of Soffit
80 ft. of C.I. Gutter	Beam Filling
2 Outlets	4 Stopped Ends
2 Offsets	2 Lead Slates
Painting Gutters—Fascia—Soffit	
Reduction in Down Pipes and Drainage	

### Additions

**FINLOCK PRE-CAST EAVES  
COMPLETE WITH ALL FITTINGS  
FIXED IN ONE DAY.**

Over 100 County, City and Local Authorities are now using Finlock Gutters for their 1951 Programmes for every conceivable type of building: Police Housing, Schools, Libraries Municipal Housing. Acclaimed by Architects and the Trade as the finest advance in building construction. Our statements with regard to saving in cost are being confirmed every day by Quantity Surveyors. The actual amount varies and is dependent on the existing specification. Finlock greatly improves the appearance of a building and being of fine waterproof concrete, reduces maintenance costs appreciably. Roof maintenance is greatly facilitated by the use of Finlock Gutters and painting is reduced to doors and windows.

## CARRON EQUIPMENT CUTS COSTS!



### CARRON STEAM HEATED HOT CLOSETS

Stainless steel tops, cast iron body • Heated by coils in top, centre and bottom • Supplied with steam stop valves and exhaust traps • Sliding doors with white enamelled panels • Vitreous enamel finish.

**CARRON GAS HEATED FISH FRYING SUITES** • Four pans, with aluminium canopy fitted with sliding doors • Hot cupboards also fitted with sliding doors • Pans and top plate welded in one piece, ground and polished • Suites mounted on round pattern legs and finished in vitreous enamel.

*Part of kitchen at a large Aircraft Factory Canteen*



By Appointment  
Ironfounders  
to His Majesty



COMPANY • CARRON • STIRLINGSHIRE

Showrooms & Offices: 15 Upper Thames St., London, EC4  
22-26 Redcross Street, Liverpool, 1 • 125 Buchanan Street,  
Glasgow, C.1 • Office: 14 Ridgefield, Manchester, 2

### CARRON EQUIPMENT . . . CARRON SERVICE

The highly experienced staff of experts at Carron is always ready to assist in selecting the equipment most suited to specific needs. May we send you full information about the comprehensive range of Carron installations and our Advisory Service?





# Patent Glazing

small  
or  
LARGE

solves your problem  
with quick delivery

IN ALUMINIUM ALLOY OR  
LEAD CLOTHED STEEL SYSTEMS


PIONEERS OF ALUMINIUM PATENT GLAZING

A PRODUCT OF ENGLAND'S LARGEST GLAZING CONTRACTORS

Issued by:  
The Patent Glazing Division of  
**AYGEE LTD.**  
Head Office:  
100 WESTMINSTER BRIDGE ROAD  
LONDON, S.E.1  
Telephone: WATerloo 6314 (6 lines)  
Branch Works:  
AINTREE RD., PERIVALE, MIDDX.  
Telephone: PERivale 6211 (5 lines)



## THE BRITANNIA COMMERCIAL FITTING . . .



### WITH THESE SPECIAL FEATURES

- HINGED LOUVRE-DIFFUSER
- UNIQUE ETCHED SILVER FINISH
- SPRUNG LAMPHOLDERS
- GOOD UPWARD LIGHT

The Commercial Fitting, in common with Britannia fittings, combines fine looks with the many technical refinements, not only for extreme simplicity of erection and maintenance but for general lighting efficiency:—

1. Direct lamp light above the horizontal.
2. Diffused light only in all zones from the horizontal to 40°, below it.
3. Direct lamp light plus diffused light, in all zones lower than 40°, on to the working plane.




# Britannia

ONE OF  
BRITAIN'S  
LARGEST  
MANUFACTURERS

*Fittings with features*

BRITANNIA ENGINEERING CO. ASTON RD., LUTON, BEDS. LUTON 4082

*Louvre open for  
cleaning and lamp  
replacement.*



## PAVING FLAGS

*Made strictly to British  
Standard Specification 368.*

Granite paving is available from stock. Hydraulically pressed, clean, flat, regular in thickness and die square. Standard colours: Grey, Pink, Buff. Standard textures: Mesh and Pimple. Non-slip and guaranteed resistant to frost. Every flag is cured for a minimum period of four weeks.

Size.	No. per Ton.	Area per Ton.
3' 0" x 2' 0" x 2 1/2"	13	2 1/2" thick .. 8 1/2 yds. super
2' 6" x 2' 0" x 2 1/2"	15	
2' 0" x 2' 0" x 2 1/2"	19	
1' 6" x 2' 0" x 2 1/2"	25	
3' 0" x 2' 0" x 2"	15 1/2	2" thick .. 10 yds. super
2' 6" x 2' 0" x 2"	18 1/2	
2' 0" x 2' 0" x 2"	23	
1' 6" x 2' 0" x 2"	31	
2' 6" x 2' 0" x 1 1/2"	25	1 1/2" thick .. 13 1/2 yds. super
2' 0" x 2' 0" x 1 1/2"	31	
1' 6" x 2' 0" x 1 1/2"	41	

Gravel or Slag Aggregate Flags are also made when required. Special shapes and sizes cast to order.

## TARMAC LIMITED, VINCULUM DEPT.

ETTINGSALL, WOLVERHAMPTON

Telephone: BILSTON 41101/8 (8 lines).

Hydraulic presses at Willenhall, S. Staffs., Kidsgrove, N. Staffs., Iwer, Bucks. and Littlehampton, Sussex.  
London Office: 50, Park Street, W.1. Phone: GROsvenor 1422/5 (4 lines).





# Planifer

You can trust the 'Planifer' label. Wherever it appears, it is your guarantee of uniform top quality Drawing Office Material. 'Planifer' products are manufactured by the House of **WEST** to satisfy the exacting demands of those who insist upon the best. There are none better.



\* Catalogues available on request

A full range of fine quality Engineers' and Architects' Drawing Instruments; Drawing Office Furniture; Photographic Materials; Drawing, Detail and Tracing Papers; Tracing Cloths and Surveying Equipment. If unobtainable from your usual suppliers please write direct to

**WEST**

\* A. West & Partners, Limited, 36, Broadway, Westminster, London, S.W.1. Telephone Whitehall 5677.

## The MARLEY MUNICIPAL GARAGE


for use where two or more permanent garages are required in block form.

Extremely robust in construction and of pleasant appearance, the Marley Municipal Garage has a durability more than equal to that of a brick garage at a considerably lower finished cost. Made of high grade reinforced concrete, with asbestos roofing, it

is virtually fireproof and therefore earns the ready approval of Local Authorities.

Overall Size: 18' 5" long by 7' high to eaves at front tapering to 6' at rear. Height can be increased by 1' or 2', allowing length to be extended by multiples of 6'.


Write for full details and specifications.



### SURREY CONCRETE LIMITED

PEASMARSH • GUILDFORD • SURREY. Guildford 62986/7  
Send also for details of Marley Portable and Standard Garages, Farm and Factory Buildings.

## Specify 'GALEPROOF' WINDOWS - All Wood



Wind, dust and rain cannot penetrate Shanks 'Galeproof' Windows. Sturdily built of selected timber, with check beads worked on solid. 'Galeproof' patent construction permits loose fitting casements to eliminate the bugbear of easing. Low in cost and needing little maintenance, they are repeatedly specified by many local authorities. Shanks 'Galeproof' windows can end your window worries. Why not write now for Folder and Specification Sheet?

★ WE WILL GLADLY SEND A REPRESENTATIVE TO DEMONSTRATE A MODEL WINDOW.

Shanks have been Timber Merchants for 45 years and their Joinery Plant is without equal in the Midlands.


**SHANKS**  
TROUBLE-FREE JOINERY

E. O. SHANKS & SONS LIMITED  
Dept. W.1, Lockhurst Lane, Coventry.


Phone 89051 (3 lines).

Established 1905

*"We are unable  
to get the lengths"*



REG.  
DESIGN  
APPLIED  
FOR



HOW OFTEN

DO WE HEAR THIS?

'BAT' square toothed plate Timber Connectors can be used in the construction of standard timber components, such as purlin, trusses, bracing members, towers, temporary framework and any timber joint.

WRITE FOR LIST AND SAMPLES

**SQUARE TOOTHED PLATE  
TIMBER CONNECTORS**

**AUTOMATIC PRESSINGS LTD.**

**'BAT' WORKS, BLACKHEATH, STAFFS.**

Manufacturers of the "Bat" Carded Belt Hooks,  
Belt Lacing and V-type lacer

PLEASE MENTION "THE ARCHITECTS JOURNAL"




## Your furnishing problem

As you may have read on the editorial pages, we have done some work for Lambeth's new Festival Inn. We have done many other complete jobs from carpets to light fittings—and most enjoyable jobs to do. Do you know the whole range of Russell Furnishings? It includes much standard furniture with many tax free pieces that give lie to the current notion that good things are always expensive. We are always glad to send someone to talk to you about your furnishing problem. Ring us up or write to us.

## Russell Furnishings

RUSSELL FURNISHINGS LIMITED  
38, Wigmore Street, W.1. Telephone: Welbeck 6148



Perfect dye  
lines, blue  
prints and  
photostats  
can be made  
direct from  
Turquoise  
pencil  
drawings

However you sharpen your Turquoise pencil—whatever grade you use—the point will stand up to its job, saving you the time and trouble of constant resharpening.

**"CHEMI\*SEALED"**

**TURQUOISE**

**THE DRAUGHTSMAN'S PENCIL**



Have you had a free sample of Turquoise pencils in any one grade you wish?

EAGLE PENCIL COMPANY • TOTTENHAM • LONDON • N.17

# INSULITE

*the Wood Fibre Insulating Board*

More  
than  
30 years  
MANUFACTURING  
EXPERIENCE  
of  
WOOD-FIBRE  
INSULATING BOARD  
and  
HARDBOARD

**INSULITE PRODUCTS CORPORATION LTD**  
41, KINGSWAY, LONDON, W.C.2. TEMple Bar 9385/7

# NOEL WOOD MOSAIC

**OFFICES  
SCHOOLS  
HOSPITALS  
FACTORIES**

**WOODBLOCK  
FLOORING  
AT ITS BEST**

**DURABLE  
DECORATIVE  
ECONOMICAL  
GUARANTEED**

**E.J. ELGOOD LTD.** INDUSTRIAL FLOORING SPECIALISTS  
INSULCRETE WORKS, YEOMAN ST. S.E. 8 TELEPHONE: BERmondsey 1144 (6 lines)

## PHENCO PLASTIC FLOOR COVERING

**PHENCO** is recommended by Architects as exceptionally strong and hard wearing, with high resistance to oil, grease and chemicals. NON-inflammable. Non-slip and dustless and easily kept clean by normal methods.

**PHENCO** is tested to British Standards Specification for wear, indentation, pliability, water absorption and non-inflammability. B.S.S. 476/1932, B.S.S. 386/1936, B.S.S. 810/1938.

**PHENCO** FLOORING is a durable and flexible material with pleasing colour tones. It is supplied in 8 or 12 yard rolls, 36 in. wide by 3/32 in. or 1/8 in. thick; also in tiles 12 in. by 12 in. and 9 in. by 9 in. and 1/8 in. thick.

SAMPLES AND FULL QUOTATIONS ON REQUEST TO

**PHOENIX RUBBER CO. LTD.**

91, Bishopsgate, London, E.C.2. Tel.: London Wall 1622

Works at: 2K, Buckingham Ave., Trading Estate, Slough, Bucks  
Tel.: Slough 22307/8/9

Agents for Birmingham area: **A. D. FOULKES LTD.** Agents for Sheffield area: **JOHN HADFIELD & SONS LTD.**

## W & M NEGUS LTD


**Building Contractors**

*Station Works,  
King James St.,  
Southwark, S.E.1*

*Telephone:—  
Waterloo 5474  
(3 lines)*


## Stelcon BICYCLE PARKING

British Patent No. 425265



**SIMPLE  
AND  
ORDERLY**

**STELCON (INDUSTRIAL FLOORS) LIMITED**  
CLIFFORD'S INN LONDON, E.C.4.  
Telephone: HOLBORN 2916



## Economy . . . plus . . .

When circumstances demand economy, *plus* ease of erection, *plus* adaptability, the J.B. Pre-fabricated Garage meets *all* requirements. Weatherboard unit construction facilitates erection to any dimension of standard 9 ft. width, in any length multiples of 4 ft. 6 in. It is supplied with double doors for a garage or single door, when used for other purposes. Any unit can be lifted by one man and the whole building can be erected by two men in two days.

**Johnston Brothers**  
(CONTRACTORS) LTD.

There is a J.B. pre-fabricated building to meet most needs. Send details of your requirements.

**Doseley Quarries, Dawley, Salop**  
London Office: IBEX HOUSE, MINORIES LONDON, E.C.3

L.G.B.



# CLASSIFIED ADVERTISEMENTS

Advertisements should be addressed to the Advt. Manager, "The Architects' Journal," 9, 11 and 13, Queen Anne's Gate, Westminster, S.W.1, and should reach there by first post on Friday morning for inclusion in the following Thursday's paper.

Replies to Box Numbers should be addressed care of "The Architects' Journal," at the address given above.

## Public and Official Announcements

25s. per inch; each additional line, 2s.

### CAMBRIDGESHIRE COUNTY COUNCIL.

#### COUNTY PLANNING DEPT.

Applications are invited for the appointment of a PLANNING OFFICER on Grade A.P.T. VIII, of the National Joint Council's Scales (salary £735 to £810 per annum).

Candidates should hold the qualifications A.R.I.B.A. and A.M.T.P.I., and be able to drive a car. A wide knowledge of modern planning technique will be required, and previous experience in a planning office will be an advantage.

The successful candidate will be in charge of the design aspect of the County Development Plan, including the preparation of schemes for village development and central area redevelopment. He will also be expected to advise on housing layouts and general landscape design.

The appointment is subject to the provisions of the Local Government Superannuation Act, 1937, the Council's Conditions of Service, to the successful candidate satisfactorily passing a medical examination, and to three months' notice on either side of termination of appointment.

Financial assistance, up to £2 weekly for a period not exceeding six months, may be given if the person appointed cannot obtain housing accommodation and has to maintain his own present residence in addition to the expense of lodgings in Cambridge.

Applications, stating age, past and present appointments (with dates), experience, qualifications, present salary and the names of two referees, should be received by the undersigned not later than the 15th October, 1951.

CHARLES PHTHIAN,

Clerk of the County Council.

Shire Hall, Castle Hill, Cambridge. 4358

### LUCKLAND HOSPITAL BOARD, N.Z.

Applications are invited from Registered and suitably experienced Architects, with qualifications such as B.Arch., A.R.I.B.A., A.A.I.A. or A.N.Z.I.A., for the position of ASSISTANT ARCHITECT.

Commencing salary NZ\$850 per annum, by annual increments of NZ\$30 to NZ\$910 per annum plus the 15 per cent. General Wage Increase. Accommodation is not provided.

Conditions of Appointment and Form of Application obtainable from the office of the High Commissioner for New Zealand, 415, Strand, London, W.C.2.

Applications, addressed to the Secretary, close at the office of the Board, Kitchener Street, Auckland, New Zealand, at noon on Monday, 29th October, 1951.

R. F. GALBRAITH,

Secretary.

4394

### COUNTY BOROUGH OF BARNSELY.

#### BOROUGH ENGINEER, SURVEYOR AND PLANNING OFFICER'S DEPARTMENT.

APPOINTMENT OF GENERAL PLANNING ASSISTANT.

Applications are invited for the permanent appointment of General Planning Assistant, at a salary in accordance with A.P.T. Grade II (£470 × £15-£515 per annum).

Applicants should have passed or should be studying for the Intermediate Examination of the Town Planning Institute or its equivalent, and preference will be given to candidates who have had previous experience in a Planning Office, and who have been engaged in the preparation of Development Plans.

The appointment is subject to the National Scheme of Conditions of Service and to the provisions of the Local Government Superannuation Act, 1937, and the successful applicant will be required to pass a medical examination.

The appointment will also be subject to one month's notice on either side.

Applications, stating age, present salary, present and previous appointments, experience and qualifications, etc., accompanied by copies of two recent testimonials, should be addressed to the Borough Engineer, Surveyor and Planning Officer, Town Hall, Barnsley, to reach him not later than Saturday, 20th October, 1951.

Canvassing will disqualify.

A. E. GILFILLAN,

Town Clerk.

Town Hall, Barnsley. 4416

### LONDON COUNTY COUNCIL.

#### ARCHITECT'S DEPARTMENT.

Applications are invited for positions of ARCHITECT, Grade III (£550-£700) and TECHNICAL ASSISTANT (up to £580) for architectural work on new housing, schools and other public buildings. The positions are superannuable, and the above rates are subject to an addition of 10 per cent. on the first £600 and 7½ per cent. on any remainder. Applications forms from the Architect, The County Hall, S.E.1, enclosing stamped addressed foolscap envelope and quoting AR/EK/A. Canvassing disqualifies. (514) 3914

### BOROUGH OF BLYTH.

#### BOROUGH ENGINEER'S DEPARTMENT.

Applications are invited for the appointment of a JUNIOR ARCHITECTURAL ASSISTANT.

The salary for the appointment will be fixed within Grade II, £470 rising to £515, or Grade III, £500, rising to £545, of the A.P.T. Division, according to experience and qualifications.

Candidates should have passed the R.I.B.A. Intermediate Examination or its equivalent.

The appointment is subject to the Local Government Superannuation Act, 1937, one month's notice on either side, and the successful candidate passing a medical examination.

Applications, endorsed "Junior Architectural Assistant," stating age, qualifications and experience, must be delivered to the undersigned, with copies of three recent testimonials, not later than 1st October, 1951.

Canvassing will disqualify, and applicants should disclose relationship with any member or official of the Council.

THE COUNCIL WILL PROVIDE HOUSING ACCOMMODATION TO THE SUCCESSFUL APPLICANT, IF REQUIRED.

EDWIN W. CARTER,

Town Clerk.

"Dinsdale," 75, Marine Terrace, Blyth, 4397

### GLOUCESTERSHIRE COUNTY COUNCIL.

#### COUNTY ARCHITECT'S DEPARTMENT.

Applications are invited for the appointment of ASSISTANT ARCHITECT, on A.P. and T. Grade VI (£645-£710 per annum). Candidates must be qualified members of the R.I.B.A., with not less than 4 years' experience with a local authority.

The appointment will be subject to the Local Government Superannuation Act, 1937, and will be terminable by one month's notice on either side. The successful applicant will be required to pass a medical examination before appointment.

Applicants should state whether or not they possess a motor car and/or hold a driving licence.

Applications, stating (1) name and address, (2) married or single, (3) age, (4) qualifications, (5) present position, salary and date of appointment, (6) previous positions with dates and salaries, (7) names and addresses of two persons to whom reference can be made, should be sent to S. E. Urwin, F.R.I.B.A., County Architect, Shire Hall, Gloucester, not later than Monday, 15th October, 1951.

GUY H. DAVIS,

Clerk of the County Council.

Shire Hall, Gloucester. 4417

### URBAN DISTRICT COUNCIL OF STANLEY.

#### ENGINEER AND SURVEYOR'S DEPARTMENT.

#### APPOINTMENT OF ARCHITECTURAL ASSISTANT.

Applications are invited for the appointment of an Architectural Assistant for housing work. Applicants must be registered Architects, and have sound experience, particularly in housing.

Salary will be in accordance with Grade V, A.P.T. Division, £570-£620. The successful applicant will be required to pass a medical examination.

Applications, endorsed "Architectural Assistant," stating age, present and past appointments and experience, with three references, to be received by the undersigned by Monday, 15th October, 1951.

R. BLAKEY,

Clerk of the Council.

Council Offices, Coach Road, Outwood, 4440

### THE ROAD HAULAGE EXECUTIVE are pre-

pared to receive applications for the post of DRAUGHTSMAN in the South-Western Division (Bournemouth). Applicants, preferably qualified, with a good experience of industrial buildings, should be able to make surveys of land and buildings, and have reached at least the Intermediate stage of the R.I.B.A./R.I.C.S. Salary range £435-£595 per annum. Applications in writing, giving date of birth, qualifications, experience and present post and salary, should be forwarded to the Divisional Staff and Welfare Officer, 2, Richmond Gardens, Bournemouth, to reach him not later than 3 weeks from the date of this publication. 4441

### BOROUGH OF ERITH.

#### APPOINTMENT OF ARCHITECTURAL ASSISTANT.

Applications are invited for the above appointment at a salary in accordance with the National Scale, A.P.T. II, commencing at £470 and rising by annual increments of £15 to a maximum of £515 per annum, plus London area weighting.

Applicants, who should be capable of preparing plans, specifications, estimates and Bills of Materials for building works, should have had a good architectural training and be neat draughtsmen.

The appointment will be subject to the National Conditions of Service, to the Council's Regulations governing staff, to one month's notice in writing, and to the Local Government Superannuation Act, 1937. The successful candidate will be required to pass a medical examination.

Applications must be on the form to be obtained, together with a list of duties, from the Borough Engineer and Surveyor, Town Hall, Erith, Kent, and be delivered to him not later than 16th October, 1951.

Canvassing, either directly or indirectly, will disqualify.

J. A. CROMPTON,

Town Clerk.

Town Hall, Erith, Kent. 4443

### COUNTY BOROUGH OF BARNSELY.

#### BOROUGH ENGINEER AND SURVEYOR'S DEPARTMENT.

#### APPOINTMENT OF

(a) CHIEF ASSISTANT ARCHITECT.

(b) SECOND ASSISTANT ENGINEER.

(c) THIRD ENGINEERING ASSISTANT.

Applications are invited for the above appointments on the authorised establishment. Appointments (a) and (b) in accordance with A.P.T., Grades VI-VII, £545-£760. Appointment (c) in accordance with A.P.T., Grade V, £570-£620.

Preference will be given to candidates who are Associate Members of the Royal Institute of British Architects and have had considerable experience in Local Government, preferably with a County Borough.

Appointments must be Associate Members of the Institution of Civil Engineers and/or should have the Testamur of the Institution of Municipal Engineers, as well as having experience in a Municipal Engineer's office.

The appointments will be subject to the Scheme of Conditions for A.P.T.C. Services to the General Conditions of Service within the Corporation as varied from time to time, and to the provisions of the Local Government Superannuation Act, 1937.

The successful candidates will be required to pass a medical examination, and the appointments will also be subject to one month's notice on either side.

If necessary, housing accommodation may be offered to the successful candidates.

Applications, stating age, present and previous appointments, experience and qualifications, etc., together with the names of three referees, should be addressed to the Borough Engineer and Surveyor and Planning Officer, Town Hall, Barnsley, to reach him not later than Saturday, 13th October, 1951.

Canvassing will disqualify, and applicants should disclose in their applications whether or not to their knowledge they are related to any member or senior officer of the Council.

A. E. GILFILLAN,

Town Clerk.

Town Hall, Barnsley. 4399

### LONDON COUNTY COUNCIL.

#### ARCHITECT'S DEPARTMENT.

Applications are invited for positions of CLERK OF WORKS (salaries up to £660, plus 10 per cent. on first £600 and 7½ per cent. on any remainder) in Housing Division of Architect's Department, to supervise erection of Multi-storey Blocks of Flats. Applicants should have considerable experience in modern reinforced concrete and steelwork construction, and have supervised large building contracts. Position superannuable.

Application forms, to be returned by 20th October, 1951, obtainable from Architect to the Council, County Hall, S.E.1, enclosing stamped addressed foolscap envelope and quoting AR/EK/HCV. (1151) 4449

Applications, stating age, present and previous appointments, experience and qualifications, etc., together with the names and addresses of three referees, should be sent to the City Planning Officer and Architect, 2, Princes Buildings, Bath, not later than the 19th October, 1951.

The Corporation are prepared to render assistance to the successful candidate in securing housing accommodation if required.

JARED. E. DIXON,

Town Clerk.

Guildhall, Bath. 4457

### CITY OF BATH.

#### CITY PLANNING AND ARCHITECTURAL DEPARTMENT.

Applications are invited for the appointment of CHIEF ARCHITECTURAL ASSISTANT, Grade A.P.T. VII (£685-£760) per annum. Applicants must be Registered Architects, and preference will be given to those who are Associates of the Royal Institute of British Architects. They should have good experience in design and construction of Municipal housing and other works.

The appointment is subject to the provisions of the Local Government Superannuation Act, 1937, and the successful candidate will be required to pass a medical examination.

Applications, stating age, qualifications and experience, together with the names and addresses of three referees, should be sent to the City Planning Officer and Architect, 2, Princes Buildings, Bath, not later than the 19th October, 1951.

The Corporation are prepared to render assistance to the successful candidate in securing housing accommodation if required.

JARED. E. DIXON,

Town Clerk.

Guildhall, Bath. 4457

### CITY OF BIRMINGHAM.

#### APPOINTMENT OF CITY ARCHITECT.

The Council of the City of Birmingham desire to appoint a City Architect to be responsible for the architectural work of the Corporation, and are prepared to consider applications for the position from gentlemen who by membership of the Royal Institute of British Architects and otherwise are suitably qualified.

The initial salary for the post will be £3,000 per annum.

A memorandum giving details about the scope of the appointment, and about salary increments and other conditions, may be obtained by application to me at the Council House, Birmingham, 1.

Applications for the post must be received by me not later than the 17th November, 1951.

J. F. GREGG,

Town Clerk.

The Council House, Birmingham, 1. 4455

September, 1951.



**COUNTY BOROUGH OF WEST HARTLEPOOL.**

**BOROUGH ARCHITECT'S DEPARTMENT.**  
Applications are invited for the position of **ASSISTANT QUANTITY SURVEYOR**, Grade A.P.T. V (£570×£15×£20-£620) in the Borough Architect's Department.

The appointment is subject to the Scheme of Conditions of Service of the National Joint Council for Local Authorities' Administrative, Professional, Technical and Clerical Services with the exception of Paragraph 39. The post will be superannuable and the successful candidate will be required to pass a medical examination.

The Council are prepared to consider the provision of housing accommodation for the successful applicant, if required.

Applications, stating age, experience and qualifications, together with copies of not more than three testimonials should be delivered at the office of the Borough Architect, Municipal Buildings, West Hartlepool, not later than Wednesday the 17th October, 1951.

**ERIC J. WAGGOTT,**  
Town Clerk.

Town Clerk's Office,  
Municipal Buildings,  
West Hartlepool.  
September, 1951. 4480

**HEMEL HEMPSTEAD DEVELOPMENT CORPORATION.**

Applications are invited for the appointment of **SENIOR PLANNING ASSISTANT**. Salary in the scale £610×£30-£810.

Applicants should hold a Town Planning qualification. The applicant appointed will be engaged on the design of residential areas, being chiefly concerned with the preparation of housing layouts, and should be a qualified architect or have a sound architectural background.

The appointment will be subject to the Development Corporation's staff rules and conditions of service (which are broadly similar to the Local Government Officers' Charter).

Contributory superannuation with an opportunity of entering or continuing in Local Government Superannuation Fund will be provided.

Housing accommodation may be provided if necessary.

Applications, giving particulars of age, qualifications and experience, the names of two persons to whom reference may be made, and endorsed "Planning" should be addressed to the undersigned to reach him by 15th October, 1951.

**W. O. HART,**  
General Manager.

Westbrook Hay,  
Hemel Hempstead, Herts. 4478

**CITY OF BIRMINGHAM EDUCATION COMMITTEE.**

**COLLEGE OF TECHNOLOGY, BIRMINGHAM. DEPARTMENT OF BUILDING AND CIVIL ENGINEERING.**

Applications are invited for the post of **SENIOR LECTURER** in Quantity Surveying and associated subjects.

Candidates must be Fellows or Associates by examination of the Royal Institute of Chartered Surveyors or possess an equivalent qualification.

The successful applicant may be required to teach all necessary subjects up to the standard of the Final Examinations of the R.I.C.S. and other appropriate Institutions.

The person appointed will be expected to commence duties by not later than 1st January, 1952. Salary for Senior Lecturers will be in accordance with the 1951 Burnham (Further Education) Scale (men: £1,000×£25-£1,150).

Further particulars and form of application may be obtained from the Registrar, College of Technology, Suffolk Street, Birmingham, 1, on receipt of a stamped addressed foolscap envelope. Completed forms should be returned to him not later than two weeks after the appearance of this advertisement.

**C. McCAW,**  
Clerk to the Governing Body. 4458

**CITY OF LIVERPOOL—EDUCATION COMMITTEE.**

**COLLEGE OF BUILDING.**

**CLARENCE STREET, LIVERPOOL, 3.**

**Principal: T. E. HALL, Dip. Arch., A.R.I.B.A.**  
Applications are invited for the appointment of **ASSISTANT** (full time), Grade B, to teach Architecture in the Department of Building and Professional Studies to the standard of the Final Examination of the Royal Institute of British Architects. (Duties to commence as soon as possible.)

Salary: £450×£25 to £725 (men); £405×£20 to £580 (women).

Candidates must possess the appropriate professional qualification and professional or industrial experience. Teaching experience is desirable but not essential.

The correct position at entry will be determined by the length of industrial teaching and war service of the candidate, and additions to the scale for training and graduate qualifications are payable up to a maximum of £114 per annum (men); £93 per annum (women).

Application forms and further particulars may be obtained from H. S. Magnay, Director of Education, 14, Sir Thomas Street, Liverpool, 1, to whom completed applications should be returned within two weeks of the appearance of this advertisement.

**THOMAS ALKER,**  
Town Clerk and Clerk to the Local Education Authority. (JA 2721) 4454

**BOROUGH OF BLYTH.**

**SENIOR ARCHITECTURAL ASSISTANT.**

Applications are invited for the appointment of a Senior Architectural Assistant, in the Borough Engineer's Department, at a salary in accordance with Grade V, A.P.T., namely £570 per annum, rising to £620 per annum by annual increments.

Applicants should be Registered Architects, with a good experience in Municipal Housing.

The appointment is subject to the National Scheme of Conditions of Service, the provisions of the Local Government Superannuation Act, 1937, the passing of a medical examination, and one month's notice on either side.

Applications suitably endorsed and accompanied by three recent testimonials must reach the undersigned not later than first post on 10th October, 1951.

Canvassing will disqualify, and applicants must state whether they are related to any member or senior official of the Council.

**HOUSING ACCOMMODATION WILL BE PROVIDED IF NECESSARY.**

**EDWIN W. CARTER,**  
Town Clerk.

"Dinsdale," Marine Terrace, Blyth, Northumberland. 4452

**METROPOLITAN BOROUGH OF LEWISHAM. APPOINTMENT OF ASSISTANT ARCHITECTS.**

Applications are invited for the appointment in the Borough Architect's Department of: (a) A **SENIOR ASSISTANT ARCHITECT**, salary scale A.P.T. Division, Grade VIII (£735×£25-£810 per annum), and (b) an **ASSISTANT ARCHITECT**, salary scale A.P.T. Division, Grade IV-VI (£530, rising to £710 per annum). London "weighting," varying between £10 and £30 per annum, according to age, is applicable to each salary.

Applicants for both appointments must be suitably qualified, and in the case of (a) should be Associates of the Royal Institute of British Architects.

The appointments will be subject to the Rules and Regulations of the Council from time to time in force relating to Officers; to the National Scheme of Conditions of Service; to the provisions of the Local Government Superannuation Act, 1937; to termination by one month's notice on either side, and to the successful candidates passing satisfactorily a medical examination by the Council's Medical Officer of Health.

Forms of application may be obtained from the undersigned, to whom they should be returned, accompanied by copies of not more than three recent testimonials, in an envelope endorsed with the name of the post applied for, so as to be received not later than Saturday, the 20th October, 1951.

Canvassing, either directly or indirectly, will be a disqualification.

**ALAN MILNER SMITH,**  
Town Clerk.

Lewisham Town Hall, Catford, S.E.6. 26th September, 1951. 4463

**DOWN COUNTY COUNCIL (NORTHERN IRELAND).**

Applications are invited for the following:—

(a) **DEPUTY COUNTY PLANNING OFFICER.** Salary £875-£1,000×two £50 and one £25.

(b) **ASSISTANT ARCHITECT.** Salary £600-£710×four £20 and one £30.

Applicants for (a) must be Associate Members of the Town Planning Institute and Associates of the Royal Institute of British Architects; for (b) must be Associates of the Royal Institute of British Architects.

The appointments are subject to the Local Government Officers' (Superannuation) Act (N.I.), 1950, and are terminable by one month's notice on either side. The successful applicants for both posts will be required to live in or near Downpatrick, and for (a) will be required to provide a car for official journeys. Mileage allowance is payable at the County Council's rate for such journeys.

Preference will be given to suitable ex-Service candidates.

Applications, stating age, qualifications and experience, and accompanied by copies of two recent testimonials, to be delivered to the undersigned not later than 16th October, 1951.

**J. H. HARVEY,**

Courthouse, Downpatrick, Co. Down. 4462

**PETERLEE DEVELOPMENT CORPORATION.**

Applications are invited for the appointment of an **ARCHITECTURAL ASSISTANT**, in the Chief Architect's Department, at a salary of £500, rising by £50 increments to £600 per annum. Applicants must be to the standard of the Intermediate Examination of the R.I.B.A., or equivalent, be of good general training, and preferably have experience in a Municipal Architect's or Engineer's office.

Lodging allowance is payable at the discretion of the Corporation to a successful applicant who is married or has equivalent responsibilities, until suitable housing accommodation in the area is secured.

The appointment is subject to the provisions of the Local Government Superannuation Act, 1937, to the Corporation's Staff Rules and Conditions of Service, and the passing of a medical examination.

Applications, setting out details of age, qualifications, experience, past and present appointments, should be submitted to me not later than 15th October, 1951.

**A. V. WILLIAMS,**  
General Manager. 4459

Shotton Hall, Castle Eden, Co. Durham.

**AMENDED.**

**METROPOLITAN BOROUGH OF FULHAM.**

**SENIOR ASSISTANT ARCHITECT.**

Applications are invited for this appointment in the Architectural Section of the Housing and Public Buildings Department.

Salary: A.P.T., Grade VI (£645×£20 (2) × £25 (1)—£710 per annum, including London weighting.

Applicants should be Registered Architects, experienced in designing and dealing with large contracts through all stages. The successful applicant will be employed in a senior capacity in connection with the planning, design and execution of large schemes of flats and public buildings. Lack of previous experience in a Municipal office will not deter applicants from consideration.

Applications on forms obtainable from me: closing date 13th October, 1951.

**CYRIL F. THATCHER,**

Town Hall, Fulham, S.W.6. 4468

September, 1951.

**BURGH OF ALLOA.**

**APPOINTMENT OF SENIOR ARCHITECTURAL ASSISTANT.**

Applications are invited for the appointment of Senior Assistant Architect, on the staff of the Council's Architect, at a salary of £520-£565, placing on grade according to experience.

Applicants must be Registered Architects. Preference will be given to candidates who are Members of the R.I.B.A., and who have knowledge of Local Authority Housing Design. Experience in quantities is essential.

The post will be superannuable, and the successful applicant will be required to pass a medical examination.

A house will be made available if required. Applications, giving age, qualifications and experience, accompanied with the names and addresses of two persons to whom reference may be made, should be sent to Mr. W. H. Gillespie, L.R.I.B.A., Burgh Architect, Municipal Buildings, Alloa, not later than 31st October.

**WILLIAM MALTMAN,**

Town Clerk. 4476

**STAFFORDSHIRE COUNTY COUNCIL. COUNTY PLANNING DEPARTMENT.**

Applications are invited for senior appointments in the County Planning Department, in A.P.T. Grades VII-VIII. Salary from £635 to £760 p.a.

The persons appointed will be mainly engaged on the preparation and carrying into effect of housing and other estate development proposals. Applicants should be qualified in Architecture or Engineering and Membership of the Town Planning Institute would also be an advantage.

Applications should give details of age, education and training, qualifications, present and previous appointments and experience, and should include copies of two recent testimonials and the names of two other persons to whom reference can be made. Applications should be sent to D. W. Riley, County Planning Officer, 41a, Eastgate Street, Stafford, not later than the 20th October, 1951.

**T. H. EVANS,**  
Clerk of the County Council. 4469

**Tenders for Contracts**

6 lines or under, 12s. 6d.; each additional line, 2s.

**COUNTY BOROUGH OF READING. TO BUILDERS AND CONTRACTORS.**

The Corporation of Reading invite tenders for the conversion for use as a Metal Workshop and Drawing Office of a Building in Crescent Road, Reading, adjacent to Alfred Sutton Central School.

The General Conditions may be inspected at the office of the Borough Architect, Town Hall, Reading, and copies of the Drawings, Specification, Form of Tender, and endorsed envelope obtained on application to him.

Tenders must be delivered to the undersigned not later than Friday, the 26th October, 1951.

No tender will be considered unless enclosed in the endorsed envelope provided and sealed, but not bearing any name or mark indicating the sender.

The Corporation do not bind themselves to accept the lowest or any tender.

**G. F. DARLOW,**

Town Hall, Reading. 4475

October, 1951.

**BOROUGH OF DAGENHAM.**

**WOODLANDS ESTATE, RAINHAM ROAD.**

**ERECTION OF FLATS.**

Tenders are invited for the erection of 36 flats, in three blocks of twelve flats (three-storey).

Bills of Quantities and Form of Tender may be obtained from the Borough Engineer and Surveyor on payment of a deposit of two guineas, which will be refunded on receipt of a bona-fide tender.

Plans and General Conditions of Contract may be inspected during normal office hours.

Sealed tenders, in an envelope provided which must bear no indication of the identity of the senders, to be delivered to the undersigned by noon on Saturday, 27th October, 1951.

**KEITH LAUDER,**

Town Clerk. 4479

Civic Centre, Dagenham.

## Architectural Appointments Vacant

4 lines or under, 7s. 6d.; each additional line, 2s.

**VACANCY for JUNIOR ASSISTANT**, single. Salary £350-£450. Must be good draughtsman, with good practical knowledge of construction. Pension scheme. Interesting and varied work. Gotch, Saunders & Surridge, Chartered Architects, Kettering. 4409

**ARCHITECTURAL ASSISTANT**, Intermediate standard, required in Architects' office of multiple shop company, interesting work, possibility of permanency. Write Box 4383.

**ARCHITECT'S ASSISTANT** required by firm of Architects in South-West England; age 30 to 35. State experience and salary required to Box 4372.

**PROGRESSIVE post for LADY ASSISTANT** in small private practice, London, W.1. Neat Draughtsmanship, some typing ability required. Box 4401.

**JUNIOR ARCHITECT'S ASSISTANT** required in busy Westminster office, with good prospects of advancement and interesting work. Salary £260 p.a. Box 4419.

**ARCHITECTURAL ASSISTANT**, of R.I.B.A. Intermediate standard, with office experience, required immediately. Starting salary £400 to £500, according to experience. Apply, with full details, to Deacon & Laing, F./A.R.I.B.A., 9, St. Paul's Square, Bedford. 4470

**FAMOUS Mutual Life Assurance House** needs a few men of drive and integrity to act as AGENTS. Architects and Surveyors have the right contacts, and can best serve their "Mutual" interests. Further details from Box 4466.

**ARCHITECTURAL ASSISTANT**, with at least 4 years' office experience, required in Architects' office in Ilford area. Must be neat and quick draughtsman, capable of preparing working drawings and full size details for school and hospital projects. Good prospects for man of initiative; 5-day week. Write, stating age, details of past work, education, and salary required. Box 4465.

**OLD-ESTABLISHED Company**, with headquarters in Lincoln, currently exporting houses to Australia, has a vacancy for an ARCHITECTURAL ASSISTANT of R.I.B.A. Intermediate standard, and with at least three to four years' office experience. Interesting work and excellent prospects, where ability and initiative are displayed. Full particulars to Box 4456.

**PARTLY qualified ARCHITECTURAL STUDENT**, prepared to emigrate to New Zealand, offered generous salary, good conditions, interesting work, and share flat with University student. Air mail. B. E. Orchiston, B.Arch., P.O. Box 35, Wellington, New Zealand. 4464

**ASSISTANTS** required at Minehead and Taunton Offices. Intermediate Standard; for work on Housing, Hospitals and W.D. projects. Write, stating qualifications, experience, and salary required. Donati & Torrens, A./A.R.I.B.A., 13, The Parade, Minehead. 4466

**ARCHITECT'S ASSISTANT** required. Must have first-class knowledge of design and construction, and be prepared to use his own initiative. Apply, stating age, experience and salary required, to Gratrix & McLellan, Architects, 7, St. Helens Road, Swansea. 4438

**ARCHITECT'S ASSISTANT** required for Andover, Hants, Branch Office. Must be third or fourth year student. Write, with copies testimonials, and state salary expected to Box 4445.

**ASSISTANT** for busy and varied practice London, S.W., with sound knowledge of construction and reasonable London office experience essential. Excellent prospects for one willing to work hard and having ambition greater than required for public service. Box 4474.

## Architectural Appointments Wanted

**B. ARCH.**, Liverpool, needs part-time work near Liverpool. Experienced in design, working drawings, British and Swiss, translations of and into German. Very wide education. Box 4437.

**SENIOR ASSISTANT** (32), married, with family, requires post in small but progressive provincial office. Office trained, 12 years' experience, housing both L.A. and private, hospitals, schools, factory and industrial buildings. Experienced in site supervision, control of staff, handling contracts and working on own initiative. Preferably coastal town, but willing to go anywhere offering living accommodation. Minimum salary £575 p.a. All letters acknowledged. Box 260.

**CHARTERED ARCHITECT** (36) desires responsible position, home or abroad. L.R.I.B.A., 20 years' varied experience in private and public posts. Able to handle schemes from design to final accounts, including preparation of quantities. Sound business acumen. Car owner. Please write Box 261.

**CHARTERED ARCHITECT** requires responsible appointment. Wide experience, including contemporary London practice. Box 259.

**A. R.I.B.A.** seeks part-time situation in London area. Three days per week. Box 4491.

**ARCHITECTURAL DRAUGHTSMAN** and Model Maker-cum-Field Surveyor-cum-Clerk of Works-cum-Technical and Free-Lance Journalist and Photographer, seeks part-time job, embracing housing accommodation of some sort. Salary immaterial. Box 4450.

**ASSOCIATE** (31), varied general experience, office trained, requires responsible position in Lancashire area. Able to manage contracts from sketch plan stage to final account. Salary by arrangement, dependent on prospects. Box 257.

**TEMPORARY position** in North or Central London desired by student. R.I.B.A., with 5 years' office experience. Box 258.


**ASSOCIATE (woman)**, 4 years' office experience, requires position. 4 days per week, in contemporary office of Architect or Designer in London. Box 4471.

**ARCHITECTURAL ASSISTANT (A.R.I.B.A.)** seeks spare-time work. Sketch plans, working drawings, details, etc., including estate site works, surveys. Box 4472.

**ASSISTANT** (24), 5 years' private office experience, passed R.I.B.A. Inter., capable surveyor, requires change. Please write Box 262.

**EXPERIENCED ARCHITECTURAL MODEL MAKER** seeks position. Accustomed to working with all types of material. Box 4473.

**QUALIFIED ASSISTANT ARCHITECT** (32), with wide experience, including industrial and housing, seeks responsible position, preferably in the West Midlands. Married, and would greatly appreciate unfurnished accommodation. Salary about £650. Box 256.



The new EJMA Standard Wood Casement Window is now in production.

There's nothing like **WOOD**



THE GUARANTEE OF  
**JOINERY EXCELLENCE**

The Trade Mark is a guarantee of quality since it may only be used by licensed producers who undertake to conform to the designs and the specifications of the Association, a list of whom may be obtained from the Secretary of the Association.

**THE ENGLISH JOINERY MANUFACTURERS' ASSOCIATION**  
(INCORPORATED)

**SACKVILLE HOUSE, 40 PICCADILLY, W.1. REGENT 4448**

## STONE CLEANING & RESTORATION

INCLUDING MOSAIC TERRAZZO AND MARBLEWORK

**PETER COX & PARTNERS LTD**

TELEPHONE  
MAYFAIR  
0403

CONTRACTS UNDERTAKEN  
THROUGHOUT THE BRITISH ISLES

33, NORTH ROW,  
PARK LANE,  
W.1.

### Other Appointments Vacant

4 lines or under, 7s. 6d.; each additional line, 2s.

**LONDON COUNTY COUNCIL.**  
**HAMMERSMITH SCHOOL OF BUILDING**  
**AND ARTS AND CRAFTS.**

Applications are invited for the following appointments:—

(1) **SENIOR LECTURER IN ARCHITECTURE.** Applicants should be Fellows or Associates of the R.I.B.A., and preferably hold a degree or diploma of a recognised school of architecture.

They should have some teaching experience and also practical experience in design and construction.

(2) **SENIOR LECTURER IN BUILDING.** Applicants should be suitably qualified to control and teach in ordinary and higher national diploma and certificate courses, and should preferably have some teaching experience as well as industrial experience.

(3) **LECTURER IN QUANTITY SURVEYING.** Applicants, who will be required to supervise and teach in surveying course, should be Associates of the R.I.C.S., and preferably have some teaching experience.

(4) **STUDIO MASTER IN ARCHITECTURE.** Applicants, who will be required to give instruction in design and construction, should be Associates of the R.I.B.A., and preferably hold the degree or diploma of a recognised school.

(5) **ASSISTANT TEACHER OF BUILDING SCIENCE AND MATHEMATICS.** Applicants should be well qualified to teach these subjects in diploma and certificate courses.

Salaries for these posts will be in accordance with the Burnham Technical Report, 1951, and are as follows:—

Posts (1) and (2): £1,000 × £25—£1,150.  
Post (3): £900 × £25—£1,000.

Posts (4) and (5): Assistants, Grade B, £450 × £25—£725, plus graduate allowance £50 and training allowance where applicable.

For posts (4) and (5) the commencing point on the scale will be appropriate to previous teaching and/or industrial experience. All posts will carry a London allowance of £36 or £48, according to age.

Further particulars and application forms can be obtained on application to the Secretary at the School (S.A.E.), to whom completed applications should be returned on or before 31st October, 1951. (1181) 4467

**R.I.B.A. Postal Tuition in Mechanics and Structures.** D. A. Fowler, Dip.Arch.(Abdn.), F.R.I.B.A., Derwent House, Wressle, Selby. 4444

**FIRM,** with established connection dealing with Architects and Local Authorities, require **REPRESENTATIVE** to handle patent unit used in housing. Architectural or building knowledge essential.—Replies to Box 4451.

**FIRST-CLASS Inexpensive Drawing Sets.** Well introduced **TRAVELLERS** and **REPRESENTATIVES** required to carry these additional lines on commission. Write **I.T.A. (Great Britain), Ltd., 17, Philpot Lane, E.C.3.** 4453

**TECHNICAL ASSISTANT** required by British Railways (Western Region) at Paddington. Must be capable of dealing with maintenance of Estate properties, mainly houses. Inspections, specifications and supervision. Salary according to age (£310 at 23), rising to maximum of £515 at 36, with prospects of advancement. Apply in writing to: The Estate and Rating Surveyor, 125, Westbourne Terrace, London, W.2. 4443

**PLANT ENGINEER** with experience of building trade, factory services and plant layout to supervise maintenance of buildings and services, erection of new buildings and to undertake plant layouts in a large industrial organisation in Edinburgh. Age around 40. Position permanent and pensionable. Salary up to £750 per annum according to experience. Write giving full particulars of education and experience to Box 821, Keith & Co., Advertising Agents, Edinburgh. 4481

**LAND SURVEYOR**, preferably with colonial experience, required for extensive land survey in Ethiopia; period 6 months approx., passage paid. Salary £1,000 per annum (free of tax) dependent on experience. Box 4477.

### Services Offered

4 lines or under, 7s. 6d.; each additional line, 2s.

**ARCHITECTURAL ASSISTANTS** require additional work. Surveying, Levelling, Working Drawings, Details, Tracings, etc. **W. Graysmark, 41, Wadham Gardens, Greenford, Middx.** 4353

**CHARTERED STRUCTURAL ENGINEER**, shortly taking up new appointment in New Zealand, would be interested in any proposition, commission or agency connected with the building trade. 15 years' experience in building and civil engineering. Box 4424.

**REINFORCED or Pre-stressed Concrete**, complete schemes designed and detailed, large or small. Calculations prepared for local authorities. Several years' experience in structural design. Write Box 4439.

### PERSPECTIVES

Academy Standard. Any size. Any medium. Winston Walker, F.R.I.B.A., 107, Sloane Street, S.W.1. SLOane 1410. 4420

### For Sale or Wanted

4 lines or under, 7s. 6d.; each additional line, 2s.

**EX A.M. Nissen Type Hutting**, all sizes, delivered and erected. Also Sectional Garages and Hutting, all types. Write McIntyre & Eastwood, Ltd., Carr Road Works, Wyke, Bradford. 'Phone Low Moor 737. 4460

**STUDENT** requires Double Elephant Drawing Board and adjustable Stand. Box 4442.

### Miscellaneous

4 lines or under, 7s. 6d.; each additional line, 2s.

**A. J. BINNS, LTD.** Specialists in the supply and fixing of all types of Fencing, Gates and Cloakroom Equipment. Harvest Works, 99-107, St. Paul's Road, N.1. Canonbury 2061.

**FRENCH POLISHERS.**—Wm. Burton's, for every style of polishing. 26, Foulser Road, Upper Tooting, S.W.17. BAL. 3968. 4619

**WINKFIELD MANOE NURSERIES.** ASCOT, lay out Rock and Formal Gardens and Labourless "Allweather" Tennis Courts. Eight Chelsea Gold Medals since 1947. Contractors to the Festival of Britain. Winkfield Row 353. 1716

**DEMOLITION Site Clearance**, by Syd Bishop & Sons, Demolition Contractors, Swanley, Kent. 'Phone Swanley 2519. 4216

**"MAY I ASSIST YOU?"** Quantity Surveyor available to prepare Bills of Quantities, quickly. Large War Damage Claims negotiated. Please write and interview will be arranged at once. Box 4315b.

**RHODODENDRONS, AZALEAS, Ornamental Flowering Trees and Shrubs, Heathers, Hedging and Herbaceous Plants, Camellias, Roses, Iris, and other choice plants for all garden requirements.** The Knaphill strain of Azaleas is supreme. Descriptive catalogue from The Knap Hill Nursery, Ltd., Woking, Surrey. 4393

**NO CHIMNEY, NO BOILERHOUSE** needed with a B. & A. Electrode Boiler. Ideal for hot water and central heating... no smoke, no fuel-store, no ash removal. Most compact, can be fitted in any convenient position. Available from 102,000 to 4,080,000 B.Th.U. per hour. Write for leaflet 150, Bastian & Allen, Ltd., Ferndale Terrace, Harrow, Middlesex. 2210

Introducing...

**MARKSMAN** REGD.

A First Class

**TRACING CLOTH**

SAMPLES AND PRICES  
ON REQUEST

**J. N. HOPKINSON LIMITED** ADVERTISEMENT DEPT.,  
16 JOHN DALTON STREET  
MANCHESTER 2

### THE COLLEGE OF ESTATE MANAGEMENT

St. Albans Grove, Kensington, W.8.

Day and Evening Courses for the following Examinations:—

University of London Degree of B.Sc. (Estate Management) commence in October. (Day courses only. Completed application forms must be submitted by May 31st.)

Royal Institution of Chartered Surveyors (Building, Quantities and Valuations subdivisions) commence in April. (Completed application forms must be submitted by December 31st.)

Postal Courses

B.Sc. (Estate Management), commence in January and July. The Royal Institution of Chartered Surveyors, Institution of Municipal Engineers, Royal Sanitary Institute, commence in April and October.

Town Planning Institute, commence in May and October. Applicants for Postal Courses must submit their forms two complete calendar months before the date on which the course begins.

Applications to: The Secretary. Telephone: Western 1546

BRITAIN'S  
BEST  
BRICKS!

• FACINGS  
• ENGINEERING  
• ACID-RESISTING  
**ACCRINGTON 'NOBI' BRICKS**  
THE ACCRINGTON BRICK & TILE COMPANY LTD.  
ACCRINGTON. (ACCRINGTON 2684)



**FENCING FOR ALL PURPOSES.** Supplied and erected; established 100 years. Parker, Winder & Achurch, Ltd., 80, Broad Street, Birmingham, 1. Telephone: Midland 5001.

**INSURANCE**

**ARCHITECTS' Indemnity Insurance effected.** Please write for Proposal Form to E. J. SAXBY, Incorporated Insurance Broker, 37a, Carfax, Horsham, Sussex. Tel. 990. 2039

**Educational Announcements**

4 lines or under, 7s. 6d.; each additional line, 2s.

**R.I.B.A. and T.P.I. EXAMS.**—Stuart Stanley, (Tutor Sch. of Arch. Lon. Univ.), and G. A. Crockett, B.A., A.R.I.B.A. (Medallist), A.M.T.P.I., F.R.S.A., prepare students by correspondence tuition. Stuart Stanley & Crockett, 10, Adelaide Street, Strand, W.C.2. TEM. 1603/4.

**CITY OF LEICESTER EDUCATION COMMITTEE  
LEICESTER COLLEGE OF ART.  
SCHOOL OF ARCHITECTURE.  
SESSION 1951-1952.**

Full-time day courses of three years' duration have been arranged in Building and Quantity Surveying for Students preparing for examinations of the Professional Institutions.

The College is recognised by the Royal Institution of Chartered Surveyors as an approved place of instruction for the First and Intermediate Examinations in the Building and Quantity Surveying Sub-Divisions.

Applicants must hold a satisfactory General Certificate of Education at ordinary or advanced levels, or have passed the School Certificate Examination with 4 credits, including Mathematics and English Language.

**ELFED THOMAS,**

*Director of Education.*

Newarke Street, Leicester. 4447

**R I B A INTER, FINAL & SPECIAL FINAL**

Postal Courses in all subjects of the 1951 exam syllabus (including Professional Practice) are conducted by **THE ELLIS SCHOOL OF ARCHITECTURE** Principal: A. B. Waters M.B.E., G.M., F.R.I.B.A., 103B, OLD BROMPTON RD., LONDON, S.W.7 Phone: KEN 8641 and at Worcester

**QUANTITY SURVEYING**

Postal Courses for R.I.C.S. I.A.A.S. and I.Q.S. Exams in all subjects of each syllabus. Tuition by well qualified tutors under the direction of the Principal, A. B. Waters, M.B.E., G.M., F.R.I.B.A. Descriptive booklet on request.

**THE ELLIS SCHOOL**

103B, OLD BROMPTON RD., LONDON, S.W.7 Phone: KEN 8641 and at Worcester

**QUALIFYING EXAMINATIONS**

**R.I.B.A. AND T.P.I.  
INTER & FINAL FINAL**

Courses of Instruction by Correspondence and Personal in Studio, including TESTIMONIES OF STUDY AND PROFESSIONAL PRACTICE

**C. W. BOX**

F.R.I.B.A., A.I.STRUCT.E., M.R.SAN.I.

115 GOWER STREET, W.C. Euston 3906

**Architects Assistant required in  
COMPANY ARCHITECTS' DEPARTMENT  
OF COVENTRY MANUFACTURERS**

Interesting and responsible position. Preferably used to industrial work and of Intermediate standard although 'not essential. Five day week. Salary in accordance with 'qualifications.

Applications to Box No. 4427.

**ANCHORAGES TO  
CONCRETE**

**SPEARPOINT Floor Clips** to anchor wood floors to concrete.  
**DOVETAIL Masonry Slot** and Anchors to anchor brick and stone facings to concrete.  
**ANKORTITE Box Fittings.**

**ABBEY BUILDING SUPPLIES CO.**

6, Waldemar Road, Wimbledon, London, S.W.19

Telephone: Wimbledon 4178

**WHITE FACING  
BRICKS**

(S. P. W. BRAND)

TELEPHONE & TELEGRAMS  
BULWELL 78237-8

**M. McCARTHY & SONS, LTD**  
BULWELL NOTTINGHAM

**"STONITE"**

**WALL FINISHING MATERIALS**

Full particulars including Information Sheet No. 7.C2 from  
**CALLOW & KEPPICH LTD**

**C & K** SHIPHAM GORGE, CHEDDAR, SOMERSET  
Telephone: Cheddar 214

**LINOLEUM**

**Information Sheets**

19/G1, 2, 3 & 4

Reprints available on application to:—  
**Linoleum Manufacturers' Association,**  
273/287, Regent Street, London, W.1.

**The World's Greatest  
Bookshop**


**FOYLES  
\* FOR BOOKS \***

Large dept. for Books on  
Architecture & Art

New, secondhand and rare Books on  
every subject. Over 3 million volumes

119-125 CHARING CROSS RD LONDON WC2  
Gerrard 5660 (16 lines) \* Open 9-6 (inc. Sats.)

**BULLDOG**



**FLOOR &  
CEILING CLIPS**

*Standard and Acoustic*



**THE ADAMITE  
COMPANY LTD**


MANFIELD HOUSE, STRAND, W.C.2

**INSTITUTE of REGISTERED  
ARCHITECTS**

*Students' Service*

Architectural students, interested in becoming subscribers to the Service are invited to communicate with the Secretary of the Institute.

47 VICTORIA STREET, LONDON, S.W.1



**CHAIN LINK  
FENCING**

**A COMPLETE FENCING SERVICE**

**BOULTON AND  
PAUL LIMITED**

**NORWICH**

CRC98

*minimise fire risk with*

**DURASTEEL**

**STRUCTURAL FIRE PROTECTION**

**HIGH FIRE RESISTANCE  
LIGHTNESS AND STRENGTH  
STRUCTURAL SIMPLICITY**

in Fire Resisting Doors, Panelling and Roofing.  
Send for data mentioning Information Sheets  
Nos. 36.D1 (Fire Protection—Doors) and 15.R1  
(Sheet Materials—Fire Protection).

**DURASTEEL LTD**

OLDFIELD LANE  
GREENFORD • MIDDX


TEL: WAXLO 44 1051 1216 Bx 10  
GRAMS: EXCURATIME, WESPHONE, LONDON



# Alphabetical Index to Advertisers

	PAGE		PAGE		PAGE
Abbey Building Supplies Co.	lxxi	Finlock Gutters, Ltd.	lxi	Orlit, Ltd.	xxxv
Accrington Brick & Tile Co., The	lxx	Foyles, Ltd.	lxxi	Osters & Fleming	l
Adamite Co., Ltd., The	lxxi	Galvo (Wire Netting), Ltd.	xxiv	Philips Electrical, Ltd.	lxi
Aidas Electric, Ltd.	xxxiv	Gas Council, The	xxiii	Phoenix Rubber Co., Ltd.	lxvi
Anderson Construction Co., Ltd.	—	Gaskell & Chambers, Ltd.	xv	Pikington Brothers, Ltd.	lv
Anglo-Scottish Construction Co., Ltd.	xix	Gaze, W. H., & Sons, Ltd.	—	Prodorite, Ltd.	xii
Architectural Press, Ltd., The	—	Gerrard, J., & Sons, Ltd.	i	Rawlplug Co., Ltd., The	xi
Armstrong Cork Co., Ltd.	ii, xliii	Gillett & Johnston, Ltd.	xxviii	Rediffusion	xiv
Austin, James, & Sons (Dewsbury), Ltd.	xxiv	Greenwood's & Airvac Ventilating Co., Ltd.	—	Reunokki, Ltd.	—
Automatic Pressings, Ltd.	lxv	G.W.B. Electric Furnaces, Ltd.	ii	Reynolds, Dreyfus, Ltd.	—
Ayres, Ltd.	—	Gyproe Products, Ltd.	xxix	Rowson, Drew & Clydesdale, Ltd.	—
Barton, Wm., & Sons, Ltd.	lxxlii	Halden, J., & Co., Ltd.	lxxiii	Rubery Owen & Co., Ltd.	—
Bath Cabinet Makers & Artcraft, Ltd.	xvi	Hall, John, & Sons (Bristol & London), Ltd.	x	Russell Furnishings, Ltd.	lxv
Baume & Co., Ltd.	lx	—	—	Sadd, John, & Sons, Ltd.	—
Bellrock Gypsum Industries, Ltd.	—	Harvey, G. A., & Co. (London), Ltd.	iii	Sanders, Wm., & Co. (Wednesbury), Ltd.	xvii
Blundell Spence & Co., Ltd.	—	Hills (West Bromwich), Ltd.	viii	Sarco Thermostats, Ltd.	lix
Booth, John, & Sons (Bolton), Ltd.	xx	Hope, Henry, & Sons, Ltd.	lii	Scaffolding (Great Britain), Ltd.	—
Boulton & Paul, Ltd.	lxxi	Hopkinson, J. N., Ltd.	lxx	Sealanco (St. Helens), Ltd.	—
Box, C. W.	lxxi	Hotpoint Electric Appliances Co., Ltd.	—	Sealcrete Products, Ltd.	xxviii
Braithwaite & Co., Engineers, Ltd.	—	Ibstock Brick & Tile Co., Ltd.	lxxii	Semtex, Ltd.	—
Briggs, Wm., & Sons, Ltd.	vii	Imperial Chemical Industries, Ltd.	xxxvii	Shanks, E. O., & Sons, Ltd.	lxiv
Britannia Engineering Co.	lxxiii	Insulite Products Corporation, Ltd.	lxv	Shaw, Philip (Contractors), Ltd.	xi
British Plaster Board, Ltd., The	xi	International Correspondence Schools	—	Simplex Electric Co., Ltd.	—
British Trolley Track Co., Ltd.	iii	Institute of Registered Architects	—	Sissons, W. & G., Ltd.	xii
Britnair Electrical Co., Ltd.	—	Johnston Bros. (Contractors), Ltd.	lxvi	Small & Parkes, Ltd.	xli
Broads Manufacturing Co., Ltd.	—	Kenyon, Wm., & Sons, Ltd.	xlii	Smith, H. V., & Co., Ltd.	lxxlii
Callow & Keppich, Ltd.	lxxi	King, J. A., & Co., Ltd.	—	Smith & Rodger, Ltd.	—
Cape Asbestos Co., Ltd.	—	Lacrinoid Products, Ltd.	xxx	Smith, Samuel, & Sons, Ltd.	—
Carron Company	lxxii	Leigh, W. & J., Ltd.	xliv	Smith's Fireproof Floors, Ltd.	—
Chance Bros., Ltd.	lviii	Limmer & Trinidad Lake Asphalt Co., Ltd.	xliv	Stafford Concrete Bldgs., Ltd.	—
Clark, James, & Eaton, Ltd.	xxxiii	—	—	Standard Patent Glazing Co., Ltd., The	—
College of Estate Management, The	lxx	Linoleum Manufacturers' Association	lxxi	Stelcon (Industrial Floors), Ltd.	lxvi
Colt Ventilation, Ltd.	—	Luxfer, Ltd.	lii	Story & Co., Ltd.	ii
Costain, Richard, Ltd.	lxix	McCarthy, M., & Sons, Ltd.	lxxi	Sunleal Board Co., Ltd.	—
Cox, Peter, & Partners, Ltd.	vi	McKechnie Bros., Ltd.	xxviii	Surrey Concrete, Ltd.	lxiv
Dawnays, Ltd.	xlii	Magnet Timber, Ltd.	xxxviii	Tarmac, Ltd.	lxiii
De La Rue, Thomas, & Co., Ltd.	lx	Malinson, W., & Sons, Ltd.	lxi	Tentest Fibre Board Co., Ltd.	—
Dignus, Ltd.	—	Mander Bros., Ltd.	v	Thermacoust, Ltd.	—
Docker Brothers	xxx	Marbath Flooring Co., Ltd., The	xxi	Thermalite, Ltd.	xxxii
Dunlop Special Products, Ltd.	xxvi	Marley Tile Co., Ltd.	—	Thorn, J. & Sons, Ltd.	lxxiii
Durasteel, Ltd.	lxxi	Marryat & Scott, Ltd.	—	Thorp, John B.	—
Duresco Products, Ltd.	lv	Mavitta Drafting Machines, Ltd.	—	Tretol, Ltd.	—
Eagle Penoil Co., Ltd.	—	Martyn, Bruce, Ltd.	xxxvi	Tucker, J. H., & Co., Ltd.	—
Eclair Doors, Ltd.	—	Metropolitan-Vickers Electrical Co., Ltd.	xlvi	Turner, Charles, & Son, Ltd.	—
Econa Modern Products, Ltd.	xlviii	Midland Woodworking Co., Ltd.	—	Val de Travers Asphalt Paving Co., Ltd.	—
Edgar, Wm., & Son, Ltd.	xxxix	Mills Scaffold Co., Ltd.	lxxiv	Walker Crosswell & Co., Ltd.	—
Elgood, E. J., Ltd.	lxvi	M.K. Electric, Ltd.	—	Ward, Thomas W., Ltd.	—
Ellis School of Architecture, The	lxxi	Morris Singer Co., Ltd.	xiv	Wardle Engineering Co., Ltd.	—
English Joinery Manufacturers' Association (Inc.)	lxix	National Federation of Clay Industries	xxvii	Wareite, Ltd.	lvi
Ewart & Son, Ltd.	—	Neuchatel Asphalt Co., Ltd., The	—	Wellington Tube Works, Ltd.	lvi
Expandite, Ltd.	lvii	Negus, W. & M., Ltd.	lxvi	West, A., & Partners, Ltd.	lxiv
Ferodo, Ltd.	xli	New Day Electrical Accessories, Ltd.	—	Williams, John, & Sons (Cardiff), Ltd.	lxvii
Fibreglass, Ltd.	—	North British Chemical Co., Ltd.	lix	Williams & Williams, Ltd.	—
				Zinc Alloy Rust Proofing Co., Ltd.	—

For Appointments (Wanted or Vacant), Competitions Open, Drawings, Tracings, etc., Educational, Legal Notices, Miscellaneous Property, Land and Sales, see lxxvii, lxxviii, lxxix, lxx, lxxi.



Icknield County Secondary  
Modern School

*faced with*

**Ibstock**

BUFF-MULTI RUSTICS

F. Oliver, A.M.I.C.E., A.M.I.S.E., M.Inst.M.E.  
Borough Engineer and Surveyor, Luton Borough Council.

The Ibstock Buff-Multi rustic facings used for this fine school are natural light-tone bricks. The colours, produced by burning only, vary from brown to light buff.

Ibstock Brick & Tile Co. Ltd., near Leicester. 'Phone: 391  
London:  
L.M.S. Goods Depot, Wrights Lane, Kensington, W.8 'Phone: Western 1281

PAGE  
XXXV  
1

lxvi  
iv  
xii  
xl  
xiv

lxv

xvii  
lix

xviii

lxiv  
xl

xii  
xlvi

lxxiii

lxxvi

ii

lxiv  
lxiii

xxxii  
lxxiii

lvi  
lvi  
lxiv  
xlvi


“  
I  
”



V  
II  
Tel



# "KONGRIP" COMPRESSION FITTINGS




For use with light gauge copper tubes in hot and cold supplies, low pressure steam and exhaust leads. Makes a secure joint, unaffected by extremes of temperature, wide variations of pressure or vibration. The extended sleeve gives necessary support to the pipe and when the joint is assembled there is no obstruction to free flow. They are simple to install and as simply taken apart for alterations or extensions.

Catalogue on request


**W. BARTON & SONS, LTD.**  
11 FORREST ROAD, EDINBURGH 1,

Telephone: 31891

Telegrams: Sterilize



## The building you need . . .



is very likely one of Thorns standard range of industrial buildings, which includes new steel structures for factories, stores, garages; timber and asbestos buildings for offices, canteens, halls, etc., and reconditioned Nissen type huts and 'Blister' hangars.

★ Write today, stating details of your requirements and requesting prices of suitable buildings.



**THORNS**

J. THORN & SONS, LTD.

BOX 185, BRAMPTON RD., BEXLEYHEATH, KENT. Bexleyheath 305



## What do YOU look for in paint?

Durability? Protection? You'll find all these and covering power too in Smith & Rodger Paints and Varnishes. Constant research and care in processing keeps these high-grade products well to the fore in the decorating world.

VITAGLOSS HIGH GLOSS PAINT AND FINE WHITE ENAMEL • WALDURA WASHABLE WATER PAINT • SOLVIT PAINT REMOVER • VITACHARM FLAT PAINT

**SMITH & RODGER LTD**  
ELLIOT STREET • GLASGOW, C.3  
Phone: CITY 6341/2 Grams: "SMITROD" GLASGOW

**SMITH & RODGER**  
PAINTS • VARNISHES





***You can get  
everything  
you need-as  
well as the  
scaffolding-***



***from***

**MILLS**



**TELEPHONE YOUR NEAREST DEPOT**

BELFAST • BIRMINGHAM • BOURNEMOUTH • BRADFORD • BRIGHTON • BRISTOL  
CANTERBURY • CARDIFF • COVENTRY • CROYDON • DUBLIN • GLASGOW • HULL  
ILFORD • LIVERPOOL • LOWESTOFT • MANCHESTER • NEWCASTLE • NORWICH  
PLYMOUTH • PORTSMOUTH • READING • SOUTHAMPTON • SWANSEA • YARMOUTH

MILLS SCAFFOLD CO. LTD., Head Office: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6 RIVERSIDE 5026/9

